

CITY OF ANN ARBOR COMMUNITY SERVICES AREA LESLIE PARK GOLF COURSE GOLF CART STORAGE BUILDING - BID SET

PERMITS REQUIRED TO BE OBTAINED BY THE CONTRACTOR PRIOR TO THE BEGINNING OF CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR THESE PERMIT FEES. PERMIT **ISSUING AUTHORITY GRADING/SOIL EROSION &** CITY OF ANN ARBOR PLANNING AND DEVELOPMENT **SERVICES UNIT** CITY OF ANN ARBOR PLANNING AND DEVELOPMENT **BUILDING PERMIT SERVICES UNIT** CITY OF ANN ARBOR **ELECTRICAL PERMIT** PLANNING AND DEVELOPMENT **SERVICES UNIT** CITY OF ANN ARBOR PLANNING AND DEVELOPMENT PLUMBING PERMIT **SERVICES UNIT**

	UTILITIES ARE LOCATED IN O	R NEAR THE
PUBLIC UTILITIES	OWNER	CONTACT
WATER SEWER STORM SIGNS SIGNALS STREET LIGHTS	CITY OF ANN ARBOR COMMUNITY SERVICES AREA LARCOM CITY HALL 301 E. HURON ST. ANN ARBOR, MI 48104	DAN WOODEN (734) 794-6350 MARK COZART (734) 794-6350 MATT WALDSMITH (734) 794-6350
omeer claims		CHUCK FOJTIK (734) 794-6350
PRIVATE UTILITIES	OWNER	CONTACT
GAS	DTE ENERGY 17150 ALLEN ROAD MELVINDALE, MI 48122	JAY WILLIAMS (313) 380-7303
ELECTRIC	DTE ENERGY WESTERN WAYNE SERVICE CENTER 8001 HAGGERTY ROAD BELLEVILLE, MI 48111	CLAY COMBEE (734) 397-4112
CABLE	COMCAST 27800 FRANLKIN ROAD SOUTHFIELD, MI 48034	RON SUTHERLAND (313) 999-8300
PHONE	AT&T 550 S. MAPLE ROAD ANN ARBOR, MI 48103	BRIAN BERRY (734) 996-2135
PHONE	MCI 2800 N. GLENFILLE ROAD RICHARDSON, TX 75082	DEAN BOYERS (972) 729-6016

APRIL 2016 CITY ITB No. 4446 STANTEC FILE No. 2075135200 TASK 202





VICINITY MAP


THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO THE 1994 EDITION OF THE CITY OF ANN ARBOR PUBLIC SERVICES DEPARTMENT STANDARD SPECIFICATIONS AND IT'S DETAILS WHICH ARE INCLUDED BY REFERENCE.

THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THIS REQUIREMENT. THE WORK SHALL BE PERFORMED IN COMPLETE CONFORMANCE WITH THE CURRENT PUBLIC SERVICES STANDARD SPECIFICATIONS AND DETAILS.

FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 53, THE CONTRACTOR SHALL CALL 811 OR 1-800-482-7171 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.

		SIILLI INDLX
SHEET	DRAWING No.	TITLE
1	G-001	COVER SHEET
2	C-001	CIVIL GENERAL NOTES AND LEGEND
3	C-101	CIVIL EXISTING CONDITIONS AND DEMOLITION PLAN
4	C-102	CIVIL SITE PLAN
5	C-103	BID ALT #1 - WATER AND SANITARY SERVICE EXTENSION
6	C-501	CIVIL DETAILS
7	A-101	ARCHITECTURAL FRAMING PLAN, ROOF PLAN AND NOTES
8	A-201	ARCHITECTURAL EXTERIOR ELEVATIONS AND BUILDING SECTIONS
9	A-301	BID ALT #2 - ARCHITECTURAL EXTERIOR ELEVATIONS AND BUILDING SECTIONS
10	S-101	STRUCTURAL PLAN
11	S-201	BID ALT #1 - STRUCTURAL PLAN
12	M-101	BID ALT #1 - MECHANICAL PLAN
13	M-201	BID ALT #1 - MECHANICAL PLAN AND SECTION
14	E-001	ELECTRICAL SYMBOLS, ABBREVIATIONS AND NOTES
15	E-101	ELECTRICAL PLAN
16	E-102	ELECTRICAL WIRING DIAGRAMS AND SCHEDULES

SHFFT INDEX



PREPARED BY:



Stantec Consulting Michigan Inc. 3754 Ranchero Drive Ann Arbor MI U.S.A. 48108-2771 Tel. 734.761.1010 Fax. 734.761.1200 www.stantec.com



KEN JEWISON, P.E., - MI LICENSE No. 47438 STANTEC, PROJECT MANAGER 04/28/2016

PREPARED UNDER THE SUPERVISION OF

DATE

SHEET No.

CITY DEPARTMENTAL REVIEW REVIEW C.E.S. STORM WATER SOIL EROSION **ENGINEER OPERATIONS SUPERVISOR**

2075135200 - G-00

EXISTING	EXISTING	EXISTING			
WATER SYMBOLS	MISC. SYMBOLS	UTILITY LINETYPES			
+ + FIRE HYDRANT GATE VALVE IN	? UNKNOWN MANHOLE	WATER MAIN			
BOX GATE VALVE IN WELL	P TELEPHONE MANHOLE	s — s STORM SEWER SANITARY SEWER			
W STOP BOX	T TELEPHONE RISER	g — GAS MAIN			
■ WATER VAULT WELL	G GAS VALVE	MISC. LINETYPES ———————————————————————————————————			
STORM SYMBOLS	GAS VENT	BUILDING CENTERLINE OF DIT			
CATCH BASIN (SQ) CATCH BASIN (RD)	GAS BOX	CENTERLINE OF RO			
(RD) (RD) STORM MANHOLE	E ELECTRICAL RISER				
NON-CURB CATCH BASIN (SQ)	TRANSFORMER	R.O.W. TREELINE WETLAND			
SANITARY SYMBOLS S SANITARY MANHOLE	UTILITY POLE	HATCHING			
CO CLEAN-OUT	LAMP POLE	ASPHALT			
VEGETATION SYMBOLS	GUY ANCHOR	BUILDING			
TREE (DECIDUOUS)	GUY POLE	GRAVEL			
TREE (CONIFEROUS)	MW) MONITORING WELL	WETLAND			
	MAIL MAILBOX				
STUMP SHRUB (DECIDUOUS)	SOIL BORING				
TRAFFIC SYMBOLS	SURVEY SYMBOLS				
PEDESTRIAN SIGNAL	TRAVERSE POINT				
SIGN	BENCH MARK				
HAND HOLE ORNAMENTAL LIGHT	IRON PIPE				
FLOOD LIGHT	O MON BOX				

WATER SYMBOLS INTERPORANT (PROPILE) WATER MAIN WATER MAIN WATER MAIN WATER MAIN STORM SEWER SANITARY SEWER WATER STOP BOX WATER STOP BOX WATER STOP BOX WATER VAULT STORM SYMBOLS FENCE INLET INLET DOUBLE INLET INLET INLET DOUBLE INLET	PR	OPOSED	PROPOSED
HYDRANT (PLAN) WATER GATE WELL WATER GATE WELL WATER STOP BOX WATER STOP BOX WATER VAULT STORM SYMBOLS FENCE WILDING CENTERLINE OF DOTCH CENTERLINE OF ROAD CENTERLINE OF ROAD COLUMN CURB CURB CURB ROUND CATCH BASIN ROUND CATCH BASIN ROUND CATCH BASIN FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) WATER EXSMENT WATER SAMITARY MANHOLE CONCRETE SANITARY SIDEWALK WEGETATION SYMBOLS TREE (CONIFEROUS) TREE (CONIFEROUS) BARREL BARREL	WATER	SYMBOLS	UTILITY LINETYPES
WATER GATE WELL WATER GATE WELL WATER STOP BOX WATER STOP BOX WATER STOP BOX WATER STOP BOX BUILDING BUILDING WATER CAULT CENTERLINE OF DOTCH CENTERLINE OF ROAD FENCE INLET DOUBLE INLET DOUBLE INLET PHASE LINE LOT/JUNIT PHASE LINE CURB ROUND CATCH BASIN ROUND CATCH BASIN FLARED END SECTION (PLAN) FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) WATER SAMITARY SYMBOLS SANITARY SYMBOLS SANITARY SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL	10 3111		
WATER SATE VALVE WATER STOP BOX WATER STOP BOX WATER VAULT CENTERLINE OF DITCH STORM SYMBOLS FENCE INLET DOUBLE INLET NALET NALET NALET NALET NALET NALET PHASE LINE CURB REMENT TEMPORARY GRADING PERMIT WATER EASMENT WATER EASMENT FLARED END SECTION (PLAN) FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY WANHOLE CURB REMOVAL VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL	7/68/8/7		—— —— STORM SEWER
WATER STOP BOX WATER VAULT BUILDING WATER VAULT CENTERLINE OF DITCH CENTERLINE OF DITCH CENTERLINE OF ROAD CENTERLINE OF DITCH SILT FENCE LOTUNIT INLET I			SANITARY SEWER
WATER VAULT CENTERLINE OF DITCH STORM SYMBOLS FENCE INLET DOUBLE INLET INLET INLET DOUBLE INLET JUNCTION CHAMBER ROUND CATCH BASIN ROUND CATCH BASIN FERMIT PHASE LINE URB STORM MANHOLE DRAIN ARROW FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS S SANITARY MANHOLE CLEAN-OUT VEGETATION SYMBOLS TREE (CONIFEROUS) BARREL BARREL BARREL CENTERLINE OF DITCH CENTERLINE OF ROAD ASIL FENCE LOTAUNIT PHASE LINE STORM EASEMENT SANITARY EASEMENT RO.W. FLARED END SECTION (PROFILE) TREMPORARY GRADING PERMIT PHASE LINE LOTAUNIT PHASE LINE LOTAUNIT PHASE LINE CURB STORM EASEMENT SOLUTION SANITARY EASEMENT CONCRETE SIDEWALK PAVEMENT/WALK REMOVAL TREE (CONIFEROUS) TREE (CONIFEROUS) BARREL	WA	TER GATE VALVE	MISC. LINETYPES
STORM SYMBOLS STORM SYMBOLS FENCE INLET DOUBLE INLET NUET NUET DOUBLE INLET NUET NUET NUET PHASE LINE CURB ROUND CATCH BASIN ROUND CHAMBER THAPPORARY GRADING PERMIT PHASE LINE NATER EASMENT STORM EASEMENT ROWN HATCHING SANITARY EASEMENT ROWN FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CONCRETE SIDEWALK VEGETATION SYMBOLS TREE (CONIFEROUS) TREE (CONIFEROUS) BARREL BARREL	W WAT	ER STOP BOX	BUILDING
STORM SYMBOLS INLET INLET DOUBLE INLET JUNCTION CHAMBER ROUND CATCH BASIN RAPPORTARY GRADING PERMIT WATER EASMENT SANITARY EASEMENT ROUND ROUN	W WAT	ER VAULT	CENTERLINE OF DITC
INLET DOUBLE INLET JUNCTION CHAMBER ROUND CATCH BASIN ROUND CHAMBER WATER EASMENT SANITARY EASEMENT ROUND HATCHING SANITARY SYMBOLS SANITARY MANHOLE COCCRETE SIDEWALK VEGETATION SYMBOLS TREE (DECIDIOUS) TREE (CONIFEROUS) TREE (CONIFEROUS) BARREL	STORM S	SYMBOLS	—-— CENTERLINE OF ROAI
DOUBLE INLET INLET JUNCTION CHAMBER ROUND CATCH BASIN RATCHING SANITARY SYMBOLS ROUND CATCH BASIN ROUN	<u> </u>		
INLET JUNCTION CHAMBER ROUND CATCH BASIN ROUND C		INLET	SILT FENCE
INLET JUNCTION CHAMBER ROUND CATCH BASIN PERMIT WATER EASMENT WATER EASMENT SANITARY EASEMENT ROW. HATCHING SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TREE (CONIFEROUS) BARREL PHASE LINE CURB PHASE LINE CORB PERMIT CORB PERMIT CONCRETE SANITARY EASEMENT CONCRETE SIDEWALK PAVEMENT/WALK REMOVAL TREE (CONIFEROUS) TREE (CONIFEROUS) BARREL			LOT/UNIT
CHAMBER ROUND CATCH BASIN PERMIT WATER EASMENT WATER EASMENT STORM EASEMENT FLARED END SECTION (PLAN) FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CONCRETE SIDEWALK VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TREE (CONIFEROUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS	(INLEI	PHASE LINE
PERMIT WATER EASMENT WATER EASMENT WATER EASMENT STORM EASEMENT FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CONCRETE CONCRETE SIDEWALK VEGETATION SYMBOLS TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL PERMIT WATER EASMENT WATER EASMENT CONCRETE CONCRETE SIDEWALK TREE (CONIFEROUS) TRAFFIC SYMBOLS			CURB
BY STORM MANHOLE DRAIN ARROW FLARED END SECTION (PLAN) FLARED END SECTION (PROFILE) FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL STORM EASEMENT		ROUND CATCH BASIN	
DRAIN ARROW FLARED END SECTION (PLAN) FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL STORM EASEMENT SANITARY SANITARY EASEMENT CONCRETE CONCRETE SIDEWALK PAVEMENT/WALK REMOVAL	R		WATER EASMENT
FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL R.O.W. R.O.W. R.O.W. R.O.W. RATCHING HATCHING ASPHALT CONCRETE SIDEWALK PAVEMENT/WALK REMOVAL	→		STORM EASEMENT
FLARED END SECTION (PROFILE) HATCHING SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL BOOK			SANITARY EASEMENT
HATCHING SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT SIDEWALK VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL SIDEWALK CURB REMOVAL TREE (CONIFEROUS)		(PLAN)	
SANITARY SYMBOLS SANITARY MANHOLE CO CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL CONCRETE CONCRET			
S SANITARY MANHOLE C CLEAN-OUT VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL ASPHALT CONCRETE SIDEWALK GRAVEL TREE (CONIFEROUS) TRAFFIC SYMBOLS			HATCHING
MANHOLE CLEAN-OUT SIDEWALK VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL CONCRETE SIDEWALK GRAVEL PAVEMENT/WALK REMOVAL			ASPHALT
VEGETATION SYMBOLS TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL SIDEWALK GRAVEL PAVEMENT/WALK REMOVAL TRAFFIC SYMBOLS			CONCRETE
TREE (DECIDUOUS) TREE (CONIFEROUS) TRAFFIC SYMBOLS BARREL SIGN	(co)	CLEAN-OUT	SIDEWALK
TRAFFIC SYMBOLS BARREL BARREL	VEGETAT	TION SYMBOLS	GRAVEL
TRAFFIC SYMBOLS BARREL BARREL	•	TREE (DECIDUOUS)	PAVEMENT/WALK REMOVA
BARREL		TREE (CONIFEROUS)	·/·/·/·/·/·/·/·/·/· CURB REMOVAL
. CICN	TRAFFIC	CSYMBOLS	
. SIGN		BARREL	
1		SIGN	

PUSH BUTTON

WARNING

SOIL EROSION CONTROL NOTES:

GENERAL:

- 1. THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN THE SOIL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AT ALL TIMES DURING CONSTRUCTION ON THIS PROJECT. ANY MODIFICATIONS OR ADDITIONS TO THE SOIL EROSION CONTROL MEASURES DUE TO CONSTRUCTION OR CHANGED CONDITIONS SHALL BE COMPLIED WITH AS REQUIRED OR DIRECTED BY THE OWNER, PROJECT ENGINEER, OR THE CITY OF ANN ARBOR. THE CONTRACTOR IS REQUIRED TO OBTAIN A SOIL EROSION CONTROL PERMIT ANYTIME THE DISTURBED AREA EXCEEDS 1 ACRE.
- 2. ALL SOIL EROSION AND SEDIMENTATION CONTROL WORK SHALL CONFORM TO THE PERMIT REQUIREMENTS OF THE CITY OF ANN ARBOR, CHAPTER 63, AND THE LAWS OF THE STATE OF MICHIGAN.
- 3. DAILY OR AFTER STORM EVENTS INSPECTIONS SHALL BE MADE BY THE CONTRACTOR. PERIODIC INSPECTIONS MAY BE MADE BY THE OWNER/PROJECT ENGINEER TO DETERMINE THE EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES. ANY NECESSARY CORRECTIONS SHALL BE MADE WITHOUT DELAY AND WITHOUT ADDITIONAL COST TO THE OWNER.
- 4. EROSION AND SEDIMENTATION FROM WORK ON THE SITE SHALL BE CONTAINED ON THE SITE AND NOT BE ALLOWED TO COLLECT ON ANY OFF-SITE AREAS OR WATERWAYS.
- ALL MUD/DIRT TRACKED ONTO ROADS FROM THE SITE DUE TO CONSTRUCTION, SHALL BE PROPERTY REMOVED BY THE CONTRACTOR. IF SO ORDERED, THE CONTRACTOR SHALL EMPLOY A MECHANICAL STREET SWEEPER AT NO ADDITIONAL COST TO THE OWNER.
- 6. RESTORATION OF ALL DISTURBED AREAS, INCLUDING PLACEMENT OF TOPSOIL, SEED, FERTILIZER AND MULCH AND/OR SOD SHALL BE DONE WITHIN 5 DAYS OF THE COMPLETION OF FINAL GRADE.
- CONSTRUCTION OPERATIONS SHALL BE SCHEDULED AND PERFORMED SO THAT PREVENTATIVE SOIL EROSION CONTROL MEASURES ARE IN PLACE PRIOR TO EXCAVATION IN CRITICAL AREAS AND TEMPORARY STABILIZATION MEASURES ARE IN PLACE IMMEDIATELY FOLLOWING BACKFILLING OPERATIONS.
- 8. SPECIAL PRECAUTIONS WILL BE TAKEN IN USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION.
- PROPER DUST CONTROL SHALL BE MAINTAINED DURING CONSTRUCTION BY USE OF WATER TRUCKS AND/OR CHLORIDE AS REQUIRED OR AS DIRECTED BY ENGINEER.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY SOIL EROSION CONTROL MEASURES AND REMOVAL OF SOME UPON AUTHORIZED COMPLETION OF THE PROJECT. COMPLETION OF PROJECT WILL NOT BE AUTHORIZED UNTIL ALL SITE WORK AND UTILITY CONSTRUCTION IS COMPLETE AND ALL SOILS ARE STABILIZED.
- 11. THE CONTRACTOR SHALL NOT GRADE INTO ADJACENT PROPERTIES. SILT FENCE SHALL BE INSTALLED AND MAINTAINED TO PREVENT GRADING, EROSION AND SEDIMENTATION INTO THEM.
- 12. TREE PROTECTION FENCING MUST REMAIN INTACT UNTIL RESTORATION OF THE SITE IS COMPLETE.
- 13. CONTRACTOR SHALL EXERCISE CAUTION WHILE WORKING IN THE VICINITY OF THE PROPOSED STORM SEWER OUTLET SO AS TO AVOID CAUSING DAMAGE TO THE ADJACENT WETLAND AND POND AREA. ANY DAMAGE TO THE WETLAND OR POND SHALL BE RESTORED TO A CONDITION EQUAL OR BETTER THAN THE PRE-CONSTRUCTION CONDITION AT NO COST TO THE OWNER.

SEQUENCE OF EROSION CONTROL:

- 1. INSTALL SILT FENCE, TREE PROTECTION FENCING AND INLET FILTERS ON EXISTING STORM INLETS PRIOR TO ANY CLEARING OR EARTH MOVING OPERATION.
- 2. CONTRACTOR TO CONTINUALLY MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES, AS REQUIRED TO ALLOW DRAINAGE AND SEDIMENT REMOVAL. REMOVE ANY ACCUMULATED SEDIMENT.
- 3. STRIP AND CLEAR MAINTAIN EROSION CONTROL MEASURES AROUND TEMPORARY STOCK PILES.
- 4. ROUGH GRADE.
- 5. ENSURE ALL SOIL IS STABILIZED. REMOVE ALL TEMPORARY SOIL EROSION CONTROL

TEMPORARY SEEDING:

MEASURES.

- 1. SEED IN ACCORDANCE WITH PROJECT DRAWINGS AND SPECIFICATIONS.
- 2. ANY DISTURBED AREA NOT PAVED, SEEDED, MULCHED, SODDED OR BUILT UPON BY NOVEMBER 15TH OR JUNE 30TH IS TO BE TEMPORARILY STABILIZED PER SPECIFICATIONS.

ROAD.

- 1. DURING CONSTRUCTION, ALL ROADS SHALL BE PROTECTED FROM UNVEGETATED AREAS WASHING ONTO ROAD SURFACE BY PLACEMENT OF SILT FENCE BEHIND CURB OR A 10 FOOT WIDE STRAW MULCH BLANKET BEHIND CURB OR OTHER APPROVED METHOD AND/OR AS SHOWN ON THE PLANS.
- 2. DURING CONSTRUCTION OF ANY PORTION OF THE PROJECT, ADJOINING ROADS SHALL BE MAINTAINED FREE OF DIRT, SILT AND CONSTRUCTION DEBRIS. CONTRACTOR REQUIRED TO USE VACUUM SWEEPER EQUIPMENT FOR CLEANING CONSTRUCTION SITE AND ADJOINING ROADS. THE USE OF BROOM SWEEPER IS NOT PERMITTED.

CATCH BASIN/MANHOLE PROTECTION:

PROTECT STORM SEWER CATCH BASINS WITH APPROVED INLET FILTERS.

TRAFFIC CONTROL NOTES:

- 1. THE CONTRACTOR SHALL GIVE ADVANCE NOTICE OF CONSTRUCTION TO THE CITY OF ANN ARBOR AT LEAST SEVEN (7) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- THE CONTRACTOR SHALL FURNISH, INSTALL AND MAINTAIN ALL NECESSARY TRAFFIC CONTROLS AND PROTECTION DURING THE ENTIRE PERIOD OF CONSTRUCTION IN ACCORDANCE WITH THE LATEST REVISION OF THE "MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" AND ANY SUPPLEMENTAL SPECIFICATIONS SET FORTH HEREIN.
- 3. ALL TRAFFIC CONTROL DEVICES INCLUDING SIGNS, BARRICADES, PLASTIC DRUMS, AND WARNING LIGHTS ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- 4. THE CONTRACTOR SHALL RESTORE THE RIGHT-OF-WAY TO A CONDITION EQUAL TO OR BETTER THAN THE ORIGINAL CONDITION.
- 5. CONSTRUCTION EQUIPMENT AND EXCAVATING MATERIAL SHALL NOT BE STOCK PILED IN SUCH LOCATIONS THAT IT CREATES A TRAFFIC HAZARD OR INTERFERES WITH THE FLOW OF TRAFFIC.
- 6. THE CONTRACTOR SHALL PROTECT ALL EXISTING ROAD SIDE DRAINAGE DITCHES, DRAINS, CULVERTS AND DRAINAGE STRUCTURES DURING CONSTRUCTION. ANY ROADWAY DRAINAGE FACILITIES DAMAGED BY THE CONTRACTOR SHALL BE RESTORED TO THEIR ORIGINAL CONDITION INCLUDING GRADE, WIDTH, SIDE SLOPES, PIPE MATERIAL, ETC.
- 7. CONTRACTOR SHALL MAINTAIN ACCESS ACROSS COMMERCIAL DRIVEWAYS AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL PLACE MAINTENANCE AGGREGATES AND/OR TEMPORARY BITUMINOUS PATCHING MIXTURE AS NECESSARY. THIS WORK IS INCIDENTAL TO CONSTRUCTION.
- 8. THE CONTRACTOR SHALL PROVIDE ACCESS FOR EMERGENCY VEHICLES (POLICE, FIRE, AMBULANCE, ETC.). MAIL CARRIERS AND SCHOOL BUSES TO PASS THROUGH WORK AREAS AT ALL TIMES. ANY COMPLETED WORK THAT IS DAMAGED BY SUCH VEHICLES SHALL BE REPAIRED OR REMOVED AND REPLACED BY THE CONTRACTOR AT NO EXTRA COST TO THE OWNER.
- 9. TRAFFIC CONTROL AT THE MUD TRACKING MAT SHALL BE INSTALLED PER MMUTCD AND CITY OF ANN ARBOR STANDARDS. COST SHALL BE INCIDENTAL.

GENERAL CONSTRUCTION NOTES (ALL SHEETS):

- 1. TAKE ALL PRECAUTIONS TO SUPPORT EXISTING UTILITY POLES. COORDINATE WITH APPROPRIATE UTILITY COMPANIES TO MINIMIZE SCHEDULE DELAY.
- 2. COMPLETE ALL WORK IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL CODES, RULES AND REGULATIONS. OBTAIN ALL NECESSARY LOCAL, STATE AND FEDERAL PERMITS AND PAY PERMIT FEES FOR THE WORK OR CONFIRM THAT THE REQUIRED PERMITS HAVE BEEN OBTAINED BY OTHERS PRIOR TO COMMENCING CONSTRUCTION.
- 3. ALL ITEMS INCIDENTAL TO AND/OR REQUIRED TO COMPLETE THE INSTALLATION SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR.
- 4. RESTORE ALL DISTURBED AREAS NOT RECEIVING RIPRAP WITH 4-INCHES OF TOPSOIL AND MULCH BLANKET.
- 5. RESTORE ALL STREET SURFACES, DRIVEWAYS, STAGING AREAS, CULVERTS, ROADSIDE DRAINAGE DITCHES AND OTHER PUBLIC OR PRIVATE STRUCTURES THAT ARE DISTURBED OR DAMAGED AS A RESULT OF CONSTRUCTION ACTIVITIES TO A CONDITION EQUAL OR BETTER THAN EXISTING CONDITIONS.
- 6. ALL REMOVED MATERIALS ARE THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE NOTED IN THE DRAWINGS. CLEANUP AND DISPOSE OF ALL EXCESS MATERIALS OFF SITE IN ACCORDANCE WITH LOCAL REGULATIONS.
- 7. PROTECT TREES AND SHRUBS FROM DAMAGE DURING CONSTRUCTION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- 8. PROTECT EXISTING SITE IMPROVEMENTS AND LANDSCAPING FROM DAMAGE.
 RESTORE/REPLACE ALL DAMAGED IMPROVEMENTS AND LANDSCAPING TO THEIR ORIGINAL CONDITION.
- 9. CONTRACTOR SHALL BE RESPONSIBLE FOR BYPASSING ALL STORMWATER FLOW DURING CONSTRUCTION.

BID SET

ADVANA REVIEW SET

DESCRIPTION

DESCRIPTION

ADVANA CHECKED

Stantec Consulting Michigan Inc. 3754 Research Park Drive Ann Arbor MI U.S.A. 48108-2216 Tel. 734.761.1200 Fax. 734.761.1200 www.stantec.com




LIE PARK GOLF COURSE
CART STORAGE BUILDING
GENERAL NOTES AND LEGEND


CESLIE PARK
GOLF CART STC


NONE
No.
75135200 C-001


2 OF 16


NOT ALL SYMBOLS ARE USED
























MECHANICAL NOTES:

1. THE FUTURE FLOOR DRAIN SYSTEM IS NOT TO BE FULLY CONSTRUCTED. IT HAS BEEN DESIGNED FOR FUTURE IMPROVEMENTS TO THE BUILDING. THE LINE IS TO BE CAPPED AT THE WYE OR ELBOW AND MARKED WITH METAL INDICATOR TAPE.

2. THE FUTURE WASH STATION DRAIN SYSTEM IS NOT TO BE FULLY CONSTRUCTED . IT HAS BEEN DESIGNED FOR FUTURE IMPROVEMENTS TO THE BUILDING. THE LINE IS TO BE CAPPED AT THE WYE AND MARKED WITH METAL INDICATOR TAPE.

3. IT IS THE INTENT OF THE DESIGN THAT THE BUILDING WATER LINES AND SANITARY LINES WILL BE DRAINED AND WINTERIZED DURING THE OFF SEASON.

4. IT IS THE OWNERS INTENT TO INSTALL A 6" CONCRETE FLOOR IN THE FUTURE.



PREPARED BY:

COMMUNITY SERVICES AREA - CITY OF ANN ARBOR

LESLIE PARK GOLF COURSE

GOLF CART STORAGE BUILDING



MODEL 15W (15WK)

KEY NO. PART NO. DESCRIPTION

E.L. MUSTEE & SONS, INC.

Cleaning Note:

Most stains that you may acquire in your Model 15W Laundry Tray may be removed with common household cleanser or liquid cleaner. Stubborn stains may be removed with a bleach solution — follow bleach manufacturer's recommended procedures pertaining to safety, handling and use of their product.

Single Compartment Laundry Tray
Molded Side Filler – Left Hand
Molded Side Filler – Right Hand
Wall Plate
Lag Screw, 5/16" x 2" (4 Required)
Anchor, Plastic, 5/16" (4 Required)
Drive Rivet – 1/4" Dia. x 3/4" Lg. (4 Required)
Stopper – 1-1/2" Diameter
5/16" Flat Washer (2 Required)
1-1/2" Tailplece Washer (Not Shown)
1-1/2" Thrd. Slip Nut (Not Shown)

'NOTE: FOR REPLACEMENT HARDWARE, ORDER COMPLETE PARTS PACKAGE PART NO. 19.601 PACKAGES WILL NOT BE SPLIT FOR INDIVIDUAL PARTS.


Any type of transfer or sump pump must be supported by the floor or wall plus appropriate bracing for the waste lines. DO NOT RELY SOLELY ON THE 1/2" MOLDED DRAIN CONNECTION.

SI-140 (05•06)


IAPMO₄ LISTED FILE NO. 0636

PARTS ILLUSTRATION





1 INCH MIN



WALL SLEEVE DETAIL

MECHANICAL NOTES

(300) EJECTOR PUMP SYSTEM, 24"x36" WITH 24" RISER

(301) PROPOSED SINK

(302) PROPOSED HOSE BIB

(304) 1" PVC BALL VALVE

(305) 1" PVC BALL VALVE W/ MALE AIR HOSE ADAPTOR

(306) 1" SCH 80 PVC WATER SUPPLY LINE, I.E.= 849.00

(307) 2" SCH 80 PVC SANITARY FORCEMAIN, I.E.= 852.00

(308) 2" SCH 80 PVC SANITARY VENT LINE THROUGH ROOF SUPPORT AS NEEDED


(309) WALL SLEEVE WITH LINK SEAL, SEE DETAIL


(310) FUTURE FLOOR DRAIN


(311) 4" SCH 80 PVC, I.E.= 852.50

(312) CAP FUTURE WASH LINE STATION DRAIN LINE AT WYE WITH PVC CAP AND MARK WITH METAL INDICATOR TAPE

(313) I.E.= 852.00










13 of 16

PREPARED BY:



PREPARED BY: Stantec Consulti 3754 Research F Ann Arbor MI U. 48108-2216 Tel. 734.761.1 Fax. 734.761.1 Y OF ANN ARBOR ARK GOLF COURSE STORAGE BUILDING LIE PAR SERVICES AREA -COMMUNITY SHEET No. 14 of 16





SCHEMATIC WIRING DIAGRAM FOR VENTILATION CONTROL PANEL (VCP)

		BANEL COLLEGE E LA															
PANEL: A	AMPERE RATING	PANEL SCHEDULE 'A'	NOU	NITING CUREAGE	DANIEL			ANEL SCHEDU		MOUR	ITINO. GUIDEAGE	D. 151	AMPE		NEL SCHED		MOUNTING
	AMPERE RATING: BUS MATERIAL:	225 COPPER		INTING: SURFACE LOSURE: NEMA 1	PANEL: VOLTS:		AMPERE RATING: BUS MATERIAL:	COPPER		MOUN	ITING: SURFACE OSURE: NEMA 1	PANEL: C VOLTS: 240 120		RE RATING: MATERIAL:	22 COPPER		MOUNTING: SURFACE ENCLOSURE: NEMA 1
	MAIN DEVICE:	200A MCB		AKERS: PLUG-IN	PHASE:		MAIN DEVICE:	200A MCB		BREA		PHASE: 3		DEVICE:	200A MCB		BREAKERS: PLUG-IN
	SHORT CIRCUIT RATING:				WRE:		SHORT CIRCUIT RATING:	10kAIC				WRE: 4		T CIRCUIT RATING:	10kAIC		
LOAD DESCRIPTION CON.	WIRE BKR * #	PHASE LOAD-KVA	BKR WIRE COM	N. LOAD DESCRIPTION		LOAD DESCRIPTION CON.	WIRE BKR * #	PHASE LOAD-KV	/A	WIRE CON	LOAD DESCRIPTION	LOAD DESCRIPTION	CON. WIRE	BKR * #	PHASE LOAD-K	VA BKR WIRE	CON. LOAD DESCRIPTION
SIZE	SIZE	A B c		E ESTE BESSAII TIST				В	/A c # *	SIZE SIZE	EG/E BEGGNI HON	LOAD DESCRIPTION	SIZE SIZE	A	В	c # * BKK SIZE	SIZE EOAD DESCRIPTION
X Charger 1A	12 20 N 1	3120	N 2 20 12	X Charger 2A	X Charger 1B		12 20 1 3120	20		20 12	X Charger 2B	East Lights		20 N 1 2040		N 2 20 12	Center Lights
Y Charger 3A	12 20 13	3120	N 4 20 12	Y Charger 4A	Y Charger 3B		12 20 N 3	3120	N 4	20 12	Y Charger 4B	West Lights	12	20 N 3	1600	N 4 20 12	Storage Lights
Z Charger 5A	12 20 8	3120	М 6 20 12	Z Charger 6A	Z Charger 5B		12 20 N 5		3120 ^M ⁶	20 12	Z Charger 6B	Exterior Lights	12	20 N 5		450 M 6 20 12	Emergency Lights SE
X Charger 7A	12 20 17	3120	м 8 20 12	X Charger 8A	X Charger 7B		12 20 N 7 3120	20	M 8	20 12	X Charger 8B	Emergency Light SW	12	20 N 7 350		м 8 20 12	Emergency Lights NE
Y Charger 9A	12 20 N 9	3120	M 10 20 12	Y Charger 10A	Y Charger 9B		12 20 N 9	3120	M 10	20 12	Y Charger 10B	Emergency Light NW	12	20 N 9	1320 350	M 10 20 12	Recept Sump
Z Charger 11A	12 20 N 11	3120	N 12 20 12	Z Charger 12A	Z Charger 11B		12 20 N 11		3120 N 12	20 12	Z Charger 12B	Recept Storage		20 N 11		1320 N 12 20 12	Recept Wall
X Charger 13A	12 20	3120	14 20 12	X Charger 14A	X Charger 13B			20	14	20 12	X Charger 14B	Recept MCC	1 1	20 13 1320		14 20 12	Garage North Recept
Y Charger 15A	12 20 15	3120	20 12	Y Charger 16A	Y Charger 15B		12 20 15	3120	16	20 12	Y Charger 16B	Garage South Recept	12	20 15	1320	16	Space
Z Charger 17A	12 20 17	3120	20 12	Z Charger 18A	Z Charger 17B		12 20 17		3120	20 12	Z Charger 18B	Space		17		18	Space
X Charger 19A	12 20	3120	20 12	X Charger 20A	X Charger 19B		12 20 19 312	20	20	20 12	X Charger 20B	Space		19		20	Space
Y Charger 21A	12 20 N 21	3120	22 20 12	Y Charger 22A	Y Charger 21B		12 20 N 21	3120	22	20 12	Y Charger 22B	Space		N 21		22	Space
Z Charger 23A	12 20 M 23	3120	M 24 20 12	Z Charger 24A	Z Charger 23B		12 20 M 23		3120 M 24	20 12	Z Charger 24B	Space		M 23		M 24	Space
X Charger 25A	12 20 M 25	3120	м 26 20 12	X Charger 26A	X Charger 25B		12 20 M 25 3120	20	M 26	20 12	X Charger 26B	Space		M 25		M 26	Space
Y Charger 27A	12 20 127	3120	M 28 20 12	Y Charger 28A	Y Charger 27B		12 20 M 27	3120	M 28	20 12	Y Charger 28B	Space		M 27		M 28	Space
Z Charger 29A	12 20 12 29	3120	м 30 20 12	Z Charger 30A	Z Charger 29B		12 20 M 29		3120 M 30	20 12	Z Charger 30B	Space		M 29		M 30	Space
X Charger 31A	12 20 31	3120	3 2 20 12	X Charger 32A	X Charger 31B			20	1 1 1	20 12	X Charger 32B	Space		122		32	Space
Y Charger 33A	12 20	3120	3 4 20 12	Y Charger 34A	Y Charger 33B		12 20 33	3120	34	20 12	Y Charger 34B	Space		33		34	Space
Z Charger 35A	12 20 35	3120		Z Charger 36A	Z Charger 35B		12 20 35		3120	20 12	Z Charger 36B	Space		35		36	Space
X Charger 37A	12 20 37	3120	38 20 12	X Charger 38A	X Charger 37B		12 20 37 3120	20	38	20 12	X Charger 38B	Space		37		38	Space
Y Charger 39A	12 20 38	3120	20 12	Y Charger 40A	Y Charger 39B		12 20 39	3120	4 0	20 12	Y Charger 40B	Space		41		40	Space
Space	4.1		42	Space HIGH LEG LOAD:	Space		41		42		Space HIGH LEG LOAD:	Space				42	Space HIGH LEG LOAD:
TOTAL CONNECTED LOAD		21840 21840 18720	27200.00 10.00		TOTAL CONNEC	TED LOAD	2184	40 21840	18720	27200.00 1/1/4		TOTAL CONNECTED LOAD			4590	1770	
C=CONTINUOUS X 125% (NEC 210.20a)		27300.000 27300.000 23400.000	2/300.00 KVA 240 V	= 113.75 AMPERES	C=CONTINUOUS	X 125% (NEC 210.20a)	27300.	27300.000	23400.000 —	240 V	= 113.75 AMPERES	C=CONTINUOUS X 125% (NEC 210.20a)		2478.0	0 5300.000	240	KVA = 20.58 AMPERES
N=NON-CONTINUOUS		0.000 0.000 0.000			N=NON-CONTINU	Jous	0.00	0.000	0.000			N=NON-CONTINUOUS		350.00	350.000	1770.000	
M=LARGEST MOTOR X 125% (NEC 220-14)		0.000 0.000 0.000			M=LARGEST MO	TOR X 125% (NEC 220-14)		0.000	0.000			M=LARGEST MOTOR X 125% (NEC 220-14)					
TOTAL CALCULATED NEC LOAD		27300.000 27300.000 23400.000			TOTAL CALCULA	TED NEC LOAD	27300.	27300.000	23400.000			TOTAL CALCULATED NEC LOAD		2828.0	0 4940.000	1770.000	

SHORT CIRCUIT CALCULATIONS

F1 = 300,00 VA/ 240V / 1.732 x 100 / 1.6 = 45,106 A

THE VALUE IS BASED ON THE INFINITE BUSS MODEL AND A TRANSFORMER IMPEDANCE OF

1.6% AS RECOMMENDED BY DTE STANDARDS.

Know what's Below. CALL before you dig.									
			MCN	MCN	CHECKED				
			BWA	BWA	DRAWN				
			04.27.2016	03.21.2016	DATE				
			SID SET	90% REVIEW SET	DESCRIPTION				

PREPARED BY:



COMMUNITY SERVICES AREA - CITY OF ANN ARBOR

LESLIE PARK GOLF COURSE

GOLF CART STORAGE BUILDING

16 of 16