

ADDENDUM No. 5

ITB No. 4424: W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1

Due: June 9, 2016 at 2:00 p.m. (local time)

The following changes, additions, and/or deletions shall be made to the Invitation to Bid for W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1, ITB No. 4424, on which proposals will be received on/or before June 9, 2016 at 2:00 p.m. (local time).

The information contained herein shall take precedence over the original documents and all previous addenda (if any), and is appended thereto. **This Addendum includes 22 page(s).**

Bidder is to acknowledge receipt of this Addendum No. 5, including all attachments (if any) in its Bid by so indicating on Page ITB-1 of the ITB document. Bids submitted without acknowledgement of receipt of this addendum will be considered nonconforming.

The following forms provided within the ITB document must be included in submitted bids:

- City of Ann Arbor Prevailing Wage Declaration of Compliance
- City of Ann Arbor Living Wage Ordinance Declaration of Compliance
- Vendor Conflict of Interest Disclosure Form
- City of Ann Arbor Non-Discrimination Ordinance Declaration of Compliance

Bids that fail to provide these completed forms listed above upon bid opening will be rejected as non-responsive and will not be considered for award.

I. CORRECTIONS/ADDITIONS/DELETIONS

Changes to the Bid document which are outlined below are referenced to a page or Section in which they appear conspicuously. The Bidder is to take note in its review of the documents and include these changes as they may affect work or details in other areas not specifically referenced here.

Section/Page(s)

Change

All mentions

As provided in Addendum 4:
Bid Due Date: June 3, 2016 at 10:00 a.m.

As updated herein:
Bid Due Date: June 9, 2016 at 2:00 p.m.

Comment: The Due Date and Time for responses to this ITB has been extended to June 9, 2016 at 2:00 p.m. (local time). Note that all other dates are unchanged.

Bid Forms/ADD 4-7 thru 12

Base Bid Forms; replace with pages ADD 5-3 thru 8

Bid Forms/ADD 4-13 thru 18

Time Alternate Bid Forms; replace with pages ADD 5-9 thru 14

Detailed Specifications/ADD 4-54 thru 58

Detailed Specification for Timber Boardwalk and Foundation System; replace with pages ADD 5-15 thru 19

APPENDIX/ADD 4-59

Appendix title page; replace with page ADD 5-20

APPENDIX

Pittsfield Charter Twp Water Main Specifications and Details; insert pages ADD 5-21 thru 22

Respondents are responsible for any conclusions that they may draw from the information contained in the Addendum.

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

BASE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use by August 31, 2016; Slope Restoration and Landscape Plantings Complete by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
10	1047051	_General Conditions, Max \$75,000.00	LSUM	1.000	\$ _____	\$ _____
20	1047051	_Project Supervision, Max \$10,000.00	LSUM	1.000	\$ _____	\$ _____
30	1047051	_Audiovisual Tape Coverage	LSUM	1.000	\$ _____	\$ _____
40	2020002	Tree, Rem, 19 inch to 36 inch	Ea	2.000	\$ _____	\$ _____
50	2020004	Tree, Rem, 6 inch to 18 inch	Ea	19.000	\$ _____	\$ _____
60	2030001	Culv, Rem, Less than 24 inch	Ea	3.000	\$ _____	\$ _____
70	2030011	Dr Structure, Rem	Ea	2.000	\$ _____	\$ _____
80	2030015	Sewer, Rem, Less than 24 inch	Ft	30.000	\$ _____	\$ _____
90	2047001	_Curb, Gutter, and Curb and Gutter, Any Type, Rem	Ft	137.000	\$ _____	\$ _____
100	2047011	_Sidewalk, Sidewalk Ramp, and Driveway Approach, Any Thickness, Rem	Syd	109.000	\$ _____	\$ _____
110	2047050	_Exploratory Excavation (0-10' Deep) Tr Det I	Ea	5.000	\$ _____	\$ _____
120	2050023	Granular Material, CI II	Cyd	705.000	\$ _____	\$ _____
130	2057011	_Grading, Driveway Approach	Syd	360.000	\$ _____	\$ _____
140	2057011	_Grading, Sidewalk	Syd	6,070.000	\$ _____	\$ _____
150	2057011	_Grading, Sidewalk Ramp	Syd	30.000	\$ _____	\$ _____
160	2057011	_Machine Grading, Special	Syd	115.000	\$ _____	\$ _____
170	2057021	_Subgrade Undercutting, Type IIA	Cyd	50.000	\$ _____	\$ _____
180	2057021	_Subgrade Undercutting, Type IIB	Cyd	50.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

BASE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use by August 31, 2016; Slope Restoration and Landscape Plantings Complete by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
190	2080012	Erosion Control, Check Dam, Stone	Ft	330.000	\$ _____	\$ _____
200	2080036	Erosion Control, Silt Fence	Ft	2,153.000	\$ _____	\$ _____
210	2087050	_Erosion Control, Inlet Filter	Ea	21.000	\$ _____	\$ _____
220	2090001	Project Cleanup	LSUM	1.000	\$ _____	\$ _____
230	3020001	Aggregate Base	Ton	35.000	\$ _____	\$ _____
240	3060020	Maintenance Gravel	Ton	50.000	\$ _____	\$ _____
250	4020987	Sewer, CI IV, 12 inch, Tr Det B	Ft	229.000	\$ _____	\$ _____
260	4021260	Trench Undercut and Backfill	Cyd	10.000	\$ _____	\$ _____
270	4030200	Dr Structure, 24 inch dia	Ea	2.000	\$ _____	\$ _____
280	4021204	Sewer Tap, 12 inch	Ea	4.000	\$ _____	\$ _____
290	4030035	_Dr Structure Cover, Type E	Ea	3.000	\$ _____	\$ _____
300	4030040	_Dr Structure Cover, Type G	Ea	2.000	\$ _____	\$ _____
310	4037001	_Dr Structure, Adj, Add Depth, Modified	Ft	5.000	\$ _____	\$ _____
320	4037050	_Dr Structure Cover, Type B, Modified	Ea	2.000	\$ _____	\$ _____
330	4037050	_Dr Structure Cover, Type D, Modified	Ea	1.000	\$ _____	\$ _____
340	4037050	_Dr Structure Cover, Type K, Modified	Ea	2.000	\$ _____	\$ _____
350	4037050	_Dr Structure, Adj, Case 1, Modified	Ea	1.000	\$ _____	\$ _____
360	4037050	_Dr Structure, Adj, Case 2, Modified	Ea	17.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

BASE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use by August 31, 2016; Slope Restoration and Landscape Plantings Complete by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
370	4037050	_Dr Structure, Cleaning, Modified	Ea	10.000	\$ _____	\$ _____
380	4047001	_Underdrain, Subgrade, 6 inch, Special	Ft	200.000	\$ _____	\$ _____
390	5010005	HMA Surface, Rem	Syd	7.500	\$ _____	\$ _____
400	5010025	Hand Patching	Ton	85.000	\$ _____	\$ _____
410	6030005	Cement	Ton	0.500	\$ _____	\$ _____
420	7057001	Helical Pier	Foot	5,400.000	\$ _____	\$ _____
430	7097001	Timber Boardwalk	Foot	360.000	\$ _____	\$ _____
440	7097001	Safety Railing	Foot	720.000	\$ _____	\$ _____
450	8017011	_Driveway, Nonreinf Conc, 6 inch, Modified	Syd	130.000	\$ _____	\$ _____
460	8017011	_Driveway, Nonreinf Conc, 8 inch, Modified	Syd	230.000	\$ _____	\$ _____
470	8027001	_Curb and Gutter, Conc	Ft	1,095.000	\$ _____	\$ _____
480	8037001	_Detectable Warning Surface, Modified	Ft	93.000	\$ _____	\$ _____
490	8037001	_Fence, Protective, Modified	Ft	5,153.000	\$ _____	\$ _____
500	8037010	_Sidewalk Ramp, Conc, 6 inch, Modified	Sft	260.000	\$ _____	\$ _____
510	8037010	_Sidewalk Retaining Wall, Integral, 6 inch to 18 inch Height	Sft	375.000	\$ _____	\$ _____
520	8037010	_Sidewalk Retaining Wall, Integral, Greater than 18 inch Height	Sft	1,550.000	\$ _____	\$ _____
530	8037010	_Sidewalk, Conc, 4 inch, Modified	Sft	53,660.000	\$ _____	\$ _____
540	8037010	_Sidewalk, Conc, 6 inch, Modified	Sft	595.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

BASE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use by August 31, 2016; Slope Restoration and Landscape Plantings Complete by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
550	8037010	_Sidewalk, Conc, 8 inch, Modified	Sft	365.000	\$ _____	\$ _____
560	8067050	_HMA Path Terminus	Each	2.000	\$ _____	\$ _____
570	8070095	Post, Mailbox	Ea	4.000	\$ _____	\$ _____
580	8077050	Post, Anchor, Mailbox	Ea	2.000	\$ _____	\$ _____
590	8110049	Pavt Mrkg, Ovly Cold Plastic, Direction Arrow Sym, Bike	Ea	2.000	\$ _____	\$ _____
600	8110058	Pavt Mrkg, Ovly Cold Plastic, Bike, Small Sym	Ea	2.000	\$ _____	\$ _____
610	8110197	Pavt Mrkg, Thermopl, 6 inch, Crosswalk	Ft	12.000	\$ _____	\$ _____
620	8110198	Pavt Mrkg, Thermopl, 6 inch, White	Ft	1,080.000	\$ _____	\$ _____
630	8110218	Pavt Mrkg, Thermopl, 24 inch, Stop Bar	Ft	6.000	\$ _____	\$ _____
640	8117001	_Pavt Mrkg, Thermopl, 24 inch, Crosswalk	Ft	36.000	\$ _____	\$ _____
650	8120012	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	Ea	10.000	\$ _____	\$ _____
660	8120013	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	Ea	10.000	\$ _____	\$ _____
670	8120030	Channelizing Device, 42 inch, Furn	Ea	75.000	\$ _____	\$ _____
680	8120031	Channelizing Device, 42 inch, Oper	Ea	75.000	\$ _____	\$ _____
690	8120140	Lighted Arrow, Type C, Furn	Ea	2.000	\$ _____	\$ _____
700	8120141	Lighted Arrow, Type C, Oper	Ea	2.000	\$ _____	\$ _____
710	8120260	Plastic Drum, High Intensity, Furn	Ea	75.000	\$ _____	\$ _____
720	8120261	Plastic Drum, High Intensity, Oper	Ea	75.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

BASE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use by August 31, 2016; Slope Restoration and Landscape Plantings Complete by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
730	8120330	Sign, Portable, Changeable Message, Furn	Ea	2.000	\$ _____	\$ _____
740	8120331	Sign, Portable, Changeable Message, Oper	Ea	2.000	\$ _____	\$ _____
750	8120350	Sign, Type B, Temp, Prismatic, Furn	Sft	200.000	\$ _____	\$ _____
760	8120351	Sign, Type B, Temp, Prismatic, Oper	Sft	200.000	\$ _____	\$ _____
770	8120370	Traf Regulator Control	LSUM	1.000	\$ _____	\$ _____
780	8127051	_Minor Traffic Control, Max \$7,500.00	LSUM	1.000	\$ _____	\$ _____
790	8150002	Watering and Cultivating, First Season, Min. \$1,500.00	LSUM	1.000	\$ _____	\$ _____
800	8150003	Watering and Cultivating, Second Season, Min. \$1,500.00	LSUM	1.000	\$ _____	\$ _____
810	8152541	Pachysandra terminalis, 3 inch pot	Ea	1,600.000	\$ _____	\$ _____
820	8150780	Celtis occidentalis, 2 inch	Ea	2.000	\$ _____	\$ _____
830	8151409	Fagus grandifolia, 2 inch	Ea	2.000	\$ _____	\$ _____
840	8151409	Gymnocladus dioicus, 2 inch	Ea	1.000	\$ _____	\$ _____
850	8152742	Picea abies, 6 foot	Ea	5.000	\$ _____	\$ _____
860	8153044	Quercus bicolor, 2 inch	Ea	2.000	\$ _____	\$ _____
870	8167011	_Slope Restoration	Syd	8,915.000	\$ _____	\$ _____
880	8190132	Conduit, DB, 2, 3 inch	Ft	4,933.000	\$ _____	\$ _____
890	8197050	_Handhole Assembly, 12 Inch X 18 Inch	Ea	20.000	\$ _____	\$ _____
900	8197050	_Handhole Assembly, 17 Inch X 30 Inch	Ea	2.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

BASE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use by August 31, 2016; Slope Restoration and Landscape Plantings Complete by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
910	8197050	_Handhole, Adj, Modified	Ea	9.000	\$ _____	\$ _____
920	8200105	Pedestal, Fdn	Ea	1.000	\$ _____	\$ _____
930	8230096	Hydrant, Relocate, Case 2	Ea	3.000	\$ _____	\$ _____
940	8507050	_Monitoring Well, Adj	Ea	11.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____
TOTAL FROM PAGE ADD 5-3						\$ _____
TOTAL FROM PAGE ADD 5-4						\$ _____
TOTAL FROM PAGE ADD 5-5						\$ _____
TOTAL FROM PAGE ADD 5-6						\$ _____
TOTAL FROM PAGE ADD 5-7						\$ _____
TOTAL BASE BID						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

TIME ALTERNATE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use, and Slope Restoration and Landscape Plantings Complete All by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
10	1047051	_General Conditions, Max \$75,000.00	LSUM	1.000	\$ _____	\$ _____
20	1047051	_Project Supervision, Max \$10,000.00	LSUM	1.000	\$ _____	\$ _____
30	1047051	_Audiovisual Tape Coverage	LSUM	1.000	\$ _____	\$ _____
40	2020002	Tree, Rem, 19 inch to 36 inch	Ea	2.000	\$ _____	\$ _____
50	2020004	Tree, Rem, 6 inch to 18 inch	Ea	19.000	\$ _____	\$ _____
60	2030001	Culv, Rem, Less than 24 inch	Ea	3.000	\$ _____	\$ _____
70	2030011	Dr Structure, Rem	Ea	2.000	\$ _____	\$ _____
80	2030015	Sewer, Rem, Less than 24 inch	Ft	30.000	\$ _____	\$ _____
90	2047001	_Curb, Gutter, and Curb and Gutter, Any Type, Rem	Ft	137.000	\$ _____	\$ _____
100	2047011	_Sidewalk, Sidewalk Ramp, and Driveway Approach, Any Thickness, Rem	Syd	109.000	\$ _____	\$ _____
110	2047050	_Exploratory Excavation (0-10' Deep) Tr Det I	Ea	5.000	\$ _____	\$ _____
120	2050023	Granular Material, CI II	Cyd	705.000	\$ _____	\$ _____
130	2057011	_Grading, Driveway Approach	Syd	360.000	\$ _____	\$ _____
140	2057011	_Grading, Sidewalk	Syd	6,070.000	\$ _____	\$ _____
150	2057011	_Grading, Sidewalk Ramp	Syd	30.000	\$ _____	\$ _____
160	2057011	_Machine Grading, Special	Syd	115.000	\$ _____	\$ _____
170	2057021	_Subgrade Undercutting, Type IIA	Cyd	50.000	\$ _____	\$ _____
180	2057021	_Subgrade Undercutting, Type IIB	Cyd	50.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

TIME ALTERNATE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use, and Slope Restoration and Landscape Plantings Complete All by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
190	2080012	Erosion Control, Check Dam, Stone	Ft	330.000	\$ _____	\$ _____
200	2080036	Erosion Control, Silt Fence	Ft	2,153.000	\$ _____	\$ _____
210	2087050	_Erosion Control, Inlet Filter	Ea	21.000	\$ _____	\$ _____
220	2090001	Project Cleanup	LSUM	1.000	\$ _____	\$ _____
230	3020001	Aggregate Base	Ton	35.000	\$ _____	\$ _____
240	3060020	Maintenance Gravel	Ton	50.000	\$ _____	\$ _____
250	4020987	Sewer, CI IV, 12 inch, Tr Det B	Ft	229.000	\$ _____	\$ _____
260	4021260	Trench Undercut and Backfill	Cyd	10.000	\$ _____	\$ _____
270	4030200	Dr Structure, 24 inch dia	Ea	2.000	\$ _____	\$ _____
280	4021204	Sewer Tap, 12 inch	Ea	4.000	\$ _____	\$ _____
290	4030035	_Dr Structure Cover, Type E	Ea	3.000	\$ _____	\$ _____
300	4030040	_Dr Structure Cover, Type G	Ea	2.000	\$ _____	\$ _____
310	4037001	_Dr Structure, Adj, Add Depth, Modified	Ft	5.000	\$ _____	\$ _____
320	4037050	_Dr Structure Cover, Type B, Modified	Ea	2.000	\$ _____	\$ _____
330	4037050	_Dr Structure Cover, Type D, Modified	Ea	1.000	\$ _____	\$ _____
340	4037050	_Dr Structure Cover, Type K, Modified	Ea	2.000	\$ _____	\$ _____
350	4037050	_Dr Structure, Adj, Case 1, Modified	Ea	1.000	\$ _____	\$ _____
360	4037050	_Dr Structure, Adj, Case 2, Modified	Ea	17.000	\$ _____	\$ _____

TOTAL THIS PAGE \$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

TIME ALTERNATE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use, and Slope Restoration and Landscape Plantings Complete All by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
370	4037050	_Dr Structure, Cleaning, Modified	Ea	10.000	\$ _____	\$ _____
380	4047001	_Underdrain, Subgrade, 6 inch, Special	Ft	200.000	\$ _____	\$ _____
390	5010005	HMA Surface, Rem	Syd	7.500	\$ _____	\$ _____
400	5010025	Hand Patching	Ton	85.000	\$ _____	\$ _____
410	6030005	Cement	Ton	0.500	\$ _____	\$ _____
420	7057001	Helical Pier	Foot	5,400.000	\$ _____	\$ _____
430	7097001	Timber Boardwalk	Foot	360.000	\$ _____	\$ _____
440	7097001	Safety Railing	Foot	720.000	\$ _____	\$ _____
450	8017011	_Driveway, Nonreinf Conc, 6 inch, Modified	Syd	130.000	\$ _____	\$ _____
460	8017011	_Driveway, Nonreinf Conc, 8 inch, Modified	Syd	230.000	\$ _____	\$ _____
470	8027001	_Curb and Gutter, Conc	Ft	1,095.000	\$ _____	\$ _____
480	8037001	_Detectable Warning Surface, Modified	Ft	93.000	\$ _____	\$ _____
490	8037001	_Fence, Protective, Modified	Ft	5,153.000	\$ _____	\$ _____
500	8037010	_Sidewalk Ramp, Conc, 6 inch, Modified	Sft	260.000	\$ _____	\$ _____
510	8037010	_Sidewalk Retaining Wall, Integral, 6 inch to 18 inch Height	Sft	375.000	\$ _____	\$ _____
520	8037010	_Sidewalk Retaining Wall, Integral, Greater than 18 inch Height	Sft	1,550.000	\$ _____	\$ _____
530	8037010	_Sidewalk, Conc, 4 inch, Modified	Sft	53,660.000	\$ _____	\$ _____
540	8037010	_Sidewalk, Conc, 6 inch, Modified	Sft	595.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

TIME ALTERNATE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use, and Slope Restoration and Landscape Plantings Complete All by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
550	8037010	_Sidewalk, Conc, 8 inch, Modified	Sft	365.000	\$ _____	\$ _____
560	8067050	_HMA Path Terminus	Each	2.000	\$ _____	\$ _____
570	8070095	Post, Mailbox	Ea	4.000	\$ _____	\$ _____
580	8077050	Post, Anchor, Mailbox	Ea	2.000	\$ _____	\$ _____
590	8110049	Pavt Mrkg, Ovly Cold Plastic, Direction Arrow Sym, Bike	Ea	2.000	\$ _____	\$ _____
600	8110058	Pavt Mrkg, Ovly Cold Plastic, Bike, Small Sym	Ea	2.000	\$ _____	\$ _____
610	8110197	Pavt Mrkg, Thermopl, 6 inch, Crosswalk	Ft	12.000	\$ _____	\$ _____
620	8110198	Pavt Mrkg, Thermopl, 6 inch, White	Ft	1,080.000	\$ _____	\$ _____
630	8110218	Pavt Mrkg, Thermopl, 24 inch, Stop Bar	Ft	6.000	\$ _____	\$ _____
640	8117001	_Pavt Mrkg, Thermopl, 24 inch, Crosswalk	Ft	36.000	\$ _____	\$ _____
650	8120012	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	Ea	10.000	\$ _____	\$ _____
660	8120013	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	Ea	10.000	\$ _____	\$ _____
670	8120030	Channelizing Device, 42 inch, Furn	Ea	75.000	\$ _____	\$ _____
680	8120031	Channelizing Device, 42 inch, Oper	Ea	75.000	\$ _____	\$ _____
690	8120140	Lighted Arrow, Type C, Furn	Ea	2.000	\$ _____	\$ _____
700	8120141	Lighted Arrow, Type C, Oper	Ea	2.000	\$ _____	\$ _____
710	8120260	Plastic Drum, High Intensity, Furn	Ea	75.000	\$ _____	\$ _____
720	8120261	Plastic Drum, High Intensity, Oper	Ea	75.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

TIME ALTERNATE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use, and Slope Restoration and Landscape Plantings Complete All by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
730	8120330	Sign, Portable, Changeable Message, Furn	Ea	2.000	\$ _____	\$ _____
740	8120331	Sign, Portable, Changeable Message, Oper	Ea	2.000	\$ _____	\$ _____
750	8120350	Sign, Type B, Temp, Prismatic, Furn	Sft	200.000	\$ _____	\$ _____
760	8120351	Sign, Type B, Temp, Prismatic, Oper	Sft	200.000	\$ _____	\$ _____
770	8120370	Traf Regulator Control	LSUM	1.000	\$ _____	\$ _____
780	8127051	_Minor Traffic Control, Max \$7,500.00	LSUM	1.000	\$ _____	\$ _____
790	8150002	Watering and Cultivating, First Season, Min. \$1,500.00	LSUM	1.000	\$ _____	\$ _____
800	8150003	Watering and Cultivating, Second Season, Min. \$1,500.00	LSUM	1.000	\$ _____	\$ _____
810	8152541	Pachysandra terminalis, 3 inch pot	Ea	1,600.000	\$ _____	\$ _____
820	8150780	Celtis occidentalis, 2 inch	Ea	2.000	\$ _____	\$ _____
830	8151409	Fagus grandifolia, 2 inch	Ea	2.000	\$ _____	\$ _____
840	8151409	Gymnocladus dioicus, 2 inch	Ea	1.000	\$ _____	\$ _____
850	8152742	Picea abies, 6 foot	Ea	5.000	\$ _____	\$ _____
860	8153044	Quercus bicolor, 2 inch	Ea	2.000	\$ _____	\$ _____
870	8167011	_Slope Restoration	Syd	8,915.000	\$ _____	\$ _____
880	8190132	Conduit, DB, 2, 3 inch	Ft	4,933.000	\$ _____	\$ _____
890	8197050	_Handhole Assembly, 12 Inch X 18 Inch	Ea	20.000	\$ _____	\$ _____
900	8197050	_Handhole Assembly, 17 Inch X 30 Inch	Ea	2.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____

BID FORM

Section 1 - Schedule of Prices

W.R. Wheeler (Swift Run) Service Center PUD Non-motorized Improvements – Phase 1
File No. 2014-031
Bid No. 4424

TIME ALTERNATE BID (Sidewalk and Sidewalk Ramps Complete and Open for Use, and Slope Restoration and Landscape Plantings Complete All by October 10, 2016; Entire Project Complete by November 10, 2016)

<u>Line No.</u>	<u>Item No.</u>	<u>Item Description</u>	<u>Unit</u>	<u>Estimated Quantity</u>	<u>Unit Price</u>	<u>Total Price</u>
910	8197050	_Handhole, Adj, Modified	Ea	9.000	\$ _____	\$ _____
920	8200105	Pedestal, Fdn	Ea	1.000	\$ _____	\$ _____
930	8230096	Hydrant, Relocate, Case 2	Ea	3.000	\$ _____	\$ _____
940	8507050	_Monitoring Well, Adj	Ea	11.000	\$ _____	\$ _____
TOTAL THIS PAGE						\$ _____
TOTAL FROM PAGE ADD 5-9						\$ _____
TOTAL FROM PAGE ADD 5-10						\$ _____
TOTAL FROM PAGE ADD 5-11						\$ _____
TOTAL FROM PAGE ADD 5-12						\$ _____
TOTAL FROM PAGE ADD 5-13						\$ _____
TOTAL BASE BID						\$ _____

CITY OF ANN ARBOR
DETAILED SPECIFICATION
FOR
TIMBER BOARDWALK AND FOUNDATION SYSTEM

WHEELER PUD PH I:
STANTEC/AFT, CAA/DAD

1 of 5

06/02/16

a. Description. This work consists of furnishing all labor, equipment, and materials necessary to construct a timber boardwalk over the wetland area as shown on the plans, including timber framing, decking and structural components, a foundation system using helical piers, railings with treated timber and composite wood, and concrete massive wall unit blocks as the HMA terminus.

All structural members of the boardwalk shall be designed for a uniform pedestrian live load of 90 psf. The pedestrian live load shall be applied to those areas of the walkway so as to produce maximum stress in the member being designed. The boardwalk shall be designed for a maintenance vehicle satisfying the AASHTO H-10 Design Truck configuration. A single truck shall be placed to produce the maximum load effects and shall not be placed in combinations with the pedestrian load.

b. Materials. Wood framing, decking, structural components, footings, and hardware must be in accordance with sections 709 and 912 of the Michigan Department of Transportation (MDOT) 2012 Standard Specifications for Construction except as modified herein.

Submit the following to the Engineer for approval at least 14 calendar days prior to the start of construction. Work must not begin until all submittals have been received and approved by the Engineer.

1. Working drawings and design calculations for the Helical Piles intended for use. The calculations should include the minimum torque required to install the vertical and battered helical piles based on the specified allowable capacities, the estimated pier installation depth of the helical piles, and a critical buckling load analysis due to the low strength soil conditions on site.
2. A detailed description of the construction procedures proposed for review, including a list of major equipment to be used.
3. Shop drawings for all Helical Pile components that include, but are not limited to:
 - a. Helical Pile design load,
 - b. Type and size of central steel shaft,
 - c. Helix configuration (number and diameter of helix plates),
 - d. Minimum effective installation torque,
 - e. Minimum overall length,
 - f. Inclination of Helical Pile,
 - g. Helical Pile attachment to structure relative to grade beam, column pad, pile cap, etc.,
 - h. Indication of corrosion protection.
4. Soil Analysis Report for detailed bearing capacity.

5. Copies of calibration reports for each torque indicator or torque motor, and all load test equipment to be used on the project. The calibration tests must have been performed within 45 working days of the date submitted. Helical Pile installation and testing must not proceed until the Engineer has received the calibration reports.

Helical piers as specified must conform to the applicable building code.

The helical lead sections and extension sections must be solid steel, round cornered square shaft, or round steel pipe shaft, or composite steel and grout shaft configured with one or more helical bearing plates welded to the shaft. Bolts and couplings shall be per manufacturer's recommendations for each helical pier type.

All helical pile material must be corrosion protected by hot dip galvanization after fabrication in accordance with ASTM A 123 and/or ASTM A 153.

Installation units consist of a rotary type torque motor with forward and reverse capabilities.

Appropriate helical pier selection will consider design load plus safety factor, soil parameters and the installation torque vs. capacity equation as per the manufacturer's recommendations.

Design of helical screw piers and anchors must be performed by an entity as required in accordance with existing local code requirements or established local practices. This design work shall be performed by a licensed professional engineer licensed in the state of Michigan.

Piers must have U-shape bracket sleeves to mount lateral support beams for joist and deck structure. All component materials must be protected by hot dip galvanization in accordance with ASTM A 153.

The minimum block dimensions for the concrete massive wall units shall be 12 inches high x 72 inches wide x 14 inches deep and have a minimum block weight of 850 pounds.

The concrete massive wall units shall meet the aesthetic requirements for the site.

The concrete massive wall units shall have a minimum 28-day compressive strength of 5000 psi as tested in accordance with ASTM C 140. The concrete shall have a maximum moisture absorption rate of 5 percent to ensure adequate freeze-thaw.

The drainage pipe used in the HMA path terminus section shall be perforated corrugated HDPE or PVC pipe, with a minimum diameter of 4 inches, protected by a geotextile filter to prevent the migration of soil particles into the pipe.

All timber and lumber shall be treated and in accordance with section 912 of the MDOT 2012 Standard Specifications for Construction. Lumber shall be S4S (surfaced four sides) according to ASTM D245. All lumber sizes are nominal. All lumber shall be stamped by the rating agency and certifications shall be provided to verify the preservative treatment including net retention, pressure process used, and compliance to current standards.

Fasteners, unless specifically noted, may be screws or nails in accordance with MDOT 2012 Standard Specifications for Construction.

c. Construction. Construction must be in accordance with section 709 and 912 of the MDOT 2012 Standard Specifications for Construction except as modified herein.

Protection in Transit. A coat of end sealer must be applied to ends of all wood members as soon as practicable after end trimming. Wood members must be protected until installed.

Field Storage and Handling. If products are stored temporarily at the job site after arrival, wood members must be placed on blocking, well off the ground and be separated by wood blocking so air can circulate around each member. Place water resistance paper over the top but do not use opaque polyethylene.

Butt Joints, if used, must be placed over supports and must be staggered a minimum of 3 feet apart for adjacent planks.

Centerline of Helical Piles must not be more than 3 inches from indicated plan location. Helical Pile plumbness must be within 2 degrees of design alignment. Top elevation of Helical Pile must be within +1 inch to -2 inches of the design vertical elevation.

Helical Piles must be installed by an authorized installer who has satisfied the certification requirements of the manufacturer. Provide the Engineer proof of current manufacturer's certification.

Adequate soil boring information for estimated bearing capacity and pier depths are available from the geotechnical report within the proposal. Installation of Helical Pile locations on the project site will be necessary to generate a presumptive soil profile using the well-known installed torque vs. capacity attribute of helical piles to determine an appropriate helical pier to meet the required capacity.

A torque indicator must be used during Helical Pile installation. The torque indicator can be an integral part of the installation equipment or externally mounted in-line with the installation tooling and must be properly calibrated. The torque indicator shall be capable of providing continuous measurement of applied torque throughout the installation. Installation units must be capable of developing a torque capacity 15% greater than the torsional strength rating of the central steel shaft to be installed.

Installation units must be capable of positioning the helical pier at the proper installation angle and location as indicated on the plans. The Helical Pile sections shall be engaged and advanced into the soil in a smooth, continuous manner at a rate of rotation of 5 to 20 RPM's. Extension sections shall be provided to obtain the required minimum overall length and installation torque as shown on the shop drawings and calculations. Connect sections together using coupling bolt(s) and nut torqued to 40 ft-lb. Sufficient down pressure shall be applied to uniformly advance the Helical Pile sections approximately 3 inches per revolution. The rate of rotation and magnitude of down pressure shall be adjusted for different soil conditions and depths.

Helical Piles must be installed so that the top helical plate is at minimum 42" below ground level.

Battered Helical Piles must be installed to the minimum torque value required to provide 6 kip allowable load capacities. Vertical Helical Piers must be installed to the minimum torque

value required to provide 15 kip allowable load capacities. The average torque for the last three feet of penetration shall be used as the basis of comparison with the minimum installation torque. The average torque shall be defined as the average of the last three readings recorded at on-foot intervals.

Installation torque must be monitored throughout the installation process. Measured torque shall never exceed the torsional strength rating of the central steel shaft.

If reasonable doubt exists as to the accuracy of the torque measurements, the torque indicator shall be re-calibrated on-site.

Install the piers within the construction area with the least amount of disturbance to the wetlands as possible.

Accurately record location, type, torque and depth of piers and provide the Engineer with a copy of this data.

Helical Pile capacity in soil shall not be relied upon from the soil layers indicating peat, marl, or loose sands as shown in the geotechnical report. End-bearing on the helix plates must be in appropriate soil strata.

The bottom row of wall modules for the HMA path terminus section shall be placed on the prepared leveling base as shown on the plans. Care shall be taken to ensure that the wall modules are aligned properly, leveled from side to side and front to back and in complete contact with the base material.

The wall modules above the bottom course shall be placed such that the tongue and groove arrangement provides the design batter as indicated on the plans.

The wall modules shall be swept clean before placing additional levels to ensure no dirt, concrete, or other foreign materials become lodged between successive lifts of the wall modules.

The contractor shall check the level of wall modules with each lift to ensure that no gaps are formed between successive lifts.

Care shall be taken to ensure that the wall modules are not broken or damaged during handling and placement.

Install timber decking planks with a maximum 1/8 inch gap between planks.

Use 4 inch self tapping screws to attach timber decking planks to joists and/or beams. Attach planks with at least two fasteners at each end and at every joist and/or beam. Drill planks prior to installation of screws to prevent splitting.

Fasten joists to header beams using tie down clips/brackets.

d. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit prices using the following pay items:

Pay Item	Pay Unit
Timber Boardwalk	Foot
Helical Pier	Foot
HMA Path Terminus	Each
Safety Railing	Foot

Timber Boardwalk as measured shall be paid for based on the length in feet of boardwalk installed, and includes all labor, equipment, and materials for furnishing and installing the boardwalk over the wetland including all wood members, hardware and fasteners, and appurtenances for a complete installation and as shown on the plans.

Helical Pier as measured shall be paid for based on the length in feet below grade of helical pier installed to the minimum depth specified, and includes all labor, equipment, and materials for furnishing and installing the boardwalk foundation piers in the wetland including drilling equipment, hardware and fasteners, and appurtenances for a complete installation and as shown on the plans. Any helical pier length installed below the minimum depth or minimum torque requirement, whichever is deeper will not be paid.

HMA Path Terminus as measured shall be paid for based on the number each of units installed, and includes all labor, equipment, and materials for furnishing and installing the HMA terminus at the ends of the boardwalk including all concrete massive wall unit blocks, required backfill, limestone base, geotextile fabric, and perforated drain as shown on the plans.

Safety Railing as measured shall be paid for based on the length in feet of safety railing installed, and includes all labor, equipment, and materials necessary for furnishing and installing the safety railings on the boardwalk including all wood members, hardware and fasteners, and appurtenances for a complete installation and as shown on the plans.

APPENDIX

MDOT Special Provisions






MDOT Supplemental Specifications

**MDOT, City of Ann Arbor, and Pittsfield Charter Twp Standard
Plans and Special Details**

MDEQ, WCWRC, and Pittsfield Charter Twp Permits

Geotechnical Report

Pittsfield Charter Twp Water Main Specifications and Details



ELBOWS

PIPE DIA. INCHES	BEARING AREA SQUARE FEET			
	90°	45°	22 1/2°	11 1/4°
4	2.1	1.1	0.6	0.3
6	4.1	2.2	1.1	0.6
8	6.8	3.7	1.9	0.9
10	10.1	5.5	2.8	1.4
12	14.1	7.6	3.9	2.0
16	24.2	13.0	6.7	3.3
18	30.0	16.3	8.3	4.2
20	36.8	19.9	10.1	5.1

TEES, CROSSES & HYDRANTS

PIPE DIA. INCHES	BEARING AREA SQUARE FEET
4	1.5
6	2.9
8	4.8
10	7.1
12	10.0
16	17.1
18	21.0
20	26.0

NOTES:













1. CONCRETE FOR ALL THRUST BLOCKS SHALL BE 3000 PSI, 28 DAY STRENGTH MIN.
2. ALL THRUST BLOCKS SHALL BE POURED AGAINST UNDISTURBED EARTH
3. BOLTS, FITTINGS & JOINTS SHALL BE KEPT CLEAR OF CONCRETE
4. A BEARING CAPACITY OF 2000# PER FOOT WAS USED IN DETERMINING THE MINIMUM "BEARING AREAS" IN THE ABOVE TABLE
5. THE CROSS SECTION OF THE THRUST BLOCKS SHALL BE SQUARE
6. IN ADDITION TO THRUST BLOCKS, ALL PIPE JOINTS SHALL BE RESTRAINED WITH LOCKING GASKETS PER DIPRA'S STANDARDS.

SOIL CHARACTERISTICS

SOIL CHARACTERISTICS	FACTOR
(A) LOOSE COARSE OR MEDIUM SAND; COMPACT FINE SAND; COMPACT SAND-CLAY SOILS; STIFF CLAY	0.33
(B) FIRM FINE SAND; COMPACT INORGANIC SILT; FIRM SAND-CLAY SOILS; MEDIUM CLAY	0.50
(C) LOOSE FINE SAND; FIRM INORGANIC SILT	0.67
(D) LOOSE SAND-CLAY SOILS; LOOSE INORGANIC SILT SOFT CLAY	1.00

"BEARING AREA" x FACTOR = ACTUAL BEARING AREA
2.1 x .5 = 1.05 SQ. FT.
BASED UPON 150# TEST PRESSURE

THRUST BLOCK



UPDATES

Revision	By	Appd.	YY.MM.DD
MRH	DRW		14.01.24
FDC UPDATE	BWA	DRW	11.09.13
TWP REV	BWA	DRW	11.04.27
HYDRANT, MANHOLE UPDATE	BWA	DRW	10.10.25
UPDATES	TIN	DRW	10.01.20

File Name: W-01

Revision	By	Appd.	YY.MM.DD
BWA	DRW	DRW	07.10.01
Dwn.	Chkd.	Dsgn.	YY.MM.DD

Client/Project
PITTSFIELD TOWNSHIP

Pittsfield Township, Michigan

Title
WATER MAIN DETAILS

Project No.
2075001300

Scale
NOT TO SCALE

Revision