



# CITY OF ANN ARBOR ENGINEERING

# PONTIAC, SWIFT, MOORE, & WRIGHT INFRASTRUCTURE IMPROVEMENTS

BID No. 23-22, FILE No. 2022-032





### NOTES:

FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WIT PUBLIC ACT 174 OF 2013, THE CONTRACTOR SHALL CALL 811 OF 1-800-482-7171 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS, PRIOR TO BEGINNING EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALER

THE UNDERGROUND LOCATIONS SHOWN FOR NATURAL GAS, TELEPHONE, ELECTRICAL POWER, CABLE TV AND FIBER OPTIC LINES ARE APPROXIMATE. THE CITY OF ANN ARBOR ASSUMES NO RESPONSIBILITY F THEIR ACCURATE REPRESENTATION IN THIS DRAWING. MISS DIG MUST BE CONTACTED PRIOR TO CONSTRUCTION TO LOCATE THESE UTILITIES.

THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO 1994 EDITION OF THE CITY OF ANN ARBOR PUBLIC SERVICES DEPARTMENT STANDARD SPECIFICATIONS, IT'S DETAILS, WHICH ARE INCLUDED BY REFERENCE, AND THIS PROJECT'S CONTRACT DOCUMENTS. THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THIS REQUIREMENT.

CHRIS WALL, P.E.

MI LICENSE No. 45668 **PROJECT MANAGER** 

03/28/2023



PONTIAC, SWIFT, MOORE, & WRIGHT INFRASTRUCTURE IMPROVEMENTS

Sheet List Ta	ahle
Sheet Number	COVER Sheet Title
1	INDEX
3	LEGEND
4	NOTES
5	DETAILS 1
6	DETAILS 2
7	DETAILS 2 DETAILS 3
8	DETAILS 4
9	EXISTING CONDITIONS & ALIGNMENT PLAN - SWIFT ST STA 0+00 TO 5+50
10	EXISTING CONDITIONS & ALIGNMENT PLAN - SWIFT ST STA 5+50 TO 9+00
11	EXISTING CONDITIONS & ALIGNMENT PLAN - PONTIAC TRAIL
12	EXISTING CONDITIONS & ALIGNMENT PLAN - MOORE ST
13	EXISTING CONDITIONS & ALIGNMENT PLAN - WRIGHT ST
14	TYPICALS - SWIFT STREET
15	TYPICALS - PONTIAC TRAIL
16	TYPICALS - MOORE STREET
17	TYPICALS - WRIGHT STREET
18	SOIL BORING LOGS
19	OVERALL UTILITY PLAN
20	REMOVAL PLAN - SWIFT ST STA 0+00 TO 5+50
21	REMOVAL PLAN - SWIFT ST STA 5+50 TO POE
22	REMOVAL PLAN - PONTIAC TRAIL
23	REMOVAL PLAN - MOORE
24	REMOVAL PLAN - WRIGHT
25	PROPOSED WATER MAIN PLAN AND PROFILE SWIFT ST STA 0+00 TO 3+50
26	PROPOSED WATER MAIN PLAN AND PROFILE SWIFT ST STA 3+50 TO POE
27	PROPOSED WATER MAIN PLAN AND PROFILE - PONTIAC TRAIL
28	PROPOSED WATER MAIN PLAN AND PROFILE - WRIGHT ST
29	PROPOSED WATER MAIN CONSOLIDATION - MOORE ST
30	PROPOSED PAVING PLAN - SWIFT ST STA 0+00 TO STA 2+50
31	PROPOSED PAVING PLAN - SWIFT ST STA 2+50 TO POE
32	PROPOSED PAVING PLAN - PONTIAC TRAIL
33	PROPOSED PAVING PLAN - MOORE
34	PROPOSED PAVING PLAN - WRIGHT
35	ADA RAMPS - SWIFT & PONTIAC
36	ADA RAMPS - MOORE ST
37	ADA RAMPS - WRIGHT & KELLOGG
38	PROPOSED PAVEMENT MARKING - SWIFT & WRIGHT
39	PROPOSED PAVEMENT MARKING - PONTIAC & MOORE
40	PROPOSED SIGNING - SWIFT
41	PROPOSED SIGNING - SWIFT & WRIGHT
42	PROPOSED SIGNING - PONTIAC
43	PROPOSED SIGNING - MOORE
44	PROPOSED SIGNING - WRIGHT
45	MAINTENANCE OF TRAFFIC - STAGE 1
46	MAINTENANCE OF TRAFFIC - STAGE 1A
47	MAINTENANCE OF TRAFFICE - STAGE 2
48	MAINTENANCE OF TRAFFIC - STAGE 3
49	MOT PEDESTRIAN DETAILS 1
50	MOT PEDESTRIAN DETAILS 2
51	MOT PEDESTRIAN DETAILS 3
52	MOT PEDESTRIAN DETAILS 4

LL©			Know what's <b>below</b>	Call before you d
			VCM/CEW	CHECKED
			CGT/BLA VCM/CEW	DRAWN CHECKED
			03/28/2023	DATE
			ISSUED FOR BID	DESCRIPTION
			00	REV.
ARBOR	VICES	347 3107-8647	.org	





CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

SCALE : NTS

DRAWING No.

IMPROVEMENTS

INDEX

PERMITS REQUIRED TO BE OBTAINED BY THE CONTRACTOR PRIOR TO THE BEGINNING OF CONSTRUCTION.								
PERMIT	ISSUING AUTHORITY							
LANE CLOSURE PERMIT*	CITY OF ANN ARBOR ENGINEERING							
"NO PARKING" SIGNS PERMIT*	CITY OF ANN ARBOR ENGINEERING							
GRADING/SOIL EROSION & SEDIMENTATION CONTROL PERMIT*	CITY OF ANN ARBOR CUSTOMER SERVICE							
RIGHT-OF-WAY PERMIT*	CITY OF ANN ARBOR CUSTOMER SERVICE							
* NO COST TO	CONTRACTOR							


### PERMITS REQUIRED TO BE OBTAINED BY THE CITY OF ANN ARBOR PRIOR TO THE BEGINNING OF CONSTRUCTION.


PERMIT	ISSUING AUTHORITY
EGLE WATER MAIN CONSTRUCTION PERMIT	MICHIGAN DEPARTMENT OF ENVIRONMENT, GREAT LAKES, AND ENERGY

CONTACT INFORMATION							
PUBLIC UTILITIES	OWNER	CONTACT					
WATER (DAN WOODEN)							
SANITARY (TRAVIS CONLEY) STORM	CITY OF ANN ARBOR PUBLIC WORKS	(734) 794–6350					
(MARK SIRLS) FORESTRY	W.R. WHEELER SERVICE CENTER 4251 STONE SCHOOL ROAD ANN ARBOR, MI 48108						
(NICK JACOB) SIGNS SIGNALS STREET LIGHTS (MARC MORENO)		(734) 794–6361					
FIBER OPTIC (IT)		(734) 794–6550					
PRIVATE UTILITIES	OWNER	CONTACT					
GAS	DTE ENERGY 3150 E. MICHIGAN AVE, YPSILANTI TOWNSHIP, MI 48198	DARRYL ELLINGTON (313) 995-6078 ZACH WHITE (313) 405-6024					
GAS	CONSUMERS ENERGY 1000 GRAND OAKS DR. HOWELL, MI 48843	BOB MCLACHLAN (517) 242-7878					
ELECTRIC	DTE ENERGY WESTERN WAYNE SERVICE CENTER 8001 HAGGERTY ROAD BELLEVILLE, MI 48111	ANTHONY IGNASIAK (734) 397-4112					
CABLE	COMCAST 27800 FRANKLIN ROAD SOUTHFIELD, MI 48034	RON SUTHERLAND (313) 999-8300					
PHONE	AT&T 550 S. MAPLE ROAD ANN ARBOR, MI 48103	STEVEN ALLSHOUSE (734) 996-5381					
FIBER OPTIC	MCI 2800 N. GLENFILLE ROAD RICHARDSON, TX 75082	DEAN BOYERS (972) 729-6016					
FIBER OPTIC	WNDSTREAM 1295 S LINBDEN ROAD, SUITE B FLINT, MI	GREG SERICH (810) 244-3500					
FIBER OPTIC	LUMEN 19675 W 10 MILE ROAD SOUTHFIELD, MI 48075	DAVE HUCKFELDT (517) 812-2592					
FIBER OPTIC	FIBERLINK, INC PO BOX 701 LAPEER, MI 48446	TINA SNOBLEN (810) 667-2891 EXT 307					
STREET LIGHTING	DTE ENERGY 8001 HAGGERTY ROAD BELLEVILLE, MI 48111	LANCE ALLEY (734) 397-4188					
UNIVERSITY OF MICHIGAN UTILITIES	UNIVERSITY OF MICHIGAN 1201 KIPKE DRIVE, ROOM 1080 ANN ARBOR, MI 48109	TERRY RAMSEY (734) 647-2031					

EXIS	STING LEGEND			PR	OPOS
EX =	EXISTING			PROF	P = PR
<b>†</b> + <i>F</i> :	IRE HYDRANT		WATER MAIN	<del>+</del> +	HYDRAN
-	ATE VALVE IN BOX		WATER MAIN ABANDONED	+	WATER
⊗ <i>G</i>	ATE VALVE IN WELL	<u></u>	STORM SEWER		REDUCE
w s	TOP BOX	//	STORM SEWER ABANDONED	_	WATER
w W	ATER VAULT	<u></u>	SANITARY SEWER	(1)	WATER
<b>D</b> W	ELL	//	SANITARY SEWER ABANDONED	W	WATER
] C	ATCH BASIN (SQ)	g	GAS MAIN	•	INLET
<b>∌</b> C	ATCH BASIN (RD)	— g (Dead)—— —— —— ——	GAS MAIN (DEAD)		DOUBLE
S	TORM MANHOLE		ELECTRICAL OVER HEAD	•	INLET J
□ ^	ON-CURB CATCH BASIN (SQ)		ELECTRICAL UNDER GROUND		ROUND
) <i>E</i>	ND SECTION	e duct bank	ELECTRICAL DUCT BANK	0	STORM
S	ANITARY MANHOLE	oht ·	TELEPHONE OVER HEAD	•	DRAIN .
	LEAN-OUT		TELEPHONE UNDER GROUND		FLARED
	OST	t duct bank	TELEPHONE DUCT BANK		SANITAI
	EDESTRIAN SIGNAL		CABLE TV OVER HEAD		CLEAN-
	IGN		CABLE TV UNDER GROUND		BARREL
	AND HOLE	fo	FIBER OPTIC		SIGN
	RNAMENTAL LIGHT LOOD LIGHT	fo duct bank	FIBER OPTIC DUCT BANK	110	PUSH E
	NKNOWN MANHOLE		BOUNDARY		HAND H
	ELEPHONE MANHOLE		BUILDING		
_	ELEPHONE RISER		CENTERLINE OF DITCH		
	AS VALVE		CENTERLINE/CROWN OF ROAD		
	AS VENT		CONTOUR MAJOR		
	AS BOX		CONTOUR MINOR		
lu .	LECTRICAL RISER		EDGE OF WATER		
<b>⊠</b> 77	RANSFORMER		FLOODPLAIN		
<b>σ</b> υ	TILITY POLE	—//——//—	FENCE		
⊃ <i>L</i> .	AMP POLE	:::	GRAVEL		
- G	UY ANCHOR	<del></del>	GUARDRAIL		
$\varphi$ $G$	UY POLE	000000000000000000000000000000000000000	STONE WALL		
III) M	ONITORING WELL		R.O.W.		
M M	AILBOX		TREELINE		
<b>)</b> S	OIL BORING		WETLAND		
	RAVERSE POINT		EDGE OF BRUSH		
	ENCH MARK		HEDGE		
	RON PIPE	~~~	HEDGE		
• M	ON BOX				
			TREE (DECIDUOUS)		
			TREE (CONVEEDOUS)		
			TREE (CONIFEROUS)		
			SHRUB (DECIDUOUS)		
			STUMP		
		-0-	1		
		Service Control of the Control of th	R.L.		
			TREE TO REMAIN & PROTECT (DECIDUOUS) CRITICAL ROOT ZONE (C.R.Z.) = DIAMETER BREAST HEIGHT (INCHES) X 10		
			, , , , , , , , , , , , , , , , , , ,		
		M c.5	3.7.		
			TREE TO REMAIN & PROTECT (CONIFEROUS)		
			CRITICAL ROOT ZONE (C.R.Z.) = DIAMETER BREAST HEIGHT (INCHES) X 10		

PROPO	SED LEGEND			
PROP = PF	ROPOSED			
∳+ HYDRA	NT (PLAN)	w		WATER MAIN
⊗ WATER	GATE WELL			STORM SEWER
▼ REDUC	ER	S		SANITARY SEWER
<b>■</b> WATER	GATE VALVE	——FO——		FIBER OPTIC
	STOP BOX	——Е — — —		ELECTRICAL
w water	VAULT			CENTERLINE OF DITCH
INLET				CENTERLINE OF ROAD
■■ DOUBL	E INLET	//	//	FENCE
INLET	JUNCTION CHAMBER	:-	:	GRAVEL
ROUND	CATCH BASIN			SILT FENCE
STORM	MANHOLE			PROTECTIVE FENCE
DRAIN	ARROW	. • • • •	• • • •	GUARDRAIL
TLAREI	D END SECTION			LOT/UNIT
SANITA	ARY MANHOLE			CURB
© CLEAN	-OUT			TEMPORARY GRADING PERMI
<ul><li>BARRE</li></ul>	L			CONTOUR MAJOR
<del>⊸</del> SIGN		<del> 799</del> -		CONTOUR MINOR
∥⊜ PUSH	BUTTON			WATER EASMENT
■ HAND	HOLE			STORM EASEMENT
				SANITARY EASEMENT
				R.O.W.
				LIMITS OF CONSTRUCTION
				LIMIT OF GRADING
				STONE WALL
				DETECTABLE WARNING
				ASPHALT
				CONCRETE
		:	Δ. Δ. Δ	SIDEWALK
				SIDEWALK  TREE (DECIDUOUS)







TREE TO BE REMOVED (CONIFEROUS)



CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

SCALE : NTS

DRAWING No.

IMPROVEMENTS

LEGEND

### CONSTRUCTION NOTES:

- DRIVEWAYS AND ENTRANCES TO BUILDINGS, REAL PROPERTY, AND THE LIKE SHALL NOT BE BLOCKED EXCEPT FOR SHORT DURATIONS AND ONLY WHEN APPROVED BY THE ENGINEER. VEHICULAR AND PEDESTRIAN ACCESS SHALL BE MAINTAINED AT ALL TIMES TO ALL PROPERTIES. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE ALL NECESSARY DRIVEWAY CLOSURES WITH THE PROPERTY OWNER(S) AND RESIDENT(S) IN THE AREAS OF CONSTRUCTION.
- THE CONTRACTOR SHALL MAINTAIN REASONABLE ACCESS FOR RESIDENTS AND BUSINESSES TO ACCESS THEIR HOMES AND BUSINESSES AT ALL TIMES. A SAFE ACCESS PATH SHALL BE IDENTIFIED ALONG WITH VEHICLE PARKING IN THE EVENT THAT CONSTRUCTION ACTIVITIES INHIBIT VEHICULAR ACCESS TO HOMES AND BUSINESSES.
- THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES AND SERVICE LEADS ARE TO BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THIS SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN GENERAL CONDITIONS, MAX \$\_\_
- DURING NON-WORKING HOURS NO MORE THAN TEN (10) FEET OF TRENCH SHALL REMAIN OPEN. ANY OPEN TRENCH SHALL BE PROPERLY SECURED WITH PROTECTIVE FENCING. THIS WORK SHALL BE INCLUDED IN THE ITEMS OF WORK BEING UNDERTAKEN AND WILL NOT BE PAID FOR SEPARATELY.
- TRENCHES FOR NEW WATER AND/OR SANITARY SERVICES SHALL BE EXCAVATED TO MIOSHA AND CITY OF ANN ARBOR PUBLIC WORKS REQUIREMENTS.
- FOR THE INSTALLATION OF CORPORATIONS, OR ANY OTHER ACTIVITIES RELATED TO THE INSTALLATION OF WATER SERVICES, WATER MAIN SHUTDOWN, OR SIMILAR WORK, THE CONTRACTOR SHALL NOT RECEIVE ADDITIONAL COMPENSATION FOR DELAYS DUE TO THE SCHEDULING OF, OR COORDINATION WITH, CITY OF ANN ARBOR PUBLIC WORKS.
- THE CONTRACTOR SHALL BACKFILL TRENCHES IN ACCORDANCE WITH TRENCH DETAIL(S) SPECIFIED ON PLANS. THIS WORK SHALL BE INCLUDED IN THE ITEM OF WORK BEING PERFORMED.
- ALL DUCTILE IRON PIPE AND FITTINGS SHALL BE POLYETHYLENE WRAPPED PER ANSI/AWWA C105/A21.5.
- ALL FITTINGS, HYDRANTS, VALVES AND CASTINGS REMOVED DURING CONSTRUCTION SHALL BECOME THE PROPERTY OF THE CITY OF ANN ARBOR. THE CONTRACTOR SHALL COORDINATE PICKUP BY THE CITY OF ANN ARBOR FIELD OPERATIONS UNIT.
- 10. FLOUROPOLYMER COATED BOLTS ARE TO BE USED AT ALL MECHANICAL WATER MAIN JOINTS (HYDRANTS AND MEGALUG FITTINGS). SEE DETAILED SPECIFICATION ENTITLED "WATER MAIN AND APPURTENANCES" FOR ADDITIONAL INFORMATION.
- 11. THE CONTRACTOR SHALL CONSTRUCT, FLUSH, AND BACTERIOLOGICALLY TEST THE WATER MAIN PER DETAILED SPECIFICATION "WATER MAIN AND APPURTENANCES" AND AS APPROVED BY THE ENGINEER. ALL CHLORINATED WATER SHALL BE DISCHARGED DIRECTLY INTO AN APPROVED SANITARY SEWER. THE CONTRACTOR SHALL SUPPLY ALL NECESSARY HOSES, FITTINGS AND THE LIKE TO ACCOMPLISH THIS WORK.
- WATER MAIN FITTINGS, OTHER THAN THOSE SPECIFICALLY LISTED AS SEPARATE PAY ITEMS, WHICH ARE REQUIRED TO COMPLETE THE WORK, SUCH AS BLOW-OFF ASSEMBLIES, CONCRETE THRUST BLOCKS, SOLID SLEEVES AND MECHANICAL PLUGS, SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ASSOCIATED ITEMS OF
- THE CONTRACTOR SHALL PERFORM THE CONSTRUCTION OPERATIONS SUCH THAT POSTAL DELIVERY AND REFUSE PICKUP SERVICE SHALL BE MAINTAINED AT ALL TIMES.
- 14. WHERE CURB AND GUTTER, CURB, PAVEMENT OR SIMILAR ITEMS BECOME UNDERMINED DUE TO THE CONTRACTOR'S OPERATIONS, THEY SHALL BE REMOVED AND REPLACED AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S SOLE EXPENSE.
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUOUS MAINTENANCE OF THE TEMPORARY ROAD SURFACE AND SOIL EROSION CONTROL MEASURES WITHIN THE CONSTRUCTION AREA UNTIL THE COMPLETION OF THE PROJECT. THIS WORK SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ITEM OF WORK "GENERAL CONDITIONS, MAX.\_\_\_\_".
- 16. THE LOCATION OF MATERIAL STOCK PILES AND ON-SITE STAGING AREAS SHALL BE APPROVED BY THE ENGINEER. ALL MATERIAL STOCKPILES SHALL BE MAINTAINED SUCH THAT DRAINAGE AND SIGHT DISTANCES ARE NOT ADVERSELY IMPACTED. SOIL EROSION REQUIREMENTS SHALL APPLY TO ALL MATERIAL STOCKPILES.
- 17. FOR MAINLINE PAVING, THE WIDTH OF THE MAT FOR EACH PASS OF THE PAVER SHALL BE NOT LESS THAN 10.5' OR GREATER THAN 15', AS DIRECTED BY THE ENGINEER. THE ENGINEER WILL DIRECT THE LAYOUT OF THE LONGITUDINAL JOINTS DURING CONSTRUCTION.
- WHERE SEWER PIPES OF DIFFERENT SIZES OR MATERIALS ARE JOINED, FERNCO FLEXIBLE COUPLINGS WITH STAINLESS STEEL SHEAR RINGS SHALL BE USED. THE CONTRACTOR'S PURCHASE PRICE FOR THESE DEVICES, INCLUDING SHIPPING, SHALL BE PAID FOR AS AN EXTRA. PRIOR TO PAYMENT FOR THIS ITEM, THE CONTRACTOR SHALL SUBMIT RECEIPTS FOR THE ENGINEER'S REVIEW AND APPROVAL. ALL OTHER COSTS ASSOCIATED WITH THE INSTALLATION OF THESE DEVICES SHALL BE INCLUDED IN THE PAYMENT FOR THE SEWER.
- WHERE SEWER AND WATER MAIN ARE TO BE REMOVED & REPLACED OR 19. ADDED, ALL PIPE SHALL BE INSTALLED USING TRENCH DETAIL DETAILED IN THE SPECIFICATIONS OR SHOWN ON PLANS. BACKFILL FOR SEWER AND WATER CONSTRUCTION SHALL BE MDOT GRANULAR MATERIAL, CLASS II.
- 20. THE CONTRACTOR IS TO TAKE SPECIAL CARE TO PROTECT THE EXISTING WATER MAIN AND BE RESPONSIBLE FOR MAINTAINING CONSISTENT WATER SERVICE.
- CITY OF ANN ARBOR PUBLIC WORKS WILL INSTALL THE CORPORATION AND COPPER SERVICE LEAD(S) TO TRANSFER THE CONNECTION(S). IF AN EXISTING WATER SERVICE IS FOUND TO BE FAILING OR IS NOT COPPER, THE LEAD WILL BE REPLACED TO THE CURB BOX BY PUBLIC WORKS.

### **CONSTRUCTION NOTES (CON'T):**

- 22. SOME STORM SEWER MAY UNAVOIDABLY BECOME DAMAGED DURING CONSTRUCTION OR IT MAY BE DETERMINED BY THE ENGINEER THAT EXISTING STORM SEWER NEEDS TO BE REPLACED. IN EITHER CASE, THE ENGINEER MAY DIRECT THE SEWER TO BE REMOVED AND REPLACED. THE REMOVAL OF THE EXISTING SEWER AND/OR DRAINAGE STRUCTURES SHALL BE INCLUDED IN THE CONTRACT WORK ITEMS "SEWER, ANY SIZE OR DEPTH, REM" OR "DR STRUCTURE, ANY SIZE OR DEPTH, REM". AND THE REPLACEMENT SEWER SHALL BE INSTALLED AND PAID FOR AT THE CORRESPONDING CONTRACT UNIT PRICE, IF CONTAINED WITHIN THE CONTRACT, FOR THE VARIOUS TYPES AND SIZES OF SEWER TO BE
- 23. WHERE EXISTING SEWER AND/OR DRAINAGE STRUCTURES ARE TO BE REMOVED, THEY SHALL BE PROPERLY DISPOSED OF OFF-SITE AND THE EXCAVATION SHALL BE BACKFILLED WITH MDOT CLASS II GRANULAR MATERIAL, COMPACTED TO 95% OF ITS MAX. DRY DENSITY. THIS WORK SHALL BE INCLUDED IN THE CONTRACT ITEMS "SEWER, ANY SIZE OR DEPTH, REM" AND/OR DR STRUCTURE, ANY SIZE OR DEPTH, REM".
- 24. IF THE CONTRACTOR ENCOUNTERS EXISTING EDGE DRAIN(S) DURING CONSTRUCTION OF THE PROPOSED EDGE DRAINS, INLET LEADS, OR CATCH BASINS, IT SHALL BE CAPPED AT EACH END TO PREVENT MATERIAL FROM ENTERING THE PIPE. THE COST OF THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE PARTICULAR ITEM OF WORK BEING PERFORMED WHEN EXISTING EDGE DRAIN(S) ARE ENCOUNTERED.
- 25. EXISTING STREET NAME, GUIDE AND REGULATORY SIGNS, AND MAILBOXES WHICH CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED PRIOR TO CONSTRUCTION STORED IN A MANNER WHICH WILL PREVENT DAMAGE, AND RE-SET IN LOCATIONS AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN "GENERAL CONDITIONS, MAX\_\_\_
- 26. ALL STRUCTURES SHALL RECEIVE NEW CASTINGS, EITHER TYPE K. OR TYPE Q, OR AS SPECIFIED ON THE STANDARD CASTING SCHEDULE. THE EXISTING CASTINGS SHALL BE NEATLY STACKED ON-SITE IN A SINGLE LOCATION SO THAT THE CITY OF ANN ARBOR FORCES CAN RETRIEVE THEM AT A LATER DATE. THE CONTRACTOR SHALL ASSIST CITY FORCES BY LOADING THEM INTO CITY TRUCKS. ALL COSTS ASSOCIATED WITH STORING, STOCKPILING AND LOADING CASTINGS SHALL BE INCLUDED IN THE ITEM OF WORK "GENERAL CONDITIONS, MAX.\_\_\_" AND WILL NOT BE PAID FOR SEPARATELY.
- 27. ALL EXCAVATION REQUIRED FOR PROJECT GRADING WITHIN THE PROJECT LIMITS, INCLUDING PROPOSED PAVEMENT, DRIVE APPROACHES, SIDEWALK, AND SIDEWALK RAMPS SHALL BE INCLUDED IN "MACHINE GRADING, MODIFIED."
- 28. ALL CURB, SIDEWALK, AND DRIVEWAY APPROACH REMOVALS SHALL BE APPROVED BY THE ENGINEER BEFORE THE WORK IS PERFORMED. ALL CONCRETE AND BITUMINOUS MATERIALS SHALL BE SAW-CUT FULL-DEPTH AT THEIR REMOVAL LIMITS PRIOR TO REMOVAL. SAW-CUTTING WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ITEM OF WORK "MACHINE GRADING, MODIFIED."
- 29. "NO PARKING" SIGNS SHALL BE INSTALLED BY THE CONTRACTOR AT LOCATIONS AS APPROVED OR DIRECTED BY THE ENGINEER. ALL SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILED SPECIFICATIONS.
- 30. SAWED SEWER PIPE CONNECTIONS SHALL BE COUPLED WITH A FERNCO FLEXIBLE COUPLING AND A STAINLESS STEEL SHEAR RING.
- 31. ALL STRUCTURES SHALL RECEIVE NEW CASTINGS AS DIRECTED BY THE ENGINEER. AS SPECIFIED ON THE STANDARD CASTING SCHEDULE. THE EXISTING CASTINGS ARE THE PROPERTY OF THE CITY OF ANN ARBOR. THE CONTRACTOR SHALL DELIVER TO CITY OF ANN ARBOR PUBLIC WORKS FACILITY AT THE W.R. WHEELER SERVICE CENTER LOCATED AT 4251 STONE SCHOOL ROAD.
- 32. PAYMENT FOR DRAINAGE STRUCTURE SUMPS. WHERE SPECIFIED. SHALL BE INCLUDED IN THE PAYMENT FOR THE VARIOUS DRAINAGE STRUCTURE SIZES AND OR TYPES.
- 33. IN AREAS WHERE EDGE DRAIN CANNOT BE INSTALLED IN ACCORDANCE WITH CITY OF ANN ARBOR DETAIL SD-TD-11. THE EDGE DRAIN SHALL BE INSTALLED AT THE DEPTH AS INDICATED ON THE PLANS, OR AS DIRECTED BY ENGINEER. IN NO CASE SHALL THE EDGE DRAIN BE INSTALLED AT A GRADE LESS THAN 0.50% OR AT A DEPTH OF LESS THAN 2' BELOW TOP OF PROPOSED PAVEMENT.

### SOIL EROSION AND SEDIMENTATION CONTROL NOTES

- NOTIFY THE CITY OF ANN ARBOR SOIL EROSION CONTROL OFFICE 48 HOURS PRIOR TO BEGINNING WORK ON THE PROJECT. PHONE: 734-794-6265.
- 1. THE CONTRACTOR SHALL IMPLEMENT AND MAINTAIN THE SOIL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER AT ALL TIMES DURING CONSTRUCTION. ANY MODIFICATIONS OR ADDITIONS TO THE SOIL EROSION CONTROL MEASURES DUE TO CONSTRUCTION OR CHANGED CONDITIONS SHALL BE AS DIRECTED AND APPROVED BY THE ENGINEER.
- 2. ALL SOIL EROSION AND SEDIMENTATION CONTROL WORK SHALL CONFORM TO THE PERMIT REQUIREMENTS OF THE CITY OF ANN ARBOR, CHAPTER 55 ANN ARBOR UNIFIED DEVELOPMENT CODE, CITY OF ANN ARBOR STANDARDS DIVISION VII, THE LAWS OF THE STATE OF MICHIGAN, AND THE REQUIREMENTS OF
- 3. DAILY, OR AFTER ANY STORM EVENT, INSPECTIONS OF EROSION CONTROL MEASURES SHALL BE MADE BY THE CONTRACTOR. PERIODIC INSPECTIONS MAY BE MADE BY THE ENGINEER TO DETERMINE THE EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES. ANY NECESSARY CORRECTIONS SHALL BE MADE WITHOUT DELAY, AND WITHOUT ADDITIONAL COST TO THE CITY OF ANN ARBOR.
- 4. EROSION AND SEDIMENTATION FROM WORK ON THE SITE SHALL BE CONTAINED ON THE SITE AND NOT BE ALLOWED TO COLLECT ON ANY OFF-SITE AREAS, ROADWAYS OR WATERWAYS.
- 5. ALL MUD/SOIL TRACKED ONTO ROADWAYS FROM THE SITE DUE TO CONSTRUCTION, SHALL BE PROMPTLY REMOVED BY THE CONTRACTOR. IF SO ORDERED, THE CONTRACTOR SHALL PROVIDE AND OPERATE A VACUUM-TYPE STREET SWEEPER, AT NO ADDITIONAL COST TO THE CITY OF ANN ARBOR.
- 6. RESTORATION OF ALL DISTURBED AREAS, INCLUDING PLACEMENT OF TOPSOIL, SEED, FERTILIZER AND MULCH AND/OR SOD SHALL BE PERFORMED WITHIN FIVE (5) DAYS OF THE COMPLETION OF FINAL
- 7. CONSTRUCTION OPERATIONS SHALL BE SCHEDULED AND PERFORMED SO THAT PREVENTATIVE SOIL EROSION CONTROL MEASURES ARE IN PLACE PRIOR TO EXCAVATION IN CRITICAL AREAS AND TEMPORARY STABILIZATION MEASURES ARE IN PLACE IMMEDIATELY FOLLOWING BACKFILLING OPERATIONS.
- 8. SPECIAL PRECAUTIONS WILL BE TAKEN IN THE USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION.
- 9. PROPER DUST CONTROL SHALL BE MAINTAINED DURING CONSTRUCTION BY USE OF WATER TRUCKS AND/OR DUST PALLATIVE AS REQUIRED.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY SOIL EROSION CONTROL MEASURES AND REMOVAL OF SOME MEASURES UPON AUTHORIZED COMPLETION OF THE PROJECT. FINAL COMPLETION OF PROJECT WILL NOT BE AUTHORIZED UNTIL ALL SITE WORK AND UTILITY CONSTRUCTION IS COMPLETE AND ALL SOILS ARE STABILIZED.
- 11. THE CONTRACTOR SHALL NOT GRADE INTO ADJACENT PROPERTIES. SILT AND PROTECTIVE FENCE SHALL BE INSTALLED AND MAINTAINED TO PREVENT GRADING, EROSION AND SEDIMENTATION INTO THE ADJACENT PROPERTIES.
- 12. TREE PROTECTION FENCING MUST REMAIN INTACT UNTIL RESTORATION OF THE SITE IS COMPLETE.

### **SEQUENCE OF EROSION CONTROL MEASURES:**

1. THE CONTRACTOR IS TO SUBMIT TO THE ENGINEER, A SEQUENCE OF CONSTRUCTION WITH RESPECT TO THE SOIL EROSION CONTROL MEASURES FOR REVIEW, COMMENT AND APPROVAL. THIS SCHEDULE IS TO INCLUDE INSPECTION AND REPAIR OF ALL TEMPORARY EROSION CONTROL MEASURES DAILY AND WITHIN 24 HOURS OF A STORM EVENT.

### SAMPLE SOIL EROSION AND SEDIMENTATION CONTROL INSTALLATION MINIMUM REQUIREMENTS:

- 1.1. INSTALL SILT FENCE, TREE PROTECTION FENCING, MUD MATS, INLET FILTERS ON EXISTING DRAINAGE FEATURES, AND ALL OTHER TEMPORARY SOIL EROSION CONTROLS, PRIOR TO ANY CLEARING OR EARTH MOVING OPERATION.
- 1.2. STRIP AND STOCKPILE TOPSOIL. STABILIZE STOCKPILE AS REQUIRED.
- 1.3. INSTALL WATER MAINS, STORM AND SANITARY SEWERS, AND OTHER ENCLOSED DRAINAGE FEATURES NEW INLET FILTERS SHALL BE INSTALLED IMMEDIATELY FOLLOWING INSTALLATION OF NEW DRAINAGE
- 1.4. PERFORM MACHINE GRADING OPERATIONS AND CONSTRUCT PAVEMENTS (MAINLINE, SIDEWALKS,
- 1.5. CONTINUALLY MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES, AS REQUIRED TO ALLOW DRAINAGE AND SEDIMENT REMOVAL. REMOVE ANY ACCUMULATED SEDIMENT IMMEDIATELY.
- 1.6. COMPLETE ALL FINE GRADING.
- 1.7. TEMPORARY SEED AND INSTALL EROSION CONTROL BLANKET IN ALL DISTURBED AREAS.
- 1.8. REFER TO PLANS AND SPECIFICATIONS FOR PERMANENT SITE STABILIZATION.
- 1.9. CLEAN OUT STORM SEWER SYSTEMS.
- 1.10. REMEDY ANY NOTED DEFECTS TO THE SATISFACTION OF THE CITY OF ANN ARBOR'S SOIL EROSION AND SEDIMENTATION CONTROL OFFICIAL.
- 1.11. ALL TEMP. SOIL EROSION CONTROL MEASURES MUST BE REMOVED, WITH ENGINEERS APPROVAL, PRIOR TO FINAL INSPECTION

NOTE: THIS SEQUENCE IS FOR INFORMATION ONLY. IT IS INTENDED TO SHOW THE SEQUENCE OF CONSTRUCTION WITH RESPECT TO THE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING THEIR OWN DETAILED CONSTRUCTION SEQUENCE AND SCHEDULE TO THE ENGINEER FOR REVIEW, COMMENT, AND APPROVAL.

### **TEMPORARY SEEDING:**

- 1. SEED IN ACCORDANCE WITH PROJECT DRAWINGS AND SPECIFICATIONS.
- 2. ANY DISTURBED AREA NOT PAVED, SEEDED, MULCHED, SODDED OR BUILT UPON BY NOVEMBER 15TH OR JUNE 30TH IS TO BE TEMPORARILY STABILIZED PER SPECIFICATIONS.

THE ESTIMATED COST OF SOIL EROSION AND SEDIMENTATION CONTROL MEASURES, TOPSOIL, SEEDING, AND MULCH = \$51,000

- ESTIMATE OF EXCAVATION AND FILL FROM EXISTING TO FINAL GRADE: EXCAVATION = 50 CY, FILL = 25 CY
- ON SITE SOILS PER THE USDA SOIL SURVEY OF WASHTENAW COUNTY, MICHIGAN: • Sb - SEBEWA LOAM - IN DEPRESSION AREAS, BROAD LOW-LYING AREA, AND DRAINAGEWAYS OF
- OUTWASH PLAINS, VALLEY TRAINS, AND TERRACES. SLOPE IS 0% TO 2%.
- FOX SANDY LOAM IN UPLAND AREAS AND ON OUTWASH PLAINS, KAMES, VALLEY TRAINS, TERRACES, AND MORAINES. SLOPES ARE UNIFORM OR SHORT AND COMPLEX. SLOPE IS 2% TO
- BnF BOYER LOAMY SAND IN OUTWASH PLAINS, VALLEY TRAINS, KAMES, BEACH RIDGES, RIVER
- TERRACES, LAKE TERRACES, DELTAS, AND MORAINES. SLOPE IS 25% TO 50%. - BOYER LOAMY SAND - IN OUTWASH PLAINS, VALLEY TRAINS, KAMES, BEACH RIDGES, RIVER TERRACES, LAKE TERRACES, DELTAS, AND MORAINES. SLOPE IS 1% TO 6%.

### WATER MAIN CONSTRUCTION NOTES

- 1. SEE EROSION CONTROL SHEETS FOR DETAILS ON PLACEMENT, MAINTENANCE, AND REMOVAL OF EROSION CONTROL ITEMS.
- THE CONTRACTOR SHALL CAREFULLY PROTECT FROM DAMAGE OR INJURY DURING CONSTRUCTION OPERATIONS ALL UTILITIES, SITE FEATURES, LANDSCAPING, AND OTHER ITEMS NOT DESIGNATED FOR REMOVAL OR ABANDONMENT, PAYMENT FOR PROTECTION OF UTILITIES INCLUDED IN "GENERAL CONDITIONS, MAX". EXISTING FACILITIES NOT DESIGNATED FOR REMOVAL OR ABANDONMENT, BUT WHICH ARE DAMAGED BY THE CONTRACTOR'S OPERATION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT HIS SOLE EXPENSE, AS DETERMINED BY THE ENGINEER.
  - THE EXISTING UTILITIES SHOWN ON THESE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AS OBTAINED THROUGH SURVEYS AND/OR EXISTING PLANS. THIS INFORMATION DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY TO BE SATISFIED AS TO ITS ACCURACY AND THE LOCATION OF EXISTING UTILITIES. IF STORM OR WATERMAINS CROSS OTHER UTILITIES, CONTACT THEIR RESPECTIVE OWNERS FOR INFORMATION ON HOW TO PROCEED. PAYMENT FOR THE COORDINATION EFFORTS AND ASSOCIATED ITEMS SHALL BE INCLUDED IN ASSOCIATED PROPOSED STORM OR WATERMAIN ITEMS AND SHALL NOT BE PAID FOR SEPARATELY.
- 4. THE CONTRACTOR SHALL CAREFULLY PROTECT FROM DAMAGE OR INJURY THE EXISTING WATER MAIN DURING CONSTRUCTION OPERATIONS. ANY DAMAGE TO THIS FACILITY BY THE CONTRACTOR'S OPERATION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT HIS EXPENSE, AS DETERMINED BY THE ENGINEER. PAYMENT FOR PROTECTION OF THE EXISTINGWATER MAIN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ITEM OF WORK "GENERAL CONDITIONS,
- 5. THE CONTRACTOR SHALL NOT REMOVE OR DAMAGE EXISTING SANITARY SEWER OR WATER MAIN LEADS FOR EASE OF CONSTRUCTING OTHER ASPECTS OF WORK. THE CONTRACTOR SHALL CAREFULLY PROTECT ALL LEADS FROM DAMAGE OR INJURY.
- 6. THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO THE CITY OF ANN ARBOR PUBLIC SERVICES DEPARTMENT STANDARD SPECIFICATIONS WHICH ARE INCLUDED BY REFERENCE. THE OMISSION OF ANY CURRENT STANDARD DETAIL DOES NOT RELIEVE THE CONTRACTOR FROM THE REQUIREMENT. THE WORK SHALL BE PERFORMED IN COMPLETE CONFORMANCE WITH CURRENT PUBLIC SERVICE DEPARTMENT STANDARD SPECIFICATIONS AND DETAILS.
- 7. ALL WATER MAIN SHALL BE PRESSURE CLASS 350 OR THICKNESS CLASS 52 DUCTILE IRON WATER MAIN, CEMENT-LINED (DOUBLE THICKNESS), WITH POLYWRAP UNLESS NOTED OTHERWISE.
- RESTRAINED JOINT SYSTEMS FOR WATER MAIN SHALL BE UTILIZED WHERE INDICATED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. RESTRAINED JOINT GASKET SYSTEMS ARE TO BE USED. (FIELD-LOK 350 BY U.S. PIPE, FAST-GRIP BY AMERICAN DUCTILE IRON PIPE, OR APPROVED EQUAL).
- 9. ALL WATER MAIN TO HAVE 5.5 FEET OF COVER, MAINTAIN A MINIMUM OF 18-INCH VERTICAL CLEARANCE FOR STORM AND SANITARY CROSSINGS AND A MINIMUM OF 12-INCH VERTICAL CLEARANCE WITH ALL OTHER UTILITIES.
- 10. UNLESS OTHERWISE NOTED, THE CONTRACTOR SHALL UTILIZE STANDARD PIPE DEFLECTIONS FOR FOLLOWING THE PROPOSED ALIGNMENT.
- 11. NEW FIRE HYDRANTS SHALL BE EJIW 5BR-250 WITH 5-INCH STORZ CONNECTION, 1-3/8-INCH PENTAGON OPERATING NUT, 3-3/8-INCH AA PUMPER CONNECTION, PUSH-ON JOINT WITH NO BARREL
- 12. FIRE HYDRANT ASSEMBLIES SHALL INCLUDE ALL NECESSARY HYDRANT EXTENSIONS, THRUST BLOCKS, PIPE AND FITTINGS, INCLUDING ADJUSTMENT OF THE COMPANION VALVE. FIRE HYDRANT ASSEMBLY INCLUDES 6-INCH COMPANION VALVE LOCATED THREE FEET FROM THE HYDRANT.
- 13. ALL WATER MAIN TRENCH BACKFILL SHALL BE MDOT CLASS II GRANULAR MATERIAL (SEE UTILITY TRENCH TYPE I DETAIL).
- 14. CONNECTIONS TO THE EXISTING WATER MAIN SHALL NOT BE MADE UNTIL THE NEW MAIN HAS BEEN SUCCESSFULLY TESTED AND HAS PASSED ALL HYDROSTATIC AND BACTERIOLOGICAL TESTING. FINAL CONNECTIONS SHALL BE COORDINATED WITH THE ENGINEER.
- 15. THE CONTRACTOR SHALL PERFORM ALL WATER SYSTEM SHUT DOWNS AFTER APPROPRIATE NOTIFICATION TO THOSE AFFECTED AND APPROVAL HAS BEEN GRANTED BY THE ENGINEER.
- 16. WATER SERVICES SHOWN REPRESENT THE BEST INFORMATION AVAILABLE BASED ON RECORDS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE CITY IN LOCATING, VERIFYING AND RECONNECTING ALL EXISTING ACTIVE SERVICES.
- 17. ALL LINE STOP LOCATIONS SHALL BE DETERMINED BY THE CITY ENGINEER AS NEEDED. THIS ITEM OF WORK SHALL BE PAID FOR AS "LINE STOP, DUCTILE/CAST IRON PIPE, \_-INCH."

ANN ARBOR S SERVICES HURON STREET BOX 8647 BR, MI 48107-8647 -794-6410



& WRIGHT

PONTIAC, SWIFT, MOORE, INFRASTRUCTURE IMPRONOTES

SERVICE

ARB ANN SHEET No.

4 OF 52

PROJECT BENCHMARKS BM # | ELEV | DESCRIPTION PK NAIL NORTHEAST SIDE OF UTILITY POLE, SOUTH SIDE SWIFT, 2ND POLE SOUTHWEST OF INTERSECTION OF SWIFT AND WRIGHT PK NAIL EAST SIDE OF UTILITY POLE AT NORTHWEST CORNER PONTIAC TRAIL & 51 812.11 LONGSHORE BETWEEN HYDRANT AND RAILROAD PK NAIL SOUTHWEST SIDE OF UTILITY POLE AT NORTHEAST CORNER MOORE & 784.73 BROADWAY

AREA OF PROPOSED DISTURBANCE = 1.40 ACRES


POST CONSTRUCTION


= 1.39 ACRES


IMPERVIOUS PROJECT AREA


PRIOR TO CONSTRUCTION


= 1.39 ACRES














SD-TD-1A

DATE 11/6/92

SCALE N.T.S.









SHEET No.


PONTIAC, SWIFT, MOORE, & WRIGHT INFRASTRUCTURE IMPROVEMENTS


DETAILS 1


5 OF 52












SCALE N.T.S. DATE 11/6/92



REV. NO. DATE

DRAWN BY CHECKED BY

DRAWING NO.

SD-R-9

SIDEWALK CROSS SECTION

CH. CSS


SCALE N.T.S. DATE 11/06/92


**PUBLIC SERVICES** 


P.O. BOX 8647

ANN ARBOR, MI 48107-8647


734-794-6410









SHEET No. 6 OF 52








### **CASTING SCHEDULE**

TYPE OF CASTING	MDOT DESIGNATION	EJ CASTING NO <u>.</u>	NEENAH CASTING NO.
STORM MANHOLE AND WATER GATE WELL FRAME AND COVER	Q	1040Z W/1040A LOGO COVER*	R-1642 W/TYPE C COVER*
BARRIER CURB INLET FRAME AND COVER	К	7045Z W/7050 T2 BACK W/7045 M1 GRATE	R-3031-B W/TYPE S GRATE
BARRIER CURB LARGE CAPACITY INLET FRAME AND COVER	К	7035Z W/7030 T6 BACK W/7030 M2 GRATE	N/A
GUTTER INLET FRAME AND COVER	R	5080Z W/TYPE 5000M2 GRATE	R-3448C, W/TYPE S GRATE
GUTTER LARGE CAPACITY INLET FRAME AND COVER	R	7034Z W/7034 M GRATE	N/A
MOUNTABLE CURB INLET ASSEMBLY	С	7045Z W/ 7060 T1 BACK W/ 7045 M1 GRATE	N/A
YARD DRAIN (BEE HIVE) FRAME AND COVER	E	1040Z, W/1040 02 GRATE	R-2560-E1
WATER VALVE BOX ASSEMBLY IN PAVEMENT	MON BOX	PLEASE SEE BELOW	N/A
MONUMENT BOX ASSEMBLY	MON BOX	8360Z W/ 8360A3 COVER	N/A
SUGGESTED MONUMENT BOX	MON BOX	2966Z W/ 2965A COVER	
SUGGESTED SANITARY MANHOLE FRAME AND COVER	Q	1040-1ZPT W/ 1040AGS LOGO COVER*  IN FLOOD PRONE AREAS: 1040-ZPT W/ 1040AGSPT	

\*EACH COVER SHALL HAVE "SANITARY", "STORM," OR "WATER" CAST IN THE SURFACE, WHICHEVER IS APPLICABLE. SANITARY SEWER COVERS FOR FLOOD PRONE AREAS SHALL BE UTILIZED WHERE SHOWN ON THE PLANS OR AS DIRECTED BY THE PSAA. FRAMES AND COVERS MUST HAVE MACHINED BEARING SURFACES.




www.a2gov.org


DRAWING NO.

SD-W-2

CH. CSS

SCALE N.T.S. DATE 11/06/92





DR. BY DF CH. BY CSS DRAWING NO.

SCALE NONE DATE 11-6-92

<sup>0</sup>

SD-GU-7

SHEET NO. \_\_\_\_\_OF \_\_

 WATER VALVE BOX ASSEMBLY IN PAVEMENT \*4" TO 6" VALVES: BASE #4 W/ 8550.8560.6800 SET \*8" TO 12" VALVES: BASE #6 W/ 8550,8560, 6800 SET


\*16"AND LARGER: BASE #160 W/ 8550,8560, 6800 SET


PONTIAC, SWIFT, MOORE, & WRIGHT INFRASTRUCTURE IMPROVEMENTS


DETAILS 3 - PUBLIC SERVICES - ENGINEERING


CITY OF ANN ARBOR


SHEET No.


















INFILTRATION WET/DRY WELL DETAIL

- PUBLIC SERVICES - ENGINEERING
PONTIAC, SWIFT, MOORE, & WRIGHT
INFRASTRUCTURE IMPROVEMENTS
DETAILS 4 CITY OF ANN ARBOR

ın\d1253461\CDT—PLTS—Ann Arbor Details.dwq Dwq Created: 27—Mar—23 — \_a2 standard bw.stb — Plot Date: 28—Ma

SHEET No.



				BOTTOM ELEV: 771.41
	EXISTI	NG W	ATER S	STRUCTURE TABLE
AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
01-00225	GVWD 50445	777.48	LINIZ	CONDITION: UTO TRAFFIC
01-00225	GV WD 50445	///.48	UNK	BOTTOM ELEV: UNK
				CONDITION: GOOD PRECAST FOD NPV CONC
No GIS ID	GVWD 50388	780.71	36"	BOX AT BOTTOM?
				BOTTOM ELEV: 774.41

WIRE/CONDUIT SIZE: 3 IN

WIRE/CONDUIT DIRECTION(S): NW, SE, W WIRE/CONDUIT DEPTH: 11.7 FT BOTTOM ELEV: 765.38 CONDITION: FAIR BRICK LOT WIRES LOW-7.40 HIGH-4.00 DUCT BANK: Y WIRE/CONDUIT SIZE: 3 IN

WIRE/CONDUIT DIRECTION(S): NW, SE, W WIRE/CONDUIT DEPTH: 7.4 FT BOTTOM ELEV: 768.25 CONDITION: FAIR BRICK LOW WIRE-8.00 HIGH WIRE-6.00

> DUCT BANK: Y WIRE/CONDUIT SIZE: 3 IN

WIRE/CONDUIT DIRECTION(S): NW, SE, NE WIRE/CONDUIT DEPTH: 8 FT BOTTOM ELEV: 766.86 CONDITION: FAIR BRICK LOW WIRE-10.90 HIGH WIRE-5.00 DUCT BANK: Y WIRE/CONDUIT SIZE: 3 IN

WIRE/CONDUIT DIRECTION(S): NW, SE

WIRE/CONDUIT DEPTH: 10.9 FT BOTTOM ELEV: 764.72 CONDITION: UTO TRAFFIC WIRE/CONDUIT SIZE: UNK

WIRE/CONDUIT DIRECTION(S): UNK WIRE/CONDUIT DEPTH: UNK

BOTTOM ELEV: UNK

ELMH-50408 778.18 72"

ELMH-50410 777.25 72"

ELMH-50412 776.46 72"


ELMH-50415 777.12 72"


ELMH-50444 777.16 UNK

AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
88-57447	CBS 50390	782.35	24"	CONDITION: COMBINED WITH PT#50391
00-3/44/	CB3 30390	762.33	24	BOTTOM ELEV: UNK
				CONDITION: POOR BRICK N BLOCK FOD COMBINED WITH PT#50390
88-57446	CBS 50391	782.46	24"	12 IN RCP SW, INV 779.76
				BOTTOM ELEV: 779.76
				CONDITION: POOR CONC
88-57448	CBS 50392	781.88	12"	12 IN RCP ELBOW W, INV 778.48
				BOTTOM ELEV: 778.48
				CONDITION: FAIR CLAY
88-57399	CBS 50396	808.42	12"	12 IN CLAY ELBOW N, INV 805.67
				BOTTOM ELEV: 805.67
				CONDITION: FAIR CONC FOD FOW
88-51133	CBS 50411	776.20	24"	12 IN RCP NE, INV 773.10
00-31133	CB3 50411	776.20	24	12 IN RCP SE, INV 771.40
				BOTTOM ELEV: 770.90
				CONDITION: FAIR PRECAST FOD
88-51134	CBS 50416	777.16	24"	12 IN PVC E, INV 775.26
				BOTTOM ELEV: 775.06
				CONDITION: FAIR PRECAST FOD FOW
				12 IN RCP W, INV 774.42
92-62590	CBS 50417	777.12	36"	12 IN PVC NE, INV 774.72
				12 IN RCP S, INV 771.72
				BOTTOM ELEV: 771.42

AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
				CONDITION: FAIR BRICK
				12 IN RCP N, INV 776.23
				12 IN RCP NW, INV 776.23
92-61933	STMH 50387	781.38	48"	12 IN RCP/CLAY W, INV 777.23
				12 IN RCP SE, INV 775.78
				RCP IN E 5.15, INV UNK
				BOTTOM ELEV: 775.78
				CONDITION: GOOD BRICK N BLOCK
92-63278	STMH 50389	784.02	36"	12 IN RCP S, INV 779.27
				12 IN RCP NE, INV 779.32
				BOTTOM ELEV: 779.27
				CONDITION: FAIR BRICK
				12 IN RCP NW, INV 773.98
92-61932	STMH 50409	777.68	24"	12 IN RCP SE, INV 773.88
				8 IN CLAY NE, INV 774.78
				BOTTOM ELEV: 774.88
				CONDITION: FAIR PRECAST
92-61924	STMH 50414	777.05	36"	12 IN RCP NW, INV 773.45
32-01324	311011130414	777.03	36	12 IN RCP W, INV 773.40
				BOTTOM ELEV: 774.05

		PROJECT BENCHMARKS	ANN ARBOR	
BM#	ELEV	DESCRIPTION	OF AI	
50	807.99	PK NAIL NORTHEAST SIDE OF UTILITY POLE, SOUTH SIDE SWIFT, 2ND POLE SOUTHWEST OF INTERSECTION OF SWIFT AND WRIGHT		
51	812.11	PK NAIL EAST SIDE OF UTILITY POLE AT NORTHWEST CORNER PONTIAC TRAIL & LONGSHORE BETWEEN HYDRANT AND RAILROAD	SCALE	
52	784.73	PK NAIL SOUTHWEST SIDE OF UTILITY POLE AT NORTHEAST CORNER MOORE & BROADWAY	SHEET 9	No. <b>OF</b>





### **EXISTING SANITARY SEWER STRUCTURE TABLE**


AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
				CONDITION: FAIR PRECAST
71-67952		811.36	48"	10 IN CLAY NNE, INV 802.46
	SMH 50382			10 IN CLAY SSW, INV 802.56
				4 IN CLAY WSW, INV 804.16
				BOTTOM ELEV: 802.51
				CONDITION: GOOD PRECAST
71-67953	SMH 50383	813.01	60"	10 IN CLAY NNE, INV 804.21
				10 IN CLAY BULKHEAD? S, INV 804.21
				6 IN CLAY STRAIGHT VERTICAL, INV 805.96
				BOTTOM ELEV: 804.31

### EXISTING ELECTRICAL STRUCTURE TABLE

STRUCTURE #	RIM	SIZE	CONDITION AND CONNECTIONS
			CONDITION: FAIR BRICK LARGE VAULT
51.0 M.L. 50204			DUCT BANK: Y
	910 56	120"	WIRE/CONDUIT SIZE: 3 IN
ELMH-50381	810.56		WIRE/CONDUIT DIRECTION(S): N, S
			WIRE/CONDUIT DEPTH: 5 FT
			BOTTOM ELEV: 801.36
			CONDITION: FAIR BRICK LARGE VAULT
ELMH-50384			DUCT BANK: Y
	810.62		WIRE/CONDUIT SIZE: 3 IN
	810.62		WIRE/CONDUIT DIRECTION(S): NE, SE
			WIRE/CONDUIT DEPTH: 5.5 FT
			BOTTOM ELEV: 801.62

		PROJECT BENCHMARKS
3M #	ELEV	DESCRIPTION
50	807.99	PK NAIL NORTHEAST SIDE OF UTILITY POLE, SOUTH SIDE SWIFT, 2ND POLE SOUTHWEST OF INTERSECTION OF SWIFT AND WRIGHT
51	812.11	PK NAIL EAST SIDE OF UTILITY POLE AT NORTHWEST CORNER PONTIAC TRAIL & LONGSHORE BETWEEN HYDRANT AND RAILROAD
52	784.73	PK NAIL SOUTHWEST SIDE OF UTILITY POLE AT NORTHEAST CORNER MOORE & BROADWAY

	E CITY OF ANN ARBOR	BOR - PUBLIC SERVICES - ENGINEERING
10 OF	SCALE PLAN: 1"=20'	PONTIAC, SWIFT, MOORE, & WRIGHT
52	DRAWING No.	INTRASTRUCTURE IMPROVEMENTS
	2022-032-10	EXISTING CONDITIONS & ALIGNMENT PLAN - SWIFT ST STA 5+50 TO





09-09-21-306-013 (BRENT L. ROBERTSON TRUST)

	EXISTI	NG ST	ORM S	STRUCTURE TABLE
AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
				CONDITION: FAIR CLAY
88-57399	CBS 50396	808.42	12"	12 IN CLAY ELBOW N, INV 805.67
				BOTTOM ELEV: 805.67
				CONDITION: POOR BRICK N BLOCK FOD
88-57446	CBS 50391	782.46	24"	COMBINED WITH PT#50390
88-37440	CB3 30391	702.40	24	12 IN RCP SW, INV 779.76
				BOTTOM ELEV: 779.76
88-57447	CBS 50390	782.35	24"	CONDITION: COMBINED WITH PT#50391
	CB3 30390	702.33	24	BOTTOM ELEV: UNK
				CONDITION: POOR CONC
88-57448	CBS 50392	781.88	12"	12 IN RCP ELBOW W, INV 778.48
				BOTTOM ELEV: 778.48
				CONDITION: FAIR CLAY
88-57449	CBS 50386	781.03	12"	12 IN CLAY ELBOW E, INV 778.23
				BOTTOM ELEV: 778.23
				CONDITION: FAIR BRICK
		781.38	48"	12 IN RCP N, INV 776.23
				12 IN RCP NW, INV 776.23
92-61933	STMH 50387			12 IN RCP/CLAY W, INV 777.23
				12 IN RCP SE, INV 775.78
				RCP IN E 5.15, INV UNK
				BOTTOM ELEV: 775.78
				CONDITION: GOOD BRICK N BLOCK
92-63278	STMH 50389	784.02	36"	12 IN RCP S, INV 779.27
92-03210	2110111 20202	704.02	30	12 IN RCP NE, INV 779.32
				BOTTOM ELEV: 779.27

SEE SHEET9 FOR SWIFT STREET

### **EXISTING SANITARY STRUCTURE TABLE**


3+00

2+00 **PONTIAC TRAIL** 

(66' ROW)

AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
				CONDITION: FAIR BRICK
				12 IN CLAY SW, INV 768.72
71-71768	SMH 50393	786.07	48"	12 IN CLAY E, INV 768.57
				4 IN PVC S, INV 779.97
				BOTTOM ELEV: 768.57

_		PROJECT BENCHMARKS
BM#	ELEV	DESCRIPTION
50	807.99	PK NAIL NORTHEAST SIDE OF UTILITY POLE, SOUTH SIDE SWIFT, 2ND POLE SOUTHWEST
		OF INTERSECTION OF SWIFT AND WRIGHT
51	812.11	PK NAIL EAST SIDE OF UTILITY POLE AT NORTHWEST CORNER PONTIAC TRAIL & LONGSHORE BETWEEN HYDRANT AND RAILROAD
52	784.73	PK NAIL SOUTHWEST SIDE OF UTILITY POLE AT NORTHEAST CORNER MOORE & BROADWAY



EXISTING ELECTRICAL STRUCTURE TABLE
EXISTING LELCTHICAL STREET TABLE

STRUCTURE #	# RIM	SIZE	CONDITION AND CONNECTIONS
			CONDITION: FAIR CONC
			DUCT BANK: Y
FLN4LL F0403	000 57	72"	WIRE/CONDUIT SIZE: 3 IN
ELMH-50403	808.57	/2	WIRE/CONDUIT DIRECTION(S): NE, SW
			WIRE/CONDUIT DEPTH: 6.9 FT
			BOTTOM ELEV: 797.82
			CONDITION: FAIR BRICK
	792.43	43 72"	DUCT BANK: Y
FINALL FO422			WIRE/CONDUIT SIZE: 3 IN
ELMH-50432			WIRE/CONDUIT DIRECTION(S): NW, S
			WIRE/CONDUIT DEPTH: 4.6 FT
			BOTTOM ELEV: 784.93
	780.73	80.73 UNK	CONDITION: UTO TRAFFIC
			WIRE/CONDUIT SIZE: UNK
ELMH-50465			WIRE/CONDUIT DIRECTION(S): UNK
			WIRE/CONDUIT DEPTH: UNK
			BOTTOM ELEV: UNK
			CONDITION: UTO TRAFFIC
			WIRE/CONDUIT SIZE: UNK
ELMH-50466	782.52	782.52 UNK	WIRE/CONDUIT DIRECTION(S): UNK
			WIRE/CONDUIT DEPTH: UNK
			BOTTOM ELEV: UNK

### **EXISTING STORM STRUCTURE TABLE**

EXISTING CTCHM CTHOCTCHE TABLE						
AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS		
				CONDITION: FAIR PRECAST FOD FOW		
00 57242	CBS 50424	782.00	18"	12 IN RCP SE, INV 778.15		
88-57342	CBS 50424	782.00	18	12 IN RCP NE, INV 778.30		
				BOTTOM ELEV: 777.80		
				CONDITION: FAIR BRICK N BLOCK FOD FOW		
88-57378	CBS 50425	788.20	18"	12 IN RCP S, INV 783.80		
				BOTTOM ELEV: 783.00		
				CONDITION: FAIR BRICK N BLOCK FOD FOW		
88-57379	CBS 50426	787.90	24"	12 IN RCP NNW, INV 785.90		
				BOTTOM ELEV: 785.40		
88-57380	CBS 50427	787.33	24"	CONDITION: FAIR BRICK N BLOCK		
				12 IN RCP SSE, INV 783.83		
00-37300	CB3 30427	767.33	24	12 IN CLAY WSW, INV 783.63		
				BOTTOM ELEV: 783.73		
				CONDITION: FAIR PRECAST FOD FOW		
88-57003	CBS 50428	786.33	18"	12 IN PVC NE, INV 784.03		
88-37003	CD3 30428	760.33	10	12 IN PVC SW, INV 784.13		
				BOTTOM ELEV: 783.43		
				CONDITION: FAIR PRECAST FOD FOW		
				12 IN RCP N, INV 776.92		
88-57343	CBS 50462	781.17	24"	12 IN RCP NE, INV 775.02		
				12 IN RCP NW, INV 775.07		
				BOTTOM ELEV: 774.47		
				CONDITION: FAIR BRICK N BLOCK		
88-57344	CBS 50463	781.21	24"	12 IN RCP SW, INV 775.06		
				BOTTOM ELEV: 775.01		

### **EXISTING STORM STRUCTURE TABLE**

	AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
					CONDITION: FAIR BRICK N BLOCK FOD
	No GIS ID	STMH 50402	807.87	24"	12 IN RCP N, INV 805.07
	עו פוט טאו	311VIFI 30402	807.87	24	12 IN RCP SW, INV 803.87
					BOTTOM ELEV: 803.87
					CONDITION: FAIR BRICK FOD ABANDONED
					WATER LINE PRESENT TOP-4.80
					12 IN RCP BULKHEAD NNW, INV 802.44
					12 IN CLAY WNW, INV 799.94
	92-61914	STMH 50406	806.94	48"	12 IN CLAY S, INV 799.44
					12 IN CLAY N, INV 799.94
					CLAY IN NE 4.3, INV 798.94
					N S DEPTH TO TOP IN 5.2
					BOTTOM ELEV: 799.44
					CONDITION: POOR BRICK N BLOCK
	92-63276	STMH 50422	781.18	24"	15 IN RCP N, INV 777.68
					15 IN RCP S, INV 777.68
					12 IN RCP W, INV 777.68
					BOTTOM ELEV: 777.48
					CONDITION: FAIR BRICK
		STMH 50429	783.27	36"	15 IN RCP NW, INV 779.37
	92-61921				15 IN RCP SE, INV 779.32
	32 01321				12 IN RCP N, INV 779.87
					12 IN RCP BULKHEAD E, INV 780.57
					BOTTOM ELEV: 780.47
					CONDITION: FAIR PRECAST
					12 IN CLAY N, INV 782.04
	92-61915	STMH 50431	787.44	36"	12 IN CLAY E, INV 782.44
	32 01313	31IVIH 50431	707.11		12 IN CLAY S, INV 781.94
					12 IN CLAY W, INV 782.94
					BOTTOM ELEV: 782.44
	92-63276	STMH 50464	781.03	UNK	CONDITION: UTO TRAFFIC
	92-632/6	311011130404	/61.03	CIVIC	BOTTOM ELEV: UNK

### **EXISTING SANITARY STRUCTURE TABLE**

AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
				CONDITION: FAIR BRICK
				12 IN CLAY NE, INV 798.52
71-71761	SMH 50405	807.42	48"	12 IN CLAY SE, INV 798.42
				12 IN CLAY W, INV 798.72
				BOTTOM ELEV: 798.92
				CONDITION: FAIR BRICK
	SMH 50430	786.81	36"	12 IN RCP NNW, INV 779.51
71-71759				12 IN RCP SSE, INV 779.31
				12 IN RCP E, INV 780.11
				BOTTOM ELEV: 779.91
				CONDITION: FAIR BRICK N BLOCK
71-71760	SMH 50433	797.36	48"	12 IN CLAY N, INV 789.36
/1-/1/00			48	12 IN CLAY S, INV 789.16
				BOTTOM ELEV: 789.66

### PROJECT BENCHMARKS

BM#	ELEV	DESCRIPTION
50	807.99	PK NAIL NORTHEAST SIDE OF UTILITY POLE, SOUTH SIDE SWIFT, 2ND POLE SOUTHWEST
		OF INTERSECTION OF SWIFT AND WRIGHT
51	812.11	PK NAIL EAST SIDE OF UTILITY POLE AT NORTHWEST CORNER PONTIAC TRAIL & LONGSHORE BETWEEN HYDRANT AND RAILROAD
52	784.73	PK NAIL SOUTHWEST SIDE OF UTILITY POLE AT NORTHEAST CORNER MOORE & BROADWAY



CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


CALE PLAN: 1"=20"

PONTIAC, SWIFT, MOORE, & WRIGHT


INFRASTRUCTURE IMPROVEMENTS

INFRASTRUCTURE IMPROVEMENTS

EXISTING CONDITIONS & ALIGNMENT PLAN - MOORE S



|--|





VNV 30	

CES - ENGINEERING	C, SWIFT, MOORE, & WRIGHT STRUCTURE IMPROVEMENTS	ONDITIONS & ALIGNMENT PLAN - WRIGHT ST
CES	C, S/ STRU	DILIGNO

OF ANN ARBOR - I	: 1"=20'		
2	CALE PLAN: 1"=20"	H	No.
5	CALE PL		RAWING No.

SHEET No.

13 OF 52

### **EXISTING SANITARY STRUCTURE TABLE**

AA GIS#			SIZE	CONDITION AND CONNECTIONS		
				CONDITION: FAIR BRICK FOD		
71-68583	SMH 50372	848.65	48"	8 IN PVC SSW, INV 839.45		
				BOTTOM ELEV: 839.45		
				CONDITION: FAIR BRICK		
71 60504	CMU E0274	841.55	36"	8 IN PVC NNE, INV 832.25		
/1-06564	31VID 30374	041.33	30	8 IN PVC SSW, INV 832.15		
				BOTTOM ELEV: 832.20		
				CONDITION: FAIR BRICK N BLOCK		
				8 IN PVC NNE, INV 821.65		
71 60506	SMH 50276	830.75	48"	8 IN PVC SSW, INV 821.55		
/1-00300	31010 30376	650.75	40	12 IN RCP ENE, INV 821.95		
				12 IN RCP WSW, INV 822.15		
				BOTTOM ELEV: 821.60		

### **EXISTING WATER STRUCTURE TABLE**

AA GIS#	WADE TRIM #	RIM	SIZE	CONDITION AND CONNECTIONS
				CONDITION: FAIR BRICK FOD FOW NPV TOV-
No GIS ID	GVWD 50373	848.05	36"	4.00
				BOTTOM ELEV: 843.65
				CONDITION: FAIR BRICK N BLOCK FOD FOW
01 02002	CV/M/D F027F	020.00	40!!	TOP-4.20 TOV-2.60
01-02683	GVWD 50375	830.96	48"	8 IN STEEL? WNW ESE, T/P 826.01
				BOTTOM ELEV: 826.06


CITY OF ANN ARBOR - PUBLIC

SHEET No. 14 OF 52

EXISTING PAVEMENT SECTION NOTES:

W-1 10' SOIL BORING INDICATES 3.25" OF EXISTING ASPHALT THICKNESS, 8.75" OF MOIST BROWN SAND WITH GRAVEL, 2' OF MEDIUM COMPACT MOIST BROWN CLAYEY SAND WITH TRACE OF GRAVEL, 2.5' OF MEDIUM COMPACT MOIST BROWN SAND WITH TRACE OF GRAVEL, AND 4.5' OF DENSE MOIST BROWN SAND WITH SOME GRAVEL, PEBBLE & GRAVEL SEAMS


S-4 10' SOIL BORING INDICATES 7" OF EXISTING ASPHALT THICKNESS, AND 9.42' OF MEDIUM COMPACT MOIST BROWN SAND WITH SOME GRAVEL & GRAVEL SEAMS



### EXISTING TYPICAL CROSS SECTION

### SWIFT ST

POB STA 1+16.55 TO POE STA 7+50 NOT TO SCALE




PAY ITEM	HMA MIX	APPLICATION RATE	EST. THICKNESS	PERF GRADE	AWI (MIN)
HMA, 5EML	5EML (TOP)	165 LB/SYD	1.5"	PG 70-28P	260
HMA, 4EML	4EML (LEVELING)	220 LB/SYD	2"	PG 70-28P	260
WEDGING	4EML	110 LB/IN/SYD	VARIES	PG 70-28P	_


**HMA APPLICATION ESTIMATE** 

EXISTING PAVEMENT SECTION NOTES:

 $P\!-\!5$  10' SOIL BORING INDICATES 6.5" OF EXISTING ASPHALT THICKNESS, 6.75" OF MOIST BROWN SAND WITH TRACE OF GRAVEL, AND 8.9' OF MEDIUM COMPACT MOIST BROWN MEDIUM SAND WITH TRACE OF GRAVEL

P-6 10' SOIL BORING INDICATES 6" OF EXISTING ASPHALT THICKNESS, 2.5' OF COMPACT MOIST BROWN FINE SAND, AND 7' OF MEDIUM COMPACT MOIST BROWN SAND WITH SOME GRAVEL





**HMA APPLICATION ESTIMATE** 

PROPOSED TYPICAL CROSS SECTION PONTIAC TRAIL

POB STA 1+05.26 TO POE STA 5+00.13 NOT TO SCALE

ROR					
TREET					
7 07-8647					
D	00	00 ISSUED FOR BID	03/28/2023	CGT/BLA VCM/CEW	NCM/CEW
	REV.	DESCRIPTION	DATE	DRAWN	DRAWN CHECKED



- PUBLIC SERVICES - ENGINEERING
PONTIAC, SWIFT, MOORE, &
WRIGHT INFRASTRUCTURE
IMPROVEMENTS
TYPICALS - PONTIAC TRAIL

PERF GRADE

PG 70-28P

PG 70-28P

PG 70-28P

PG 70-28P

AWI (MIN)

260

260

260


EST. THICKNESS

1.5"

VARIES

ARBOR CITY OF ANN A


SHEET No.



66' R.O.W. 31' 35' CONSTRUCTION & 37' +/- B/B 8' +/-2' +/-8' +/-18.5' 18.5 2' +/-LIMITS OF 1.5" COLD MILLING, HMA SURFACE EX. GROUND -LANE 13'± -----PAVEMENT, REMOVE — EX. GROUND (TYP.) 3.2% TO 5.4% VARIES  $\angle$ EG PER PROFILE 1.9% TO -2.9%VARIES -— EXISTING CONCRETE EXISTING AGG BASE (SEE — WALK NOTES REGARDING EXISTING THICKNESS AND - EXISTING HMA PAVEMENT EX. CONC. CURB AND MATERIAL) EXISTING CONCRETE WALK — (SEE NOTES REGARDING GUTTER (TYP.) TO REMAIN ÈXISTING THICKNESS AND EXCEPT WHERE CALLED MATERIAL) FOR ON THE PLANS GUTTER PAN PAVED OVER IN SOME LOCATIONS. -CONTRACTOR SHALL TAKE CARE NOT TO DAMAGE - GUTTER PAN PAVED OVER IN SOME LOCATIONS. EXISTING CONCRETE CURB AND GUTTER DURING CONTRACTOR SHALL TAKE CARE NOT TO DAMAGE REMOVAL OF HMA PAVEMENT. REMOVAL OF HMA EXISTING CONCRETE CURB AND GUTTER DURING PAVEMENT FROM THE GUTTER SHALL BE INCLUDED IN THE PRICE FOR COLD MILLING, HMA SURFACE. REMOVAL OF HMA PAVEMENT. REMOVAL OF HMA PAVEMENT FROM THE GUTTER SHALL BE INCLUDED IN THE PRICE FOR COLD MILLING, HMA SURFACE.

### EXISTING TYPICAL CROSS SECTION


MOORE ST POB STA 1+77.81 TO POE STA 5+50.00 NOT TO SCALE



\*NOTE: MOORE STREET IS MILL AND OVERLAY OF 1.5". IN THE AREAS OF THE WATER MAIN TIE OVERS THE PROPOSED SECTION IS 10" AGGREGATE BASE AND 3.5" ASPHALT.

PAY ITEM	HMA MIX	APPLICATION RATE	EST. THICKNESS	PERF GRADE	AWI (MIN)
HMA, 5EML	5EML (TOP)	165 LB/SYD	1.5"	PG 70-28P	260
WEDGING	4EML	110 LB/IN/SYD	VARIES	PG 70-28P	ı

**HMA APPLICATION ESTIMATE** 



### PROPOSED TYPICAL CROSS SECTION

MOORE ST

POB STA 1+77.81 TO POE STA 5+50.00 NOT TO SCALE

CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

SCALE PLAN: ######


PONTIAC, SWIFT, MOORE, &

WRIGHT INFRASTRUCTURE

WRIGHT INFRASTRUCTURE

WRIGHT INFRASTRUCTURE

TYPICALS - MOORE STREET SHEET No.





IC SERVICES - ENGINEERING
PONTIAC, SWIFT, MOORE, & WRIGHT
INFRASTRUCTURE IMPROVEMENTS
TYPICALS - WRIGHT STREET

CITY OF ANN ARBOR

SHEET No. 17 OF 52

# Testing Engineers & Consultants, Inc. 1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249 (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Project: Watermain Resurfacing Project

Boring N	lo.: W-1		Job No.:	63228 Project: Watermain Resurfaci	ng Project		
Client: C	ity of Ann	Arbor		Location: Ann Arbor, Michigan	ń		
Type of	Rig: Truck			Drilled By:    Mickle			
Drilling l	Method: S	olid Stem	Augers	Started: 2/12/2023			
Ground	Surface E	levation:		Completed: 2/12/2023			1,
					J		
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu
	LS	4	1	ASPHALT (3 1/4")	14.8	133	j I
2.5		4 4 7	3	Moist Brown Gravelly Well Graded Sand With Some Clay-FILL		o V	
	LS	5		Medium Compact Moist Brown Clayey SAND With Trace Of Gravel	14.8	133	i i
5.0		8 12	5.5			]	
1	LS	11		Medium Compact Moist Brown SAND With Trace Of Gravel	5,9	146	
7.5		31/6"		Dense Moist Brown SAND With Some Gravel, Pebble & Gravel Seams		[] 	
E E	LS	21/2"					
10.0			10				
				Bottom-of Boring at 10 <sup>1</sup>			
12.5							
5 5			}				
15.0				<u> </u>			
			į,				
17.5-	n Tu				11		
5	]						
20.0			ς [		j L		
						0	
22.5							
5		Ī.					
		 		% of dry weight Water Enco	ountered:	None	Ĺ <u>.,,,,,</u> ,,,
SS - 2" I LS - Sec	ndard Penetral D. Split Spool tional Liner Sa	n Sample ample	d - Bulk gu - Unc	Density, pcf onlined Compression, psf			j
ST - She AS - Aug	elby Tube Sam ger Sample	ipie	RC - Ro	ect Hush			)



## Testing Engineers & Consultants, Inc. 1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249 (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Boring N	lo.: W-2		Job No.:	63228 Project: Watermain Resurfact	ng Project		
Client: C	ity of Ann	Arbor		Location: Ann Arbor, Michigan	1		
Type of	Rig: Truck			Drilled By: 1 Mickle			
Drilling	Method: S	olid Stem	Augers	Started: 2/12/2023			
Ground	Surface E	evation:		Completed: 2/12/2023			
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	W	d	qu
			46	ASPHALT (5 1/2")			
	LS	4 4 5			13.0	137	
2.5		5	3.3	Firm Moist Brown CLAY With Some Silt & Trace Of Gravel-Possible Fill	[		
i i	LS	5 10		Medium Compact Moist To Wet Brown SAND With Some	9.9	140	
5.0		12	5.8	Gravel			
Į	LS	6 8	3.0	OWAN I D OI AVAINE COME CITE	19,2	130	4940
7.5		8 13		Stiff Moist Brown CLAY-With Some Silt		n	
	LS	7	9		16.3	135	11540
10.0	13	7 10 17	10	Extremely Stiff Moist Gray CLAY With Some Silt			
					] ]		]
				Bottom of Boring at 10'			
12.5							0
						į.	Op.
15.0					T T	l.	
Ī					Ţ.	0	
17.5					1	[]	
10							
20.0							[]
ia E	103				ļ		[
22.5-							
		L	[]				
"N" - Star	ndard Penetrat D. Split Spoor tional Liner Sa	ion Resistan	ce w-H2O,	% of dry weight Water Enco	untered:	4'3"	



Testing Engineers & Consultants, Inc.


1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249
(248) 588-6200 or (313) T-E-S-T-I-N-G
Fax (248) 588-6232

Boring N	o.: W-3	Arbor	Job No.:	63228  Project: Watermain Resurfact  Location: Ann Arbor, Michiga			
Drilling I	Rig: Truck Method: So Surface El	olid Stem	Augers	Drilled By: I. Mickle Started: 2/12/2023 Completed: 2/12/2023			
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	
2.5	LS	3 5 4	- (23 <sub>3</sub> -	ASPHALT (2 3/4")  Loose Moist Brown Clayey Sand With Some Gravel & Clay	9.8	131	
5.0	LS	5 21 19	4 5.5	Layer-FILL  Compact Moist Brown SAND & Gravel	7.5	135	
7.5	LS	9 12 17	8	Medium Compact Moist Brown Clayey SAND With Some Gravel & Clay Layers	7.4	135	ĺ
10.0	Ls [	4 5 7	10	Medium Compact Moist Brown Fine To Medium SAND	6.4	137	
12.5			<u>u</u> j	Bottom of Boring at 10"			
15.0							
17.5	70 79 500 13						
20.0=							
22.5							
SS - 2" I LS - Sec ST - She	ndard Penetrat D. Split Spoor tional Liner Sa lby Tube Sam ler Sample	n Sample Imple	d - Bulk gu - Unc	% of dry weight Density, pcf Density, pcf At Comple ect Push At Comple			



## Testing Engineers & Consultants, Inc. 1343 Rochester Road - PO Box 249 - Troy, Michigan - 48099-0249 (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Project: Watermain Resurfacing Project Boring No.: S-4 Client: City of Ann Arbor Location: Ann Arbor, Michigan Type of Rig: Truck Drilled By: I Mickle Drilling Method: Solid Stem Augers Started: 2/12/2023 Ground Surface Elevation: Completed: 2/12/2023 Soil Classification 7.0 136 Medium Compact Moist Brown Well Graded Sand & Gravel With Some Silt & Gravel Seams-FILL 6.0 138 10.0 Bottom of Boring at 10' "N" - Standard Penetration Resistance w-H2O, % of dry weight d-Bulk Density, pcf du Unconfined Compression, psf ST - Shelby Tube Sample DP - Direct Push AS - Auger Sample RC - Rock Core Water Encountered: None





### Testing Engineers & Consultants, Inc. (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Boring No. W-1

Project: Watermain Resurfacing Project

_	Method: So Surface El			Completed: 2/12/2023	Started: 2/12/2023  Completed: 2/12/2023				
Depth Sample N Strata Change				Soil Classification	W	d	qu		
2.5	LS	8 10 12	54 1.1	ASPHALT (6 1/2")  Moist Brown Fine Sand With Some Silt & Trace Of Gravei-FILL	5.0	139	] ] [		
5.0	LS	5 6 8		Medium Compact Moist Brown Medium SAND With Trace Of Gravel	3.5	139 }			
7.5	LS	7 7 9			3,5	138			
10.0	Ls	4 6 10	10		3.2	139			
12.5				Bottom of Boring at 10"	μ. [		[		
15.0									
17.5							1		
20.0		] [[ [							
22.5		]							



### Testing Engineers & Consultants, Inc. (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Boring No. W-2

	No.: P-6		Job No.:	Project: Watermain Resurfac		_	
Client; (	City of Ann	Arbor		Location: Ann Arbor, Michiga	n		
	Rig: Truck			Drilled By: I. Mickle			
Drilling	Method: S	olid Stem	Augers	Started: 2/12/2023			
Ground	Surface E	levation:		Completed: 2/12/2023			[
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu
2.5	LS	16 15 16	5	ASPHALT (6")  Compact Moist Brown Fine SAND With Some Silt & Trace Of	3.3	130	
5.0	LS	5 9 10	3	Gravel  Medium Compact Moist Brown SAND With Some Gravel	4.4	126	
7.5	LS	11 10 13			1,4	133	
10.0	Ls	5 10 17	10		3,2	133	
12.5				Bottom of Boring at 10 <sup>t</sup>			
15.0							
17.5							C
20.0					1 1 1		
22,5							
5 5							
"N" - Star SS - 2".I	ndard Penetrat	ion Resistano Sample	d - Bulk	% of dry weight Water Enc			
ST - She	D. Split Spoor tional Liner Sa alby Tube Sam ger Sample	ple	Qu - Unco DP - Dire RC - Roc	onlined Compression, psf oct Push sk Core Boring No.		е	



Job No.: 63228

Boring No.: M-7

### Testing Engineers & Consultants, Inc. (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

Project: Watermain Resurfacing Project

	Surface El	evation:		Completed: 2/12/2023			
Depth Sample N Strata (ft) Type N Change			Strata Change	Soil Classification	w	d	qu
2.5	LS	11 15 15	1.3 3	ASPHALT (3 1/2")  Moist Brown Gravelly Well Graded Sand With Some Silt-FILL	6.6	137	
5.0	LS	3 2 2	5	Compact Moist Brown SAND With Trace Of Gravel  Loose Moist Brown Clayey SAND With Trace Of Gravel	16.1	134	410
7,5				Bottom of Boring at 5'	c c		
10.0							
12.5					{		
15.0					0 0		
17.5							
					1		
20.0	Ì						



Client: City of Ann Arbor

### Testing Engineers & Consultants, Inc. (248) 588-6200 or (313) T-E-S-T-I-N-G Fax (248) 588-6232

At Completion: None

Boring No. S-4


Project: Watermain Resurfacing Project


Location: Ann Arbor, Michigan

Ground	Surface El	evation:		Completed: 2/12/2023				
Depth (ft)	Sample Type	N	Strata Change	Soil Classification	w	d	qu	
I T			<sub>-</sub> 42	ASPHALT (5")				
2.5	LS	16 12 7	2.2	Medium Compact Moist Brown Gravelly Well Graded Sand With Some Silt-FILL	7.0	136		
5,0 <del>-</del>	LS	5 7 7	5	Firm Moist Brown CLAY With Some Silt, Trace Of Gravel & Sand Seams	19.4	129	2230	
		•		Bottom of Boring at 5°				
7,5	7 ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) (				[			
10.0	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1							
12.5							g g	
15.0							Ü	
17.5							0	
20.0	*							
22.5						[		
-	E .					,		

- PUBLIC SERVICES - ENGINEERING
PONTIAC, SWIFT, MOORE, & WRIGHT
INFRASTRUCTURE IMPROVEMENTS
SOIL BORING LOGS CITY OF ANN ARBOR

SHEET No. 18 OF 52





CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

SCALE PLAN: 1"=40'

DRAWING No.

DRAWING No.


OVERALL UTILITY PLAN

OVERALL UTILITY PLAN

19 OF 52








SOIL BO

SOIL BORING LOCATION



**REMOVAL KEY** 10 DR STRUCTURE COVER, TYPE K, SPECIAL **KEY** DESCRIPTION 13 GATE VALVE IN WELL, ABANDON PAVEMENT, REMOVE 14 FIRE HYDRANT, REM 2 CURB AND GUTTER, ANY TYPE OR COLD MILLING, HMA SURFACE SIZE, REMOVE\* 3 SIDEWALK AND RAMPS, REMOVE\* EROSION CONTROL, INLET FILTER DRIVEWAY APPROACH, REMOVE\* ADJUST MONUMENT BOX, 5 GATE VALVE BOX, OR 19 GATE VALVE IN BOX, ABANDON STRUCTURE COVER 7 DR STRUCTURE, ANY SIZE 21 WATER MAIN PIPE ABANDONMENT OR DEPTH, REM 8 22 GUARDRAIL, REMOVE, SALVAGE SEWER, ANY SIZE OR DEPTH, REM AND RECONSTRUCT 9 PROTECTIVE FENCE, ORANGE, PLASTIC, 4 FOOT HT DR STRUCTURE COVER, TYPE Q, 24

NOTE: SAWCUT FULL DEPTH AT REMOVAL LIMITS

SPECIAL

NOTE 1: CONTRACTOR MUST NOTIFY THE ENGINEER PER THE CONTRACT DOCUMENTS IN ADVANCE OF DISTURBING MONUMENT SO THAT WITNESSING OF THE MONUMENT CAN BE COORDINATED.


NOTE 2: REMOVE AND SALVAGE GUARDRAIL TERMINAL. REMOVE ONE GUARDRAIL PANEL. REINSTALL GUARDRAIL TERMINAL TO ALLOW FOR CLEARANCE TO INSTALL SIDEWALK RAMP

LEGEND					
	PAVEMENT, REMOVE				
	BITUMINOUS DRIVEWAY APPROACH, REM				
	CONCRETE DRIVEWAY APPROACH, REM				
	COLD MILLING, HMA SURFACE				
	SIDEWALK AND RAMPS, REM				
· xx ·	CURB AND GUTTER, REM SEWER, ANY SIZE OR DEPTH, REM				
	SILT FENCE				
D	TREE PROTECTION FENCE				

- PUBLIC SERVICES - ENGINEERING
PONTIAC, SWIFT, MOORE, & WRIGHT
INFRASTRUCTURE IMPROVEMENTS
REMOVAL PLAN - SWIFT ST STA 0+00 TO 5+50

CITY OF ANN ARBOR

SHEET No.



3

5

8

9

SIDEWALK AND RAMPS, REMOVE\*
DRIVEWAY APPROACH, REMOVE\*

ADJUST MONUMENT BOX, GATE VALVE BOX, OR

DR STRUCTURE, ANY SIZE

SEWER, ANY SIZE OR DEPTH, REM

DR STRUCTURE COVER, TYPE Q,

STRUCTURE COVER

OR DEPTH, REM

SPECIAL

EROSION CONTROL, INLET FILTER

GATE VALVE IN BOX, ABANDON

WATER MAIN PIPE ABANDONMENT

GUARDRAIL, REMOVE, SALVAGE

PROTECTIVE FENCE, ORANGE,

NOTE: SAWCUT FULL DEPTH AT REMOVAL LIMITS

AND RECONSTRUCT


PLASTIC, 4 FOOT HT


19


CONCRETE DRIVEWAY APPROACH, REM COLD MILLING, HMA SURFACE SIDEWALK AND RAMPS, REM · x x · CURB AND GUTTER, REM SEWER, ANY SIZE OR DEPTH, REM — SILT FENCE TREE PROTECTION FENCE


CITY OF ANN ARBOR


SHEET No.














- 1. TWO WEEKS PRIOR TO THE START OF CONSTRUCTION ON WRIGHT ST THE CONTRACTOR SHALL PERFORM EXPLORATORY EXCAVATION ON WRIGHT STREET AT THE CONNECTION POINT OR AS DIRECTED BY THE ENGINEER TO VERIFY THE LOCATION OF THE EXISTING WATERMAIN. ALL COSTS ASSOCIATED WITH THIS WORK SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ITEM OF WORK :EXPLORATORY EXCAVATION (0-10; DEEP)"(TRENCH DETAIL 1)
- 2. WHERE EXISTING WATER MAIN IS EXPOSED FOR A CONNECTION OR APPURTENANCE INSTALLATION, THE CONTRACTOR SHALL INSTALL ONE SACRIFICIAL ANODE ON THE EXISTING PIPE. IF THE FITTING IS INSTALLED IN-LINE WITH THE EXISTING MAIN, SUCH AS AT A CUT-IN TEE OR VALVE INSERTION, ONE ANODE SHALL BE INSTALLED ON THE EXISTING PIPE TO EACH SIDE OF THE NEW FITTING. EACH ANODE INSTALLED ON EXISTING WATER MAIN WILL BE PAID FOR AS "SACRIFICIAL ANODE, XX LB"
- 3. THE DEPTH AND SIZE OF ELECTRICAL, TELEPHONE AND FIBER OPTIC CONDUITS/DUCTS AND THE DEPTH OF GAS MAINS ARE APPROXIMATE. CONTRACTOR SHALL VERIFY, SUPPORT AND PROTECT DURING CONSTRUCTION AND ADJUST WATER MAIN WHERE NECESSARY TO MAINTAIN 12-INCHES VERTICAL CLEARANCE FROM ALL UTILITIES (EXCEPT SANITARY AND STORM SEWER WHERE 18-INCHES IS REQUIRED). THIS WORK IS PAID FOR UNDER GENERAL CONDITIONS, MAX.

WATER MAIN STRUCTURE TABLE								
STRUCTURE	TYPE	STATION	RIM	WELL DEPTH				
GVIW1	12" GVIW	0+20	809.99	7.52				

WATER MAIN STRUCTURE TABLE									
STRUCTURE	TYPE	STATION	FG	T/P					
H1	HYD	???	813.20	5.50					

**Existing Water Service** Station Size (in) 1+08 601 0+79 1.50




CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING


SCALE PLAN: ######


PONTIAC, SWIFT, MOORE, & WRIGHT


DRAWING No.

PROPOSED WATER MAIN PLAN AND PROFILE SWIFT STAR 0+0












- PUBLIC SERVICES - ENGINEERING
- PONTIAC, SWIFT, MOORE, & WRIGHT
- INFRASTRUCTURE IMPROVEMENTS
- PROPOSED WATER MAIN CONSOLIDATION - MOORE ST


CITY OF ANN ARBOR

SHEET No.











**KEY MAP** 







|--|


CONSTRUCTION RET				
KEY	DESCRIPTION			
HMA-AGG	SURFACE AREA FOR HMA ON AGGREGATE BASE			
НМА	SURFACE AREA FOR HMA			
CG	CURB AND GUTTER, CONC, AA DET SD-R-1			
SW-6	SIDEWALK, CONCRETE, 6 INCH, P-NC			
SWR-6	SIDEWALK RAMP, CONCRETE, 6 INCH,			
DWS	DETECTABLE WARNING SURFACE, MODIFIED			
REST	TOPSOIL SURFACE, 4 INCH HYDROSEEDING			
CDA-6	DRIVE APPROACH, CONC, 6 INCH, NONREINF, P—NC			
DW M	DRIVEWAY OPENING, CONC,			


AC, SWIFT, MOORE, & WRIGHT STRUCTURE IMPROVEMENTS	D PAVING PLAN - SWIFT ST STA 2+50 TO POE
AC, SV STRU	) PAVING


<b>JE ANN ARBOR - PUBLIC SERVICES - ENGINEERING</b>		FONTIAC, SWIFT, MOORE, &		PROPOSED PAVING PLAN - SWIFT ST STA
CITY OF ANN	SCALE PLAN: 1"=20'		DRAWING No.	2022-032-31
SHEE	TN	0.		










































- PUBLIC SERVICES - ENGINEERING
PONTIAC, SWIFT, MOORE, & WRIGHT
INFRASTRUCTURE IMPROVEMENTS
MAINTENANCE OF TRAFFIC - STAGE 1

CITY OF ANN ARBOR

SHEET No. 45 OF 52







CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

CALE PLAN: Custom

CALE PLAN: Custom

PONTIAC, SWIFT, MOORE, & WRIGHT


PONTIAC, SWIFT, MOORE, & WRIGHT

INFRASTRUCTURE IMPROVEMENTS

INFRASTRUCTURE IMPROVEMENTS

MAINTENANCE OF TRAFFICE - STAGE 2

SHEET No.





CITY OF ANN ARBOR - PUBLIC SERVICES - ENGINEERING

CALE PLAN: Custom

CALE PLAN: Custom

PONTIAC, SWIFT, MOORE, & WRIGHT

PONTIAC, SWIFT, MOORE, & WRIGHT


INFRASTRUCTURE IMPROVEMENTS

INFRASTRUCTURE IMPROVEMENTS

MAINTENANCE OF TRAFFIC - STAGE 3

SHEET No.

## PEDESTRIAN DETOUR USING OPPOSITE SIDE OF STREET



# OTHER SIDE OF STREET DETOUR OR DETOUR WITH TRAILBLAZING SIGNS (FOR CORNER SIDEWALK CLOSURE WITH OPTIONAL TEMPORARY CROSSWALK)

### **GENERAL NOTES**

WHEN CLOSING OR RELOCATING CROSSWALKS OR SIDEWALKS, THE CONTRACTOR SHALL PROVIDE DETECTABLE TEMPORARY FACILITIES AND INCLUDE ACCESSIBILITY FEATURES CONSISTENT WITH EXISTING PEDESTRIAN FACILITIES.

TEMPORARY TRAFFIC CONTROL DEVICES FOR PEDESTRIANS ARE SHOWN. OTHER DEVICES MAY BE NECESSARY TO CONTROL VEHICULAR TRAFFIC. STAGE WORK, AS NECESSARY, TO PROVIDE AN ALTERNATE PEDESTRIAN ROUTE (APR) AT ALL TIMES. FOR ROADWAYS WITH NO AVAILABLE DETOURS, MAINTAIN ONE OPEN SIDEWALK AT ALL TIMES.

PROVIDE A SMOOTH, CONTINUOUS, HARD SURFACE THROUGH THE LENGTH OF THE APR. COMPACTED GRAVEL, AGGREGATE, OR SLAG MATERIALS ARE NOT ALLOWED. PROVIDE A FIRM, STABLE, AND SLIP RESISTANT TEMPORARY WALKWAY SURFACE TO COVER SHORT SEGMENTS OF ROUGH, SOFT, OR UNEVEN GROUND.

THE PEDESTRIAN TRAFFIC SIGNALS CONTROLLING CLOSED CROSSWALKS SHALL BE COVERED OR DEACTIVATED BY THE CITY OF ANN ARBOR. THE CONTRACTOR SHALL SCHEDULE AND COORDINATE THIS WORK WITH THE ENGINEER A MINIMUM OF 72 HOURS (NOT INCLUDING WEEKENDS & HOLIDAYS) PRIOR TO THE BEGINNING OF WORK THAT REQUIRES A SIDEWALK CLOSURE.

POST MOUNTED SIGNS LOCATED ADJACENT TO A SIDEWALK SHALL HAVE A 7 FOOT MINIMUM CLEARANCE FROM THE BOTTOM OF THE SIGN TO THE SIDEWALK SURFACE.

WHEN THE ENGINEER DETERMINES THAT THE CONTRACTOR'S OPERATIONS OR PLACEMENT OF TRAFFIC CONTROL DEVICES HAS CAUSED A SITUATION THAT THE VISIBILITY OF IS REDUCED ENOUGH TO CREATE A HAZARD, THE TRAFFIC CONTROL DEVICES SHALL BE DELINEATED WITH FLAGS OR OTHER ENGINEER-APPROVED DEVICES AT NO ADDITIONAL COST TO THE PROJECT.

MINIMIZE DISRUPTION TO PEDESTRIANS TO THE MAXIMUM EXTENT FEASIBLE BY PROVIDING AN APR IN THE FOLLOWING ORDER OF PREFERENCE:


- PROVIDE THE APR ON THE SAME SIDE OF THE STREET AS THE DISRUPTED ROUTE UTILIZING BYPASSES.
- 2. WHERE IT IS NOT FEASIBLE TO PROVIDE A SAME SIDE APR, PROVIDE A DETOUR ON THE OTHER SIDE OF THE STREET.
- 3. WHERE IT IS NOT FEASIBLE TO PROVIDE AN APR ON THE OTHER SIDE OF THE ROADWAY, PROVIDE AN APR DETOUR WITH TRAILBLAZING SIGNS AS SHOWN ON THE PROJECT PLANS.

### SPECIFIC NOTES

- 1 TEMPORARY CURB RAMPS WITH DETECTABLE WARNINGS.
- 2 TEMPORARY PAVEMENT MARKING FOR CROSSWALK LINES.
- AN APPROVED AUDIBLE MESSAGE DEVICE OR TACTILE MESSAGE SHALL BE PROVIDED FOR SIGHT-IMPAIRED PEDESTRIANS.
- THE INTERNATIONAL SYMBOL OF ACCESSIBILITY SHOULD BE DISPLAYED WHEN ANY WALKWAY THROUGH A WORK ZONE HAS BEEN DETERMINED TO BE TPAR COMPLIANT. THE SYMBOL OF ACCESSIBILITY SHALL NOT BE DISPLAYED IF PERSONS WITH DISABILITIES SHOULD NOT USE THE PRIMARY TEMPORARY PEDESTRIAN DETOUR. THE REASON FOR THE NON-COMPLIANCE SHALL BE POSTED AND AN ALTERNATE ROUTE SHALL BE POSTED WHEN THE PRIMARY TEMPORARY PEDESTRIAN DETOUR IS NON-COMPLIANT TO TPAR STANDARDS.
- 5 TYPICAL SIGN MESSAGE FOR A TEMPORARY PEDESTRIAN DETOUR SHALL INCLUDE INFORMATION SUCH AS THE DURATION OF THE WALKWAY RESTRICTIONS (BEGINNING AND/OR END DATES) AND A PROJECT CONTACT NUMBER FOR 24 / 7 QUESTIONS OR REPORTING HAZARDS.
- 6 PEDESTRIAN DETOUR TRAILBLAZING SIGNS SHALL BE USED IF THE PEDESTRIAN DETOUR IS IN A LOCATION OTHER THAN ACROSS THE STREET FROM THE SIDEWALK CLOSURE.

### PEDESTRIAN TEMPORARY TRAFFIC CONTROL NOTES


- THE CONTRACTOR SHALL MAINTAIN PEDESTRIAN THROUGH MOVEMENTS FROM ONE END OF THE CONSTRUCTION AREA TO THE OTHER, ON AT LEAST ONE SIDE OF THE STREET DURING CONSTRUCTION. ANY SIDEWALK CLOSURES SHALL MEET THE REQUIREMENTS OF THE MMUTCD, PART 6.
- 2. PEDESTRIAN ACCESS SHALL BE PROVIDED TO ALL ADJACENT PROPERTIES, BUILDINGS, RESIDENCES AND COMMERCIAL PROPERTIES AT ALL TIMES. THIS MAY INCLUDE TEMPORARY WALKWAYS SPANNING THE CONSTRUCTION AREA.
- 3. IF SIDEWALKS ARE CLOSED, A TEMPORARY PEDESTRIAN ACCESS ROUTE (TPAR) SHALL BE PROVIDED ON THE SAME SIDE OF THE ROAD AS THE CLOSED SIDEWALK, IF POSSIBLE. SIGNS AND BARRICADES SHALL BE USED TO PROVIDE ADVANCE NOTICE OF THE CLOSURE AND THE ROUTE OF ANY PEDESTRIAN DETOURS. THE TPAR SHALL HAVE A MINIMUM UNOBSTRUCTED WIDTH OF 4 FEET. IF THE TPAR IS LESS THAN 5 FEET IN WIDTH, A 5 FOOT BY 5 FOOT PASSING SPACE SHALL BE PROVIDED AT LEAST EVERY 200 FEET. THE SURFACE OF THE TPAR SHALL BE SMOOTH AND CONTINUOUS FOR THE LENGTH OF THE TPAR. THE TPAR SHALL MAINTAIN THE SAME LEVEL OF ACCESSIBILITY AND DETECTABILITY AS THE FACILITY THAT IS BEING CLOSED. THE TPAR SHALL NOT LEAD PEDESTRIANS INTO CONFLICTS WITH VEHICLES, EQUIPMENT, OR CONSTRUCTION OPERATIONS.
- 4. IF THE TPAR IS ADJACENT TO MOVING TRAFFIC, CONSTRUCTION OPERATIONS/EQUIPMENT, OR DROP-OFFS, THEN CRASH WORTHY CHANNELIZING DEVICES THAT MEET THE REQUIREMENTS OF NCHRP 350 AND THE MMUTCD SHALL BE USED.
- 5. THE CONTRACTOR SHALL NOT STORE OR PLACE ANY CONSTRUCTION MATERIALS, EQUIPMENT OR SIGNS IN THE PEDESTRIAN PATH OF TRAVEL.
- 6. THE CONTRACTOR'S OPERATIONS SHALL NOT OCCUPY SIDEWALKS EXCEPT WHERE PROPER PROTECTION AND A TPAR HAVE BEEN PROVIDED.
- 7. WHEN DIRECTED BY THE ENGINEER, OR STATED ON THE PLANS, THE CONTRACTOR SHALL PROVIDE A TEMPORARY PEDESTRIAN TRAFFIC CONTROL PLAN FOR REVIEW AND WRITTEN APPROVAL BY THE ENGINEER A MINIMUM OF THREE WEEKS BEFORE SUCH PLAN IS IMPLEMENTED. THIS PLAN SHALL DETAIL THE CONSTRUCTION PHASING AND SCHEDULE AND THE SPECIFIC METHODS OF MAINTAINING SAFE PEDESTRIAN ACCESS THROUGHOUT THE CONSTRUCTION AREA. THIS PLAN SHALL PROVIDE THE LOCATION AND DETAILS OF TEMPORARY CONSTRUCTION SIGNING, MARKINGS, BARRICADES, CHANNELIZING DEVICES, TPARS AND METHODS TO MAINTAIN ACCESS TO ADJACENT PROPERTIES, BUSINESSES, RESIDENCES, ETC. NO WORK SHALL BE ALLOWED TO BEGIN UNTIL THIS PLAN IS APPROVED BY THE ENGINEER IN WRITING.
- 8. PROVISION OF THE TPAR AND ALL OF ITS ELEMENTS, INCLUDING BUT NOT LIMITED TO, CREATION OF THE TEMPORARY PEDESTRIAN CONTROL PLAN, SIGNS, CHANNELIZING DEVICES, BARRICADES, TEMPORARY PAVEMENT MARKINGS AND OTHER TRAFFIC CONTROL DEVICES SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE ITEM OF WORK "MINOR TRAF DEVICES."



BYPASS ON ADJACENT AVAILABLE RIGHT OF WAY


**BYPASS TYPE A** 

NOTE: MAY ONLY BE USED ON ROADWAY WITH POSTED SPEED OF 45 MPH OR LESS.



SIDEWALK BYPASS USING PARKING OR SHOULDER ON LOW SPEED ROADWAY

**BYPASS TYPE B** 



**BYPASS TYPE C** 

### **GENERAL NOTES**

WHEN CLOSING OR RELOCATING CROSSWALKS OR SIDEWALKS, THE CONTRACTOR SHALL PROVIDE DETECTABLE TEMPORARY FACILITIES AND INCLUDE ACCESSIBILITY FEATURES CONSISTENT WITH EXISTING PEDESTRIAN FACILITIES.

TEMPORARY TRAFFIC CONTROL DEVICES FOR PEDESTRIANS ARE SHOWN. OTHER DEVICES MAY BE NECESSARY TO CONTROL VEHICULAR TRAFFIC. STAGE WORK, AS NECESSARY, TO PROVIDE AN ALTERNATE PEDESTRIAN ROUTE (APR) AT ALL TIMES. FOR ROADWAYS WITH NO AVAILABLE DETOURS, MAINTAIN ONE OPEN SIDEWALK AT ALL TIMES.

PROVIDE A SMOOTH, CONTINUOUS, HARD SURFACE THROUGH THE LENGTH OF THE APR. COMPACTED GRAVEL, AGGREGATE, OR SLAG MATERIALS ARE NOT ALLOWED. PROVIDE A FIRM, STABLE, AND SLIP RESISTANT TEMPORARY WALKWAY SURFACE TO COVER SHORT SEGMENTS OF ROUGH, SOFT, OR UNEVEN GROUND.

THE PEDESTRIAN TRAFFIC SIGNALS CONTROLLING CLOSED CROSSWALKS SHALL BE COVERED OR DEACTIVATED BY THE CITY OF ANN ARBOR. THE CONTRACTOR SHALL SCHEDULE AND COORDINATE THIS WORK WITH THE ENGINEER A MINIMUM OF 72 HOURS (NOT INCLUDING WEEKENDS & HOLIDAYS) PRIOR TO THE BEGINNING OF WORK THAT REQUIRES A SIDEWALK CLOSURE.

POST MOUNTED SIGNS LOCATED ADJACENT TO A SIDEWALK SHALL HAVE A 7 FOOT MINIMUM CLEARANCE FROM THE BOTTOM OF THE SIGN TO THE SIDEWALK SURFACE.


WHEN THE ENGINEER DETERMINES THAT THE CONTRACTOR'S OPERATIONS OR PLACEMENT OF TRAFFIC CONTROL DEVICES HAS CAUSED A SITUATION THAT THE VISIBILITY OF A TRAFFIC CONTROL DEVICE IS REDUCED ENOUGH TO CREATE A HAZARD, THE TRAFFIC CONTROL DEVICES SHALL BE DELINEATED WITH FLAGS OR OTHER ENGINEER-APPROVED DEVICES AT NO ADDITIONAL COST TO THE PROJECT.


MINIMIZE DISRUPTION TO PEDESTRIANS TO THE MAXIMUM EXTENT FEASIBLE BY PROVIDING AN APR IN THE FOLLOWING ORDER OF PREFERENCE:


- 1. PROVIDE THE APR ON THE SAME SIDE OF THE STREET AS THE DISRUPTED ROUTE UTILIZING BYPASSES.
- 2. WHERE IT IS NOT FEASIBLE TO PROVIDE A SAME SIDE APR, PROVIDE A DETOUR ON THE OTHER SIDE OF THE STREET.
- 3. WHERE IT IS NOT FEASIBLE TO PROVIDE AN APR ON THE OTHER SIDE OF THE ROADWAY, PROVIDE AN APR DETOUR WITH TRAILBLAZING SIGNS AS SHOWN ON THE PROJECT PLANS.


### SPECIFIC NOTES

- 1 TEMPORARY CURB RAMPS WITH DETECTABLE WARNINGS.
- 5 DEVICE TAPER 25 FEET LONG, RECOMMENDED WHEN THE CLOSED AREA WAS USED AS AN INTERMITTENT TRAFFIC LANE OR BYPASS LANE. STREET PARKING SHALL BE PROHIBITED FOR AT LEAST 50 FEET IN ADVANCE OF THE MID-BLOCK CROSSWALK.
- 3 AN APPROVED AUDIBLE MESSAGE DEVICE OR TACTILE MESSAGE SHOULD BE PROVIDED FOR SIGHT-IMPAIRED PEDESTRIANS.
- THE INTERNATIONAL SYMBOL OF ACCESSIBILITY SHALL BE DISPLAYED WHEN ANY WALKWAY THROUGH A WORK ZONE HAS BEEN DETERMINED TO BE TPAR COMPLIANT. THE SYMBOL OF ACCESSIBILITY SHALL NOT BE DISPLAYED IF PERSONS WITH DISABILITIES SHOULD NOT USE THE PRIMARY TEMPORARY PEDESTRIAN DETOUR. THE REASON FOR THE NON-COMPLIANCE SHALL BE POSTED AND AN ALTERNATE ROUTE SHALL BE POSTED WHEN THE PRIMARY TEMPORARY PEDESTRIAN DETOUR IS NON-COMPLIANT TO TPAR STANDARDS.
- 5 TYPICAL SIGN MESSAGE FOR A TEMPORARY PEDESTRIAN DETOUR SHALL INCLUDE INFORMATION SUCH AS THE DURATION OF THE WALKWAY RESTRICTIONS (BEGINNING AND/OR END DATES) AND A PROJECT CONTACT NUMBER FOR 24 / 7 QUESTIONS OR REPORTING HAZARDS.
- (6) SEE MMUTCD FOR GUIDANCE ON PLACEMENT AND USAGE OF BARRIER.









Know what's below.

Call before you dig.

 00
 ISSUED FOR BID
 03/28/2023
 CGT/BLA VCM/CEW

 REV.
 DATE
 DRAWN
 CHECKED

CITY OF ANN ARBOR PUBLIC SERVICES 301 EAST HURON STREET P.O. BOX 8647 ANN ARBOR, MI 48107-8647 734-794-6410 www.a2gov.org



ICES - ENGINEERING DNTIAC, SWIFT, MOORE, & RIGHT INFRASTRUCTURE

OR - PUBLIC SERVICES PONTIAC
WRIGHT

CITY OF ANN ARBOR-

T No.