



**NOTES:**

1. HOLE TO BE AUGERED. MINIMIZE DISTURBANCE OF IN-SITU SOILS DURING AUGERING.
2. CONTRACTOR TO PROVIDE PREFABRICATED ANCHOR BOLT BUILD-UP.
3. THE CITY WILL INSPECT THE AUGERED HOLE AND THE ANCHOR BOLT BUILD-UP AND PROVIDE WRITTEN APPROVAL PRIOR TO THE PLACEMENT OF CONCRETE.
4. NO WATER IS TO BE IN HOLE AT TIME OF CONCRETE PLACEMENT.
5. CONCRETE SHALL BE VIBRATED DURING PLACEMENT.
6. CONTRACTOR WILL PROVIDE NECESSARY CONDUIT FOR ENTRY. PAID FOR AT THE CONTRACT UNIT PRICE FOR 2" CONDUIT.
7. COPPER CLAD GROUND ROD (1 REQUIRED) TO BE 5/8" DIA. x 8'-0"
8. CONDUIT TO EXTEND 1-2" ABOVE BASE. CABLES TO EXTEND 6" OUTSIDE OF HANDHOLE.
9. SHIMS TO BE 1/2" MIN., PER D.E. SPEC
10. GROUND CABLE SHALL BE #6 SOFT BARE COPPER WIRE WELDED TO GROUND ROD WITH 24" SLACK ABOVE FOUNDATION TOP. THE NEUTRAL AT THE POLE IS TO BE CONNECTED TO THIS GROUND CABLE.

\* UNLESS OTHERWISE NOTED ON THE PLANS OR CONTRACT DOCUMENTS

<b>ADDED CLARIFYING DETAILS</b>				
	2	DPF	MB	2/09
<b>GENERAL REVISIONS</b>				
	1	NCF	CSS	1-31-94
<b>REVISIONS</b>		<b>REV. NO.</b>	<b>DR. BY</b>	<b>CH. BY</b>
<b>PUBLIC SERVICES DEPARTMENT</b>				
<b>CITY OF ANN ARBOR</b>				
STREETLIGHT FOUNDATION				
<b>DR. BY</b>	NCF	<b>CH. BY</b>	CSS	<b>DRAWING NO.</b>
<b>SCALE</b>	N.T.S.	<b>DATE</b>	11-6-92	SD-SL-1
				<b>SHEET NO.</b> ____ <b>OF</b> ____