

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
File No. 2013-034
ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|------------------------|--|-------------|---------------------------|-------------------|--------------------|
| 1047051 | Audio-visual Recording | LSUM | 1.000 | \$ _____ | \$ _____ |
| 1047051 | General Conditions, Max \$70,000 | LSUM | 1.000 | \$ _____ | \$ _____ |
| 1047051 | Project Supervision, Max \$40,000 | LSUM | 1.000 | \$ _____ | \$ _____ |
| 2020002 | Tree, Rem, 19 inch to 36 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 2020004 | Tree, Rem, 6 inch to 18 inch | Ea | 11.000 | \$ _____ | \$ _____ |
| 2030011 | Dr Structure, Rem | Ea | 10.000 | \$ _____ | \$ _____ |
| 2030015 | Sewer, Rem, Less than 24 inch | Ft | 100.000 | \$ _____ | \$ _____ |
| 2040080 | Exploratory Investigation, Vertical | Ft | 75.000 | \$ _____ | \$ _____ |
| 2047001 | Curb, Gutter, and Curb and Gutter, Any Type, Rem | Ft | 2027.000 | \$ _____ | \$ _____ |
| 2047011 | Sidewalk, Sidewalk Ramp, and Driveway Approach, Any Thickness, Rem | Syd | 515.000 | \$ _____ | \$ _____ |
| 2050023 | Granular Material, CI II | Cyd | 100.000 | \$ _____ | \$ _____ |
| 2057011 | Machine Grading, Modified | Syd | 11354.000 | \$ _____ | \$ _____ |
| 2057021 | Subgrade Undercutting | Cyd | 100.000 | \$ _____ | \$ _____ |
| 2080036 | Erosion Control, Silt Fence | Ft | 200.000 | \$ _____ | \$ _____ |
| 2087050 | Erosion Control, Inlet Filter | Ea | 40.000 | \$ _____ | \$ _____ |
| 2090001 | Project Cleanup | LSUM | 1.000 | \$ _____ | \$ _____ |
| 3020001 | Aggregate Base | Ton | 100.000 | \$ _____ | \$ _____ |
| 3060020 | Maintenance Gravel | Ton | 150.000 | \$ _____ | \$ _____ |
| TOTAL THIS PAGE | | | | \$ _____ | _____ |

ADD-2-2
ADD-1-8
BF-1

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
File No. 2013-034
ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|------------------------|---|-------------|---------------------------|-------------------|--------------------|
| 4020987 | Sewer, CI IV, 12 inch, Tr Det B | Ft | 100.000 | \$ _____ | \$ _____ |
| 4021260 | Trench Undercut and Backfill | Cyd | 50.000 | \$ _____ | \$ _____ |
| 4030010 | Dr Structure Cover, Type B | Ea | 34.000 | \$ _____ | \$ _____ |
| 4030050 | Dr Structure Cover, Type K | Ea | 10.000 | \$ _____ | \$ _____ |
| 4030200 | Dr Structure, 24 inch dia | Ea | 10.000 | \$ _____ | \$ _____ |
| 4030390 | Dr Structure, Temp Lowering | Ea | 10.000 | \$ _____ | \$ _____ |
| 4037050 | Adjust Structure Cover | Ea | 30.000 | \$ _____ | \$ _____ |
| 4047001 | Underdrain, Subgrade, 6 inch, Special | Ft | 6986.000 | \$ _____ | \$ _____ |
| 5010005 | HMA Surface, Rem | Syd | 11354.000 | \$ _____ | \$ _____ |
| 5010025 | Hand Patching | Ton | 80.000 | \$ _____ | \$ _____ |
| 5010703 | HMA, LVSP | Ton | 3280.000 | \$ _____ | \$ _____ |
| 6030005 | Cement | Ton | 0.500 | \$ _____ | \$ _____ |
| 8017011 | Driveway, Nonreinf Conc, 6 inch, Modified | Syd | 146.000 | \$ _____ | \$ _____ |
| 8020004 | Curb, Conc, Det E4 | Ft | 50.000 | \$ _____ | \$ _____ |
| 8027001 | Curb and Gutter, Conc | Ft | 1910.000 | \$ _____ | \$ _____ |
| 8027001 | Driveway Opening, Conc, Det M, Modified | Ft | 373.000 | \$ _____ | \$ _____ |
| 8037001 | Detectable Warning Surface, Modified | Ft | 35.000 | \$ _____ | \$ _____ |
| 8037010 | Sidewalk Ramp, Conc, 6 inch, Modified | Sft | 255.000 | \$ _____ | \$ _____ |
| TOTAL THIS PAGE | | | | \$ _____ | _____ |

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
File No. 2013-034
ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|-----------------|--|-------------|---------------------------|-------------------|--------------------|
| 8037010 | Sidewalk, Conc, 4 inch, Modified | Sft | 2353.000 | \$ _____ | \$ _____ |
| 8037010 | Sidewalk, Conc, 6 inch, Modified | Sft | 156.000 | \$ _____ | \$ _____ |
| 8087001 | Fence, Protective, Modified | Ft | 463.000 | \$ _____ | \$ _____ |
| 8107050 | No Parking Sign | Ea | 97.000 | \$ _____ | \$ _____ |
| 8110025 | Pavt Mrkg, Ovly Cold Plastic, 6 inch, White | Ft | 60.000 | \$ _____ | \$ _____ |
| 8110045 | Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar | Ft | 15.000 | \$ _____ | \$ _____ |
| 8110078 | Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym | Ea | 2.000 | \$ _____ | \$ _____ |
| 8120012 | Barricade, Type III, High Intensity, Double Sided, Lighted, Furn | Ea | 10.000 | \$ _____ | \$ _____ |
| 8120013 | Barricade, Type III, High Intensity, Double Sided, Lighted, Oper | Ea | 10.000 | \$ _____ | \$ _____ |
| 8120140 | Lighted Arrow, Type C, Furn | Ea | 2.000 | \$ _____ | \$ _____ |
| 8120141 | Lighted Arrow, Type C, Oper | Ea | 2.000 | \$ _____ | \$ _____ |
| 8120260 | Plastic Drum, High Intensity, Lighted, Furn | Ea | 50.000 | \$ _____ | \$ _____ |
| 8120261 | Plastic Drum, High Intensity, Lighted, Oper | Ea | 50.000 | \$ _____ | \$ _____ |
| 8120330 | Sign, Portable, Changeable Message, Furn | Ea | 1.000 | \$ _____ | \$ _____ |
| 8120331 | Sign, Portable, Changeable Message, Oper | Ea | 1.000 | \$ _____ | \$ _____ |
| 8120350 | Sign, Type B, Temp, Prismatic, Furn | Sft | 400.000 | \$ _____ | \$ _____ |
| 8120351 | Sign, Type B, Temp, Prismatic, Oper | Sft | 400.000 | \$ _____ | \$ _____ |
| 8120352 | Sign, Type B, Temp, Prismatic, Special, Furn | Sft | 100.000 | \$ _____ | \$ _____ |
| TOTAL THIS PAGE | | | | \$ _____ | _____ |

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
File No. 2013-034
ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|-----------------|--|-------------|---------------------------|-------------------|--------------------|
| 8120353 | Sign, Type B, Temp, Prismatic, Special, Oper | Sft | 100.000 | \$ _____ | \$ _____ |
| 8120370 | Traf Regulator Control | LSUM | 1.000 | \$ _____ | \$ _____ |
| 8127051 | Minor Traffic Control, Max \$7,500 | LSUM | 1.000 | \$ _____ | \$ _____ |
| 8150335 | Amelanchier x grandifolia 'Robin Hill', 2 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8150547 | Betula nigra, tree form, 2 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8150808 | Cercis canadensis, tree form, 2 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8152309 | Malus 'Harvest Gold', 2 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8152312 | Malus 'Indian Magic', 2 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8152315 | Malus 'Prairie Fire', 2 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8152330 | Malus 'Snowdrift', 2 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8152513 | Nyssa sylvatica, 2 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8153113 | Quercus robur, 2 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8153717 | Syringa reticulata 'Ivory Silk', 1 3/4 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8167011 | Slope Restoration | Syd | 3039.000 | \$ _____ | \$ _____ |
| 8167011 | Ball Field Restoration | Syd | 450.000 | \$ _____ | \$ _____ |
| 8230075 | Gate Well, Abandon | Ea | 5.000 | \$ _____ | \$ _____ |
| 8230431 | Gate Box, Adj, Case 1 | Ea | 2.000 | \$ _____ | \$ _____ |
| 8237001 | Water Main, Abandon | Ft | 3315.000 | \$ _____ | \$ _____ |
| TOTAL THIS PAGE | | | | \$ _____ | _____ |

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
File No. 2013-034
ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|-----------------|---|-------------|---------------------------|-------------------|--------------------|
| 8237001 | Water Main, DI w/Polyethylene Wrap, 12 inch, Tr Det I Modified | Ft | 1758.000 | \$ _____ | \$ _____ |
| 8237001 | Water Main, DI w/Polyethylene Wrap, 12 inch, Tr Det VI Modified | Ft | 365.000 | \$ _____ | \$ _____ |
| 8237001 | Water Main, DI w/Polyethylene Wrap, 6 inch, Tr Det I Modified | Ft | 81.000 | \$ _____ | \$ _____ |
| 8237001 | Water Main, DI w/Polyethylene Wrap, 8 inch, Tr Det I Modified | Ft | 2031.000 | \$ _____ | \$ _____ |
| 8237001 | Water Main, DI w/Polyethylene Wrap, 8 inch, Tr Det VI Modified | Ft | 127.000 | \$ _____ | \$ _____ |
| 8237001 | Water Main, HDPE, 14 inch, Directional Drill | Ft | 310.000 | \$ _____ | \$ _____ |
| 8237001 | Water Service Tap and Lead, Excavate and Backfill | Ft | 497.000 | \$ _____ | \$ _____ |
| 8237050 | Fire Hydrant Assembly, w/Extensions, Complete | Ea | 9.000 | \$ _____ | \$ _____ |
| 8237050 | Fire Hydrant, Rem | Ea | 2.000 | \$ _____ | \$ _____ |
| 8237050 | Gate Valve-in-Box, 12 inch | Ea | 5.000 | \$ _____ | \$ _____ |
| 8237050 | Gate Valve-in-Box, 6 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8237050 | Gate Valve-in-Box, 8 inch | Ea | 7.000 | \$ _____ | \$ _____ |
| 8237050 | Gate Valve-in-Well, 12 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8237050 | Gate Valve-in-Well, 8 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, 11.25 deg Bend, 12 inch | Ea | 4.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, 11.25 deg Bend, 8 inch | Ea | 2.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, 22.5 deg Bend, 12 inch | Ea | 2.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, 22.5 deg Bend, 8 inch | Ea | 7.000 | \$ _____ | \$ _____ |
| TOTAL THIS PAGE | | | | \$ _____ | _____ |

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
File No. 2013-034
ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|-----------------|--|-------------|---------------------------|-------------------|--------------------|
| 8237050 | Water Main, DI, 45 deg Bend, 12 inch | Ea | 13.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, 45 deg Bend, 8 inch | Ea | 15.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Reducer, 12 inch by 6 inch | Ea | 2.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Reducer, 12 inch by 8 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Reducer, 8 inch by 4 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Reducer, 8 inch X 6 inch | Ea | 8.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Tee, 12 inch by 12 inch | Ea | 3.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Tee, 12 inch by 8 inch | Ea | 6.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Tee, 6 inch by 6 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Tee, 8 inch by 6 inch | Ea | 1.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, DI, Tee, 8 inch by 8 inch | Ea | 4.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, Line Stop, Temp, 4 inch or 6 inch | Ea | 2.000 | \$ _____ | \$ _____ |
| 8237050 | Water Main, Tie-In | Ea | 4.000 | \$ _____ | \$ _____ |
| 8507001 | Sewer, SDR 26 PVC, Service Lead, 6 inch, Tr Det I Modified | Ft | 100.000 | \$ _____ | \$ _____ |
| 8507050 | Sewer, SDR 26 PVC, 45 deg Bend, 6 inch | Ea | 10.000 | \$ _____ | \$ _____ |
| 8507050 | Sewer, SDR 26 PVC, Riser, 6 inch | Ea | 10.000 | \$ _____ | \$ _____ |
| 8507050 | Sewer, SDR 26 PVC, Tee or Wye, 10 inch by 6 inch | Ea | 10.000 | \$ _____ | \$ _____ |
| 8507050 | Sewer, SDR 26 PVC, Tee or Wye, 8 inch by 6 inch | Ea | 10.000 | \$ _____ | \$ _____ |
| TOTAL THIS PAGE | | | | \$ _____ | _____ |

BID FORM
Section 1 - Schedule of Prices

Hewett Dr, Russell Rd, Russett Rd, and Redeemer Ave Water Main Replacement Project
 File No. 2013-034
 ITB No. 4378

| <u>Item No.</u> | <u>Item Description</u> | <u>Unit</u> | <u>Estimated Quantity</u> | <u>Unit Price</u> | <u>Total Price</u> |
|-----------------|---|-------------|---------------------------|-------------------|--------------------|
| | TOTAL FROM PAGE BF-1 (ADD-1-8 ADD-2-2) | | | \$ | _____ |
| | TOTAL FROM PAGE BF-2 (ADD-1-9 ADD-2-3) | | | \$ | _____ |
| | TOTAL FROM PAGE BF-3 (ADD-1-10 ADD-2-4) | | | \$ | _____ |
| | TOTAL FROM PAGE BF-4 (ADD-1-11 ADD-2-5) | | | \$ | _____ |
| | TOTAL FROM PAGE BF-5 (ADD-1-12 ADD-2-6) | | | \$ | _____ |
| | TOTAL FROM PAGE BF-6 (ADD-1-13 ADD-2-7) | | | \$ | _____ |
| | TOTAL BASE BID | | | \$ | _____ |

ADD-2-8
 ADD-1-14