CITY OF ANN ARBOR INVITATION TO BID



EIGHTH STREET SANITARY SEWER MANHOLE REPLACEMENT

ITB # 4337 Due Date: May 8, 2014 On or Before 2:00 P.M.

> Public Services Area Field Operations Services Unit

> > Issued By:

City of Ann Arbor Procurement Unit 301 E. Huron Street Ann Arbor, MI 48104

TABLE OF CONTENTS

<u>Section</u> <u>F</u>	Pages
Table of ContentsT	C-1
AdvertisementAD-1	to 2
Notice of Pre-Bid ConferenceN	IP-1
Instructions to BiddersIB-1	to 5
Contract Compliance FormsAFF-1	to 3
Living Wage FormsAFF-4	to 5
Vendor Conflict of Interest Disclosure FormAF	F-6
Invitation to BidITB-1	to 3
Bid Forms BF-1	to 7
Contract	to 4
Bond FormsB-1	to 2
General ConditionsGC-1 to	o 20
Standard SpecificationsS	S-1
Detailed Specifications	
Section 01000 General Requirements	50-1 40-1

Appendix A – Soil Borings

ADVERTISEMENT FOR THE EIGHTH STREET SANITARY SEWER MANHOLE REPLACEMENT CITY OF ANN ARBOR

ITB NO. 4337

Sealed Bids will be received by the City of Ann Arbor Customer Service Desk, First (1st) Floor, 301 East Huron Street, Guy Larcom City Hall, on or before <u>Thursday, May 8, 2014 by 2:00 PM</u> (Local Time) for the construction of <u>Eighth Street Sanitary Sewer Manhole Replacement</u>. Bids will be publically opened and read aloud at this time.

Work to be done includes: replacement of two existing sanitary manholes, replacement of 62 lineal feet of 8-inch sanitary sewer, bituminous pavement replacement and all related work necessary.

Bid documents, plans, specifications, and addenda shall be downloaded by Bidders at either of the following websites: Michigan Inter-governmental Trade Network (MITN) www.mitn.info or City of Ann Arbor Purchasing website: www.A2gov.org. It is the Bidder's responsibility to verify they have obtained all information before submitting a bid.

Each Bid shall be accompanied by a certified check, or Bid Bond by a recognized surety, in the amount of 5% of the total of the bid price. A Bid, once submitted, becomes the property of the City. In the sole discretion of the City, the City reserves the right to allow a bidder to reclaim submitted documents provided the documents are requested and retrieved no later than 48 hours prior to the scheduled bid opening.

The successful Bidder will be required to furnish satisfactory performance and labor and material bonds in the amount of 100% of the bid price and satisfactory insurance coverage.

Precondition for entering into a Contract with the City of Ann Arbor is compliance with Chapter 112 of Title IX of the Code of the City of Ann Arbor. The successful Bidder may also be required to comply with Chapter 23 of Title I of the Code of the City of Ann Arbor. Further information is outlined in the Contract Documents. All bidders are required to complete and submit the City of Ann Arbor Conflict of Interest Disclosure Form with the bid.

After the time of opening, no Bid may be withdrawn for a period of 90 days. The City reserves the right to accept any Bid, to reject any or all Bids, to waive irregularities and/or informalities in any Bid, and to make the award in any manner the City believes to be in its best interest.

Version 01/2010 AD-1

All questions regarding this ITB shall be submitted via email. Emailed questions and inquires will be accepted from any and all prospective Bidders in accordance with the terms and conditions of the ITB.

All questions shall be submitted by <u>Thursday</u>, <u>May 1, 2014 at 5:00 PM</u> and should be addressed as follows:

Specification/Scope of Work questions emailed to chris.elenbaas@stantec.com
Bid Process and HR Compliance questions emailed to MBerryman@a2gov.org.

Any further information on bid documents may be obtained from the Procurement Office, (734) 794-6500.

CITY OF ANN ARBOR PROCUREMENT UNIT

Version 01/2010 AD-2

NOTICE OF PRE-BID CONFERENCE

A pre-bid conference for this project will be held on <u>Tuesday, April 29, 2014 at 1:00 PM</u> at the W.R. Wheeler Service Center located at 4251 Stone School Road, Ann Arbor, Michigan 48108.

Attendance at this conference is highly recommended. Administrative and technical questions regarding this project will be answered at this time. The pre-bid conference is for information only. Any answers furnished will not be official until verified in writing by the Financial Service Area, Procurement Unit. Answers that change or substantially clarify the bid will be affirmed in an addendum.

Version 01/2010 NP-1

INSTRUCTIONS TO BIDDERS

General

Work to be done under this Contract is generally described through the detailed specifications and must be completed fully in accordance with the contract documents. All work to be done under this Contract is located in or near the City of Ann Arbor.

The City shall make available to all prospective Bidders, prior to receipt of the Bids, access to the area in which the work is to be performed. Advance notice should be given to the Administering Service Area/Unit in cases where access to the site must be arranged by the City.

Any Bid which does not conform fully to these instructions may be rejected.

Preparation of Bids

Bids should be prepared providing a straight-forward, concise description of the Bidder's ability to meet the requirements of the ITB. Bids shall be written in ink or typewritten. No erasures are permitted. Mistakes may be crossed out and corrected and must be initialed and dated in ink by the person signing the Bid.

Bids must be submitted on Page Numbers ITB 1-3 and on the "Bid Forms" provided with each blank properly filled in. If forms are not fully completed it may disqualify the bid.

Each person signing the Bid certifies that he/she is the person in the Bidder's firm/organization responsible for the decision as to the fees being offered in the Bid and has not and will not participated in any action contrary to the terms of this provision.

Questions or Clarification on ITB Specifications

All questions regarding this ITB shall be submitted via email. Emailed questions and inquires will be accepted from any and all prospective Bidders in accordance with the terms and conditions of the ITB.

All questions shall be submitted by <u>Thursday</u>, <u>May 1, 2014 at 5:00 PM</u> and should be addressed as follows:

Specification/Scope of Work questions emailed to chris.elenbaas@stantec.com
Bid Process and HR Compliance questions emailed to MBerryman@a2gov.org.

Addenda

If it becomes necessary to revise any part of the ITB, notice of the Addendum will be posted to Michigan Inter-governmental Trade Network (MITN) www.mitn.info and/or City of Ann Arbor web site www.A2gov.org for all parties to download.

Each Bidder must in its Bid, to avoid any miscommunications, acknowledge all addenda which it has received, but the failure of a Bidder to receive, or acknowledge receipt of; any addenda shall not relieve the Bidder of the responsibility for complying with the terms thereof.

The City will not be bound by oral responses to inquiries or written responses other than written addenda.

Bid Submission

All Bids are due and must be delivered to the City of Ann Arbor Procurement Unit on or before <u>Thursday</u>, <u>May 8</u>, <u>2014 by 2:00 PM</u>. Bids submitted late or via oral, telephonic, telegraphic, electronic mail or facsimile **will not** be considered or accepted.

Each Bidder must submit one (1) original Bid and two (2) additional Bid copies in a sealed envelope clearly marked: ITB No. 4337 – Eighth Street Sanitary Sewer Manhole Replacement.

Bids must be addressed and delivered to:

City of Ann Arbor Procurement Unit C/O Customer Service 1st Floor 301 East Huron Street P.O. Box 8647 Ann Arbor, MI 48104

All Bids received on or before the Due Date will be publicly opened and recorded immediately. No immediate decisions are rendered.

Hand delivered Bids will be date/time stamped/signed by the Procurement Unit at the address above in order to be considered. Normal business hours are 9:00 a.m. to 3:00 p.m. Monday through Friday, excluding Holidays. The City will not be liable to any Bidder for any unforeseen circumstances, delivery or postal delays. Postmarking to the Due Date will not substitute for receipt of the Bid. Each Bidder is responsible for submission of their Bid.

Additional time for submission of bids past the stated due date and time will not be granted to a single Bidder; however, additional time may be granted to all Bidders when the City determines in its sole discretion that circumstances warrant it.

Award

The City intends to award a Contract(s) to the lowest responsible Bidder(s). On multidivisional contracts, separate divisions may be awarded to separate Bidders. The City may also utilize alternatives offered in the Bid Forms, if any, to determine the lowest responsible Bidder on each division, and award multiple divisions to a single Bidder, so that the lowest total cost is achieved for the City. For unit price bids, the contract will be awarded based upon the unit prices and the lump sum prices stated by the bidder for the work items specified in the bid documents, with consideration given to any alternates selected by the City. If the City determines that the unit price for any item is materially different for the work item bid than either other bidders or the general market, the City, in its sole discretion, in addition to any other right it may have, may reject the bid as not responsible or nonconforming.

The acceptability of major subcontractors will be considered in determining if a Bidder is responsible. In comparing Bids, the City will give consideration to alternate Bids for items listed in the bid forms.

Qualifications

The City will evaluate Proposals based on cost as well as experience. Contractors that have not included the required list of similar work experience and associated references in Section 5 of the Bid Form may have their bid rejected.

As part of the proposal, Bidders shall provide documentation that the Bidder's company has at least 10 years of experience performing construction on similar projects. Bidders shall also submit the attached form, "Section 5 – References," which identifies a minimum of three projects completed in the past five years on similar projects, including construction cost, contractor and subcontractor information, that demonstrate similar work experience and complexity to that included within these contract documents.

All key staff and subcontractors are subject to the approval by the City.

Official Documents

The City of Ann Arbor shall accept no alternates to the bid documents made by the Bidder unless those alternatives are set forth in the "Alternate" section of Bid form.

The City of Ann Arbor officially distributes bid documents from the Procurement Unit or through the Michigan Intergovernmental Trade Network (MITN). Copies of the bid documents obtained from any other source are not Official copies. Addenda and other bid information will only be posted to these official distribution sites. If you obtained City of Ann Arbor Bid documents from other sources, it is recommended that you register on www.MITN.info and obtain an official Bid.

Bid Security

Each bid <u>must be accompanied</u> by a certified check, or Bid Bond by a surety licensed and authorized to do business within the State of Michigan, in the amount of 5% of the total of the bid price.

Withdrawal of Bids

After the time of opening, no Bid may be withdrawn for the period of 90 days specified in the Advertisement.

Contract Time

Time is of the essence in the performance of the work under this Contract. The available time for work under this Contract is indicated on page C-1, Article III of the Contract. If these time requirements can not be met, the Bidder must stipulate on Bid Form Section 3 - Time Alternate its schedule for performance of the work. Consideration will be given to time in evaluating bids.

Liquidated Damages

A liquidated damages clause, as given on page C-2, Article III of the Contract, provides that the Contractor shall pay the City as liquidated damages, and not as a penalty, a sum certain per day for each and every day that the Contractor may be in default of completion of the specified work, within the time(s) stated in the Contract, or written extensions.

Liquidated damages clauses, as given in the General Conditions, provide further that the City shall be entitled to impose and recover liquidated damages for breach of the obligations under Chapter 112 of the City Code.

The liquidated damages are for the non-quantifiable aspects of any of the previously identified events and do not cover actual damages that can be shown or quantified nor are they intended to preclude recovery of actual damages in addition to the recovery of liquidated damages.

Human Rights Information

Section 5, beginning at page GC-3, outlines the requirements for fair employment practices under City of Ann Arbor Contracts. To establish compliance with this Ordinance, the Bidder should complete and return with its bid completed copies of the Human Rights Division Contract Compliance Forms or an acceptable equivalent. In the event Human Rights forms are not submitted with bid, the Bidder will have 24 hours to provide once requested by the City.

Wage Requirements

Section 4, beginning at page GC-2, outlines the requirements for payment of prevailing wages or of a "living wage" to employees providing service to the City under this contract. The successful bidder must comply with all applicable requirements and provide documentary proof of compliance when requested.

Conflict of Interest Disclosure

The City of Ann Arbor Purchasing Policy requires that prospective Vendors complete a Conflict of Interest Disclosure form (a copy of which is attached to this ITB). A contract may not be awarded to the selected Vendor unless and until the Procurement Unit and the City Administrator have reviewed the Disclosure form and determined that no conflict exists under applicable federal, state, or local law or administrative regulation. Not every relationship or situation disclosed on the Disclosure Form may be a disqualifying conflict. Depending on applicable law and regulations, some contracts may awarded on the recommendation of the City Administrator after full disclosure, where such action is allowed by law, if demonstrated competitive pricing exists and/or it is determined the award is in the best interest of the City.

Major Subcontractors

The Bidder shall identify each major subcontractor it expects to engage for this Contract if the work to be subcontracted is 15% or more of the bid sum or over \$50,000, whichever is less. The Bidder also shall identify the work to be subcontracted to each major subcontractor.

Debarment

Submission of a Bid in response to this ITB is certification that the Bidder is not currently debarred, suspended, proposed for debarment, and declared ineligible or voluntarily excluded from participation in this transaction by any State or Federal departments or agency. Submission is also agreement that the City will be notified of any changes in this status.

Disclosures

After bids are opened, all information in a submitter's bid is subjected to disclosure under the provisions of Michigan Public Act No. 442 of 1976, as amended (MCL 15.231 et seq.) known as the "Freedom of Information Act". The Freedom of Information Act also provides for the complete disclosure of contracts and attachments thereto except where specifically exempted.

Bid Protest

All Bid protests must be in writing and filed with the Purchasing Agent within five (5) business days of the award action. The Bidder must clearly state the reasons for the protest. If a Bidder contacts a City Service Area/Unit and indicates a desire to protest an award, the Service Area/Unit shall refer the Bidder to the Purchasing Agent. The Purchasing Agent will provide the Bidder with the appropriate instructions for filing the protest. The protest shall be reviewed by the City Administrator or designee whose decision shall be final.

Reservation of Rights

The City of Ann Arbor reserves the right to accept any bid or alternative bid proposed in whole or in part, to reject any or all bids or alternatives bids in whole or in part and to waive irregularity and/or informalities in any bid and to make the award in any manner deemed in the best interest of the City.

CONTRACT COMPLIANCE FORMS

City of Ann Arbor Procurement Office INSTRUCTIONS FOR CONTRACTORS

For Completing CONTRACT COMPLIANCE FORM

City Policy

The "non discrimination in contracts" provision of the City Code, (Chapter 112, Section 9:161) requires contractors/Bidders/grantees doing business with the City not to discriminate on the basis of actual or perceived race, color, religion, national origin, sex, age, condition of pregnancy, marital status, physical or mental limitations, source of income, family responsibilities, educational association, sexual orientation, gender identity or HIV status against any of their employees, any City employee working with them, or any applicant for employment. It also requires that the contractors/Bidders/grantees include a similar provision in all subcontracts that they execute for City work or programs.

This Ordinance further requires that each prospective contractor/Bidder submit employment data to the City showing current total employee breakdown by occupation, race and gender. This allows the Human Rights Office to determine whether or not the contractor/Bidder has a workforce that is reflective of the availability of women and under-represented minorities within the contractor's labor recruitment area (the area where they can reasonably be expected to recruit employees). *This data is provided to the City on the Human Rights Contract Compliance Forms (attached)*.

To complete the form:

- 1) If a company has more than one location, then that company must complete 2 versions of the form.
 - Form #1 should contain the employment data for the entire corporation.
 - Form #2 should contain the employment data for those employees:
 - who will be working on-site;
 - in the office responsible for completing the contract; or,
 - in the case of non-profit grantees, those employees working on the project funded by the City grant(s).
- 2) If the company has only one location, fill out Form #1 only.
- 3) Complete all data in the upper section of the form including the name of the person who completes the form and the name of the company/organization's president.
- 4) Complete the Employment Data in the remainder of the form. Please be sure to complete all columns including the Total Columns on the far right side of the form, and the Total row and Previous Year Total row at the bottom of the form.
- 5) Return the completed form(s) to *your contact* in the City Department for whom you will be conducting the work.

For assistance in completing the form, contact: Procurement Office of the City of Ann Arbor

(734) 794-6500

If a contractor is determined to be out of compliance, the Procurement Office will work with them to assist them in coming into compliance.

CITY OF ANN ARBOR HUMAN RIGHTS OFFICE CONTRACT COMPLIANCE FORM

Entire Organization (Totals for All Locations where applicable)

Name of	Company/Organization				Date Form Completed	
Name an	d Title of Person Completin	ng this Form		Name of President		
Address_	(Street address)	(City)	(State)	County	Phone #	(Area Code)
E#	(Street address)	(City)	,	(Zip)		(Alea Code)
Fax#	(Area Code)		Email Address			

EMPLOYMENT DATA

						EMPLOYM N		of Employees	 }				
Job Categories													
				Male					-		male		
	White	Black or African American	Asian	Hispanic or Latino	Native Hawaiian or Other Pacific Islander	American Indian or Alaska Native	White	Black or African American	Asian	Hispanic or Latino	Native Hawaiian or Other Pacific Islander	American Indian or Alaskan Native	TOTAL COLUMNS
	A	В	C	D	E	F	G	Н	I	J	K	L	A-L
Exec/Sr. Level Officials													
Supervisors													
Professionals													
Technicians													
Sales													
Admin. Support													
Craftspeople													
Operatives													
Service Workers													
Laborers/Helper													
Apprentices													
Other													
TOTAL													
PREVIOUS YEAR TOTAL					G-11 (724)								

Questions about this form?

Call (734)794-6500

CITY OF ANN ARBOR HUMAN RIGHTS OFFICE CONTRACT COMPLIANCE FORM

Local Office (Only those employees that will do local or on-site work, if applicable)

Name of Company/Or	ganization							Date	Form Complete	d			
Name and Title of Per	son Completii	ng this Form_				Na	me of Pres	ident					
Address							County		Pho	ne #	(Area Co		
(Street add	ress)	(City)		(State)	(Z	ip)				(Area Co	ode)	
Fax#				Email Addı	ress								
(Area Code)	1							MENT DAT					
Job Categories								f Employees in only one					
Ö				Male		` •	•		<u> </u>	Fema	ıle		
	White	Black or African American	Asian	Hispanic or Latino	Native Hawaiian or Other Pacific	American Indian or Alaska Native	White	Black or African American	Asian	Hispanic or LatinO	Native Hawaiian or Other Pacific	American Indian or Alaskan Native	TOTAL COLUMNS
	A	В	С	D	Islander E	F	G	Н	I	J	Islander K	L	A-L
Exec/Sr. Level Officials				_					_				
Supervisors													
Professionals													
Technicians													
Sales													
Admin. Support													
Craftspeople													
Operatives													
Service Workers													
Laborers/Helper													
Apprentices													
Other													
TOTAL													
PREVIOUS													

Questions about this form? Call 734-794-6500

YEAR TOTAL

ATTACHMENT C CITY OF ANN ARBOR LIVING WAGE ORDINANCE DECLARATION OF COMPLIANCE

The Ann Arbor Living Wage Ordinance (Section 1:811-1:821 of Chapter 23 of Title I of the Code) requires that employers providing services to the City or recipients of grants for financial assistance (in amounts greater than \$10,000 in a twelve-month period of time) pay their employees who are working on the City project or grant, a minimum level of compensation known as the **Living Wage**. This wage must be paid to the employees for the length of the contract/project.

	nies employing fewer than 5 persons and non-prof nce. If this exemption applies to your firm, please							
	individuals.		nat we employ or contract with fewer than 5					
	This <u>non-profit agency</u> is exen than 10 employees.	npt due to th	ne fact that we employ or contract with fewer					
The Or	dinance requires that all contractors/vendors and/	or grantees	agree to the following terms:					
a)	To pay each of its employees performing work on any covered contract or grant with the City, no less than the living wage, which is defined as \$12.78/hour when health care is provided, or no less than \$14.25/hour for those employers that do <i>not</i> provide health care. It is understood that the Living Wage will be adjusted each year on April 30, and covered employers will be required to pay the adjusted amount thereafter. The rates stated above include any adjustment for 2014.							
b)	Please check the boxes below which apply to yo	our workforc	e:					
OR	☐ Employees who are assigned to any covered C living wage without health benefits Yes							
O.A.	☐ Employees who are assigned to <i>any covered</i> C living wage <u>with health benefits</u> Yes_							
c)	To post a notice approved by the City regarding to location in which employees or other persons co							
d)	To provide the City payroll records or other docu	umentation a	as requested; and,					
e)	To permit access to work sites to City representation of non-compliance.	entatives fo	or the purposes of monitoring compliance,					
	dersigned authorized representative hereby obliga ons under penalty of perjury and violation of the O		ractor/vendor or grantee to the above stated					
Company	y Name		Address, City, State, Zip					
Signature	e of Authorized Representative		Phone (area code)					
Type or F	Print Name and Title		Email address					
Date sign	ned Questions about this for	orm? Place	o contact.					

Procurement Office City of Ann Arbor Phone: 734/794-6500

CITY OF ANN ARBOR LIVING WAGE ORDINANCE

RATE EFFECTIVE APRIL 30, 2014 - ENDING APRIL 29, 2015

\$12.78 per hour

If the employer provides health care benefits*

\$14.25 per hour

If the employer does **NOT** provide health care benefits*

Employers providing services to or for the City of Ann Arbor or recipients of grants or financial assistance from the City of Ann Arbor for a value of more than \$10,000 in a twelve-month period of time must pay those employees performing work on a City of Ann Arbor contract or grant, the above living wage.

ENFORCEMENT

The City of Ann Arbor may recover back wages either administratively or through court action for the employees that have been underpaid in violation of the law. Persons denied payment of the living wage have the right to bring a civil action for damages in addition to any action taken by the City.

Violation of this Ordinance is punishable by fines of not more than \$500/violation plus costs, with each day being considered a separate violation. Additionally, the City of Ann Arbor has the right to modify, terminate, cancel or suspend a contract in the event of a violation of the Ordinance.

* Health Care benefits include those paid for by the employer or making an employer contribution toward the purchase of health care. The employee contribution must not exceed \$.50 an hour for an average work week; and the employer cost or contribution must equal no less than \$1/hr for the average work week.

The Law Requires Employers to Display This Poster Where Employees Can Readily See It.

For Additional Information or to File a Complaint Contact Mark Berryman at 734/794-6500 or mberryman@a2gov.org

Revised 3/2014 LW-1



Vendor Conflict of Interest Disclosure Form

All vendors interested in conducting business with the City of Ann Arbor must complete and return the Vendor Conflict of Interest Disclosure Form in order to be eligible to be awarded a contract. Please note that all vendors are subject to comply with the City of Ann Arbor's conflict interest policies as stated within the certification section below.

If a vendor has a relationship with a City of Ann Arbor official or employee, an immediate family member of a City of Ann Arbor official or employee, the vendor shall disclose the information required below.

Certification: I hereby certify that to my knowledge, there is no conflict of interest involving the vendor named below:

- 1. No City official or employee or City employee's immediate family member has an ownership interest in vendor's company or is deriving personal financial gain from this contract.
- 2. No retired or separated City official or employee who has been retired or separated from the City for less than one (1) year has an ownership interest in vendor's Company.
- 3. No City employee is contemporaneously employed or prospectively to be employed with the vendor.
- 4. Vendor hereby declares it has not and will not provide gifts or hospitality of any dollar value or any other gratuities to any City employee or elected official to obtain or maintain a contract.
- 5. Please note any exceptions below:

Vendor Name	Vendor Phone Number
Conflict of Int	erest Disclosure *
Name of City of Ann Arbor employees, elected officials, or immediate family members with who there maybe a potential conflict of interest.	
*Disclosing a potential conflict of interest does not disqueconflicts of interest and they are detected by the City, velocity that the information provided is true are	•
Signature of Vendor Authorized Representative Date of PROCUREMENT USE ONLY	Printed Name of Vendor Authorized Representative
Yes, named employee was involved in Bid / Proposa	process.
No, named employee was not involved in procureme	nt process or decision.

INVITATION TO BID

City of Ann Arbor
Guy C. Larcom Municipal Building
Ann Arbor, Michigan 48104

Ladies and Gentlemen:

The undersigned, as Bidder, declares that this Bid is made in good faith, without fraud or collusion with any person or persons bidding on the same Contract; that this Bidder has carefully read and examined the bid documents, including Advertisement, Human Rights Division Contract Compliance Forms, Conflict of Interest Disclosure Form, Notice of Pre-Bid Conference, Instructions to Bidders, Bid, Bid Forms, Contract, Bond Forms, General Conditions, Standard Specifications, Detailed Specifications, all Addenda, and the Plans and understands them. The Bidder declares that it conducted a full investigation at the site and of the work proposed and is fully informed as to the nature of the work and the conditions relating to the work's performance. The Bidder also declares that it has extensive experience in successfully completing projects similar to this one.

The Bidder acknowledges that it has not received or relied upon any representations or warrants of any nature whatsoever from the City of Ann Arbor, its agents or employees, and that this Bid is based solely upon the Bidder's own independent business judgment.

The undersigned proposes to perform all work shown on the plans or described in the bid documents, including any addenda issued, and to furnish all necessary machinery, tools, apparatus, and other means of construction to do all the work, furnish all the materials, and complete the work in strict accordance with all terms of the Contract of which this Bid is one part.

In accordance with these bid documents, and Addenda numbered ______, the undersigned, as Bidder, proposes to perform at the sites in and/or around Ann Arbor, Michigan, all the work included herein for the amounts set forth in the Bid Forms.

The Bidder declares that it has become fully familiar with the liquidated damage clauses for completion times and for compliance with City Code Chapter 112, understands and agrees that the liquidated damages are for the non-quantifiable aspects of non-compliance and do not cover actual damages that may be shown and agrees that if awarded the Contract, all liquidated damage clauses form part of the Contract.

The Bidder declares that it has become fully familiar with the provisions of Chapter 14, Section 1:319 (Prevailing wages) and Chapter 23 (Living Wage) of the Code of the City of Ann Arbor and that it understands and agrees to comply, to the extent applicable to employees providing services to the City under this Contract, with the wage and reporting

Version 01/2010 ITB-1

requirements stated in the City Code provisions cited. Bidder further agrees that the cited provisions of Chapter 14 and Chapter 23 form a part of this Contract.

The Bidder declares that it has become familiar with the City Conflict of Interest Disclosure Form and certifies that the statement contained therein is true and correct.

The Bidder encloses a certified check or Bid Bond in the amount of 5% of the total of the Bid Price. The Bidder agrees both to contract for the work and to furnish the necessary Bonds and insurance documentation within 10 days after being notified of the acceptance of the Bid.

If this Bid is accepted by the City and the Bidder fails to contract and furnish the required Bonds and insurance documentation within 10 days after being notified of the acceptance of this Bid, then the Bidder shall be considered to have abandoned the Contract and the certified check or Bid Bond accompanying this Bid shall become due and payable to the City.

If the Bidder enters into the Contract in accordance with this Bid, or if this Bid is rejected, then the accompanying check or Bid Bond shall be returned to the Bidder.

In submitting this Bid, it is understood that the right is reserved by the City to accept any Bid, to reject any or all Bids, to waive irregularities and/or informalities in any Bid, and to make the award in any manner the City believes to be in its best interest.

SIGNED THIS	DAY OF	, 20	
Bidder's Name		Authorized Signature of Bidder	
Official Address		(Print Name of Signer Above)	
Telephone Number		Email Address for Award Notice	

Version 01/2010 ITB-2

LEGAL STATUS OF BIDDER

(The Bidder shall fill out the appropriate form and strike out the other two.)

By signing below the authorized representative of the Bidder hereby certifies that:

The Bidder is:	
 A corporation organized ar 	nd doing business under the laws of the state of bearing the office title of ure is affixed to this proposal, is authorized to respondent.*
*If not incorporated in Michiga	an, please attach the corporation's Certificate of Authority
	doing business under the laws of the state of bearing the title of
whose signature is affixed to the behalf of the LLC.	nis proposal, is authorized to execute contract on
and filed with the county of including street and mailing ad	e with address, is affixed to this Bid.
Signature	Date:,
(Print) Name	Title
Firm:	
Address:	
Contact Phone	Fax
Email	

Version 01/2010 ITB-3

Section 1 – Schedule of Prices

Project: Eighth Street Sanitary Sewer Manhole Replacement						
Ridder's	Name:					

Notes:

- 1. All bidders shall provide a Unit Price and Total Price for all bid items specified.
- 2. Quantities included in the bid table represent estimated quantities for different work. The CONTRACTOR shall be compensated for the actual number of items completed using the unit prices provided.
- 3. The City, at its sole discretion, may elect to delete any portion of the work delineated below, with no change to the unit prices provided. Work shall be determined based upon the availability of funds.
- 4. Any item not provided in the following list shall be considered incidental.

Bid Items

The Bidder agrees to complete the Project and all related work, as specified and shown on the drawings, for the following unit prices.

EIGH [*]	EIGHTH STREET SANITARY SEWER MANHOLE REPLACEMENT								
Item No.	Item Description	Qty	Unit	Unit Price	Total Price				
101	General Conditions, Max. 10% of Bid	1	LS	\$	\$				
102	Audiovisual Tape Coverage	1	LS	\$	\$				
110	Traffic Control	1	LS	\$	\$				
200	Soil Erosion Control	1	LS	\$	\$				
201	HMA Pavement Leveling Course, 1300T	14	Ton	\$	\$				
202	HMA Pavement, Wearing Course, 1300T	14	Ton	\$	\$				
305	8" Sanitary Sewer, SDR 26 PVC, Trench Type I	62	LF	\$	\$				
360	Sanitary Sewer Manhole, Type I , 0-10' deep	1	Each	\$	\$				

		\$			
891	Clean-Up & Restoration	1	LS	\$	\$
527	Aggregate Base Course, 21AA, C.I.P	36	CY	\$	\$
500	Remove Bituminous Pavement	120	SY	\$	\$
386	Sewer Structure Removal	2	EA	\$	\$
385	Sewer Pipe Removal, 8"	62	LF	\$	\$
361	Sanitary Sewer Manhole, Type I, 12' deep	12	VF	\$	\$

TOTAL BID AMOUNT

	Dollars (\$)
(Amount shall be shown in both words and figures.	In case of a discrepancy, the	,
amount shown in words shall govern.)		

Section 2 - Material and Equipment Alternates

The Base Bid proposal price shall include materials and equipment selected from the designated items and manufacturers listed in the bidding documents. This is done to establish uniformity in bidding and to establish standards of quality for the items named.

If the Contractor wishes to quote alternate items for consideration by the City, it may do so under this Section. A complete description of the item and the proposed price differential must be provided. Unless approved at the time of award, substitutions where items are specifically named will be considered only as a negotiated change in Contract Sum.

<u>Item Number</u>	<u>Description</u>	Add/Deduct Amount
If the Bidder does no complete the following		or equipment alternate, the Bidder MUS 1
For the work outlined equipment alternate		bidder does NOT propose any material o
Signature of Authoriz	zed Representative of Bido	der

Section 3 - Time Alternate

Section 5 - Time Alternate
If the Bidder takes exception to the time stipulated in Article III of the Contract, Time of Completion, page C-1, it is requested to stipulate below its proposed time for performance of the work. Consideration will be given to time in evaluating bids.
If the Bidder does not suggest any time alternate, the Bidder MUST complete the following statement:
For the work outlined in this request for bid, the bidder does NOT propose any time alternate under the Contract.

Signature of Authorized Representative of Bidder _____

Section 4 - Major Subcontractors

For purposes of this Contract, a Subcontractor is anyone (other than the Contractor) who performs work (other than or in addition to the furnishing of materials, plans or equipment) at or about the construction site. directly or indirectly for or on behalf of the Contractor (and

whether or not in privity of Contract with the Contractor), but shall not include any individual who furnishes merely the individual's own personal labor or services.				
For the work outlined in these documents to subcontractors to perform the work identified the subcontractors the subcontractors to perform the work identified the subcontractors to perform the work identified the subcontractors the subcont		engage the following major		
Subcontractor (Name and Address)	<u>Work</u>	<u>Amount</u>		
If the Bidder does not expect to engage	e any major subcor	ntractor, the Bidder MUST		
complete the following statement:				
For the work outlined in this request for b major subcontractor to perform work under		NOT expect to engage any		
Signature of Authorized Representative of	f Bidder			

Section 5 – References

GENERAL CONTRACTO	<u>R</u> (Name:)
	e references from similar proje eplacement and related work	ects completed within the past five
Refer also to Instructions t	o Bidders for additional requi	irements.
1) Project Name	Cost	Date Constructed
Contact Name		Phone Number
2) Project Name	Cost	Date Constructed
Contact Name		Phone Number
3) Project Name	Cost	Date Constructed
Contact Name		Phone Number

Section 6 - References

SL	SUBCONTRACTOR (Name:)	
	clude a minimum of three re years.	ferences from similar pro	ejects completed within the past five	
Re	efer also to Instructions to E	Bidders for additional req	uirements.	
1)				
.,	Project Name	Cost	Date Constructed	
	Contact Name		Phone Number	
	Description			
2)	Project Name	Cost	Date Constructed	
	Contact Name		Phone Number	
	Description			
3)	Project Name	Cost	 Date Constructed	
	Contact Name		Phone Number	
3)		Cost		
	Description			

CONTRACT

THIS AGREEMENT is made on the	day of	, 20,	between the CITY OF
ANN ARBOR, a Michigan Municipa	1 Corporation, 301	East Huron Street,	Ann Arbor, Michigan
48104 ("City") and			("Contractor")
(An individual/partnership/corporation, inclu	de state of incorporation	on)	(Address)

Based upon the mutual promises below, the Contractor and the City agree as follows:

ARTICLE I - Scope of Work

The Contractor agrees to furnish all of the materials, equipment and labor necessary; and to abide by all the duties and responsibilities applicable to it for the project titled "Eighth Street Sanitary Sewer Manhole Replacement" in accordance with the requirements and provisions of the following documents, including all written modifications incorporated into any of the documents, which are incorporated as part of this Contract:

Human Rights Division Contract
Living Wage Declaration of
Compliance Forms
(if applicable)
Bid Forms
Contract and Exhibits

General Conditions Standard Specifications Detailed Specifications Plans Addenda

ARTICLE II - Definitions

Bonds

Administering Service Area/Unit means Public Services Area.

Supervising Professional or Owner means Utilities Engineer or other persons acting under the authorization of the Administrator/Manager of the Administering Service Area/Unit.

Engineer or Owner's Representative means Consulting Professional acting under the authorization of the Supervising Professional/Owner.

Project means, Eighth Street Sanitary Sewer Manhole Replacement, Bid No. ITB-4337

ARTICLE III - Time of Completion

(A) The work to be completed under this Contract shall begin immediately on the date specified in the Notice to Proceed issued by the City.

- (B) The entire work for this Contract shall be completed within ten (10) consecutive days. Shorter completion times for certain portions of the work may be specified in the Detailed Specifications. Liquidated damages shall also apply to these intermediate milestones based on the amounts listed in the Detailed Specifications.
- (C) Failure to complete all the work within the time specified above, including any extension granted in writing by the Supervising Professional, shall obligate the Contractor to pay the City, as liquidated damages and not as a penalty, an amount equal to \$500.00 for each calendar day of delay in the completion of all the work. If any liquidated damages are unpaid by the Contractor, the City shall be entitled to deduct these unpaid liquidated damages from the monies due the Contractor.

As an independent requirement, where the Detailed Specifications or Plans identify certain portions of the work to be completed within a shorter period of time and the Contractor fails to complete each portion within the shorter period specified for each portion, including any extension granted in writing by the Project Supervisor, the City is entitled to deduct from the monies due the Contractor, as liquidated damages and not as a penalty, the amount equal to that identified in Specifications or Plans for each portion or Phase of the work not timely completed for each calendar day of delay in completion of each portion of the work.

The liquidated damages are for the non-quantifiable aspects of any of the previously identified events and do not cover actual damages that can be shown or quantified nor are they intended to preclude recovery of actual damages in addition to the recovery of liquidated damages.

Liquidated damages under this section are in addition to any liquidated damages due under Section 5 of the General Conditions.

ARTICLE IV - The Contract Sum

(A)	The City shall pay to the Contractor for the performance of the Contract, the ur	nit
	prices as given in the Bid Forms for the estimated bid total of:	
	Dollars (\$)

(B) The amount paid shall be equitably adjusted to cover changes in the work ordered by the Supervising Professional but not required by the Contract Documents. Increases or decreases shall be determined only by written agreement between the City and Contractor.

ARTICLE V - Assignment

This Contract may not be assigned or subcontracted without the written consent of the City.

ARTICLE VI - Choice of Law

This Contract shall be construed, governed, and enforced in accordance with the laws of the State of Michigan. By executing this agreement, the Contractor and the City agree to venue in a court of appropriate jurisdiction sitting within Washtenaw County for purposes of any action arising under this Contract. The parties stipulate that the venue referenced in this Contract is for convenience and waive any claim of non-convenience.

Whenever possible, each provision of the Contract will be interpreted in a manner as to be effective and valid under applicable law. The prohibition or invalidity, under applicable law, of any provision will not invalidate the remainder of the Contract.

ARTICLE VII - Relationship of the Parties

The parties of the Contract agree that it is not a Contract of employment but is a Contract to accomplish a specific result. Contractor is an independent Contractor performing services for the City. Nothing contained in this Contract shall be deemed to constitute any other relationship between the City and the Contractor.

Contractor certifies that it has no personal or financial interest in the project other than the compensation it is to receive under the Contract. Contractor certifies that it is not, and shall not become, overdue or in default to the City for any Contract, debt, or any other obligation to the City including real or personal property taxes. City shall have the right to set off any such debt against compensation awarded for services under this agreement.

ARTICLE VIII - Notice

All notices given under this Contract shall be in writing, and shall be by personal delivery or by certified mail with return receipt requested to the parties at their respective addresses as specified in the Contract Documents or other address the Contractor may specify in writing.

ARTICLE IX - Indemnification

To the fullest extent permitted by law, Contractor shall indemnify, defend and hold harmless the City, its officers, employees and agents harmless from all suits, claims, judgments and expenses including attorney's fees resulting or alleged to result, in whole or in part, from any act or omission, which is in any way connected or associated with this Contract, by the Contractor or anyone acting on the Contractor's behalf under this Contract. Contractor shall not be responsible to indemnify the City for losses or damages caused by or resulting from the City's sole negligence.

Version 01/2010 C-3

ARTICLE X - Entire Agreement

This Contract represents the entire understanding between the City and the Contractor and it supersedes all prior representations or agreements whether written or oral. Neither party has relied on any prior representations in entering into this Contract. This Contract may be altered, amended or modified only by written amendment signed by the City and the Contractor.

FOR CONTRACTOR	FOR THE CITY OF ANN ARBOR
By	By John Hieftje, Mayor
	By
	Approved as to substance
	By Steven D. Powers, City Administrator
	By Craig Hupy, Public Services Area Administrator
	Approved as to form and content
	Stephen K. Postema, City Attorney

Version 01/2010 C-4

PERFORMANCE BOND

(1)					
	of	(referred to as			
	"Principal"), and to do business in the State of Michiga Michigan (referred to as "City"), for	, a corporation duly authorized an (referred to as "Surety"), are bound to the City of Ann Arbor,			
		the necessary of which Drive and oud County hind the mealures their			
	heirs, executors, administrators, success	_, the payment of which Principal and Surety bind themselves, their sors and assigns, jointly and severally, by this bond.			
(2)	The Principal has entered a written Con Eighth Street Sanitary	ntract with the City dated, 20, for: Sewer Manhole Replacement, ITB 4337			
	this bond is given for that Contract in coamended, being MCL 129.201 et seq.	ompliance with Act No. 213 of the Michigan Public Acts of 1963, as			
(3)	Whenever the Principal is declared by t remedy the default or shall promptly:	he City to be in default under the Contract, the Surety may promptly			
	(a) complete the Contract in accordance	(a) complete the Contract in accordance with its terms and conditions; or			
	and conditions, and upon determination between such bidder and the City, and n	to the City for completing the Contract in accordance with its terms in by Surety of the lowest responsible bidder, arrange for a Contract make available, as work progresses, sufficient funds to pay the cost of tract price; but not exceeding, including other costs and damages for the amount set forth in paragraph 1.			
(4)	Surety shall have no obligation to the C	City if the Principal fully and promptly performs under the Contract.			
(5)	Surety agrees that no change, extension of time, alteration or addition to the terms of the Contract or to the work to be performed thereunder, or the specifications accompanying it shall in any way affect its obligations on this bond, and waives notice of any such change, extension of time, alteration or addition to the terms of the Contract or to the work, or to the specifications.				
SIGN	IED AND SEALED this day of _	, 20			
 By	(Name of Surety Company)	(Name of Principal) By			
- J <u> </u>	(Signature)	(Signature)			
Its	(Title of Office)	Its(Title of Office)			
Appro	oved as to form:	Name and address of agent:			
Steph	en K. Postema, City Attorney				

LABOR AND MATERIAL BOND

(1)				
	of		(refer	rred to as
	"Principal"), and		, a corporation duly auth	orized to
	do business in the State of Michigan, (referred to as "Surety"), are bound to the City of Ann Arbor,			
	Michigan (referred to as "City"), fe	or the use and be	nefit of claimants as defined in Act 213 of I	Michigan
Public Acts of 1963, as amended, being MCL 129.201 et seq., in the amount of				
	\$, for the	payment of whic	ch Principal and Surety bind themselves, th	neir heirs,
	executors, administrators, successed	ors and assigns, j	jointly and severally, by this bond.	
(2)	The Principal has entered a written	n Contract with the	he City, dated, 20,	for
	Eighth Street Sanitary Sewer	Manhole Replac	ement, ITB 4337	
			; and this	s bond is
	given for that Contract in complian	nce with Act No. 2	213 of the Michigan Public Acts of 1963 as a	amended;
(3)	If the Principal fails to promptly a	and fully repay c	laimants for labor and material reasonably	required
	under the Contract, the Surety sha	ll pay those clain	nants.	
(4)	Surety's obligations shall not exc	ceed the amount	stated in paragraph 1, and Surety shall	have no
	obligation if the Principal promptl	y and fully pays	the claimants.	
SIC	GNED AND SEALED this	_ day of	, 20	
		<u></u>		_
	(Name of Surety Company)		(Name of Principal)	
Ву	(Signature)		By(Signature)	_
Its_			Its	_
	(Title of Office)		(Title of Office)	
Ap	proved as to form:		Name and address of agent:	
Ste	phen K. Postema, City Attorney	<u></u>		_
				-

GENERAL CONDITIONS

Section 1 - Execution. Correlation and Intent of Documents

The contract documents shall be signed in 2 copies by the City and the Contractor.

The contract documents are complementary and what is called for by any one shall be binding. The intention of the documents is to include all labor and materials, equipment and transportation necessary for the proper execution of the work. Materials or work described in words which so applied have a well-known technical or trade meaning have the meaning of those recognized standards.

In case of a conflict among the contract documents listed below in any requirement(s), the requirement(s) of the document listed first shall prevail over any conflicting requirement(s) of a document listed later.

(1) Addenda in reverse chronological order; (2) Detailed Specifications; (3) Standard Specifications; (4) Plans; (5) General Conditions; (6) Contract; (7) Bid Forms; (8) Bond Forms; (9) Bid.

Section 2 - Order of Completion

The Contractor shall submit with each invoice, and at other times reasonably requested by the Supervising Professional, schedules showing the order in which the Contractor proposes to carry on the work. They shall include the dates at which the Contractor will start the several parts of the work, the estimated dates of completion of the several parts, and important milestones within the several parts.

Section 3 - Familiarity with Work

The Bidder or its representative shall make personal investigations of the site of the work and of existing structures and shall determine to its own satisfaction the conditions to be encountered, the nature of the ground, the difficulties involved, and all other factors affecting the work proposed under this Contract. The Bidder to whom this Contract is awarded will not be entitled to any additional compensation unless conditions are clearly different from those which could reasonably have been anticipated by a person making diligent and thorough investigation of the site.

The Bidder shall immediately notify the City upon discovery, and in every case prior to submitting its Bid, of every error or omission in the bidding documents that would be identified by a reasonably competent, diligent Bidder. In no case will a Bidder be allowed the benefit of extra compensation or time to complete the work under this Contract for extra expenses or time spent as a result of the error or omission.

Section 4 - Wage Requirements

Under this Contract, the Contractor shall conform to Chapter 14 of Title I of the Code of the City of Ann Arbor as amended; which in part states "...that all craftsmen, mechanics and laborers employed directly on the site in connection with said improvements, including said employees of subcontractors, shall receive the prevailing wage for the corresponding classes of craftsmen, mechanics and laborers, as determined by statistics for the Ann Arbor area compiled by the United States Department of Labor. At the request of the City, any contractor or subcontractor shall provide satisfactory proof of compliance with the contract provisions required by the Section."

Where the Contract and the Ann Arbor City Ordinance are silent as to definitions of terms required in determining contract compliance with regard to prevailing wages, the definitions provided in the Davis-Bacon Act as amended (40 U.S.C. 278-a to 276-a-7) for the terms shall be used.

Further, to the extent that any employees of the Contractor providing services under this contract are not part of the class of craftsmen, mechanics and laborers who receive a prevailing wage in conformance with Section 1:319 of Chapter 14 of Title I of the Code of the City of Ann Arbor, the Contractor agrees to conform to Chapter 23 of Title I of the Code of the City of Ann Arbor, as amended, which in part states:

1:814. Applicability.

- (1) This Chapter shall apply to any person that is a contractor/Bidder or grantee as defined in Section 1:813 that employs or contracts with five (5) or more individuals; provided, however, that this Chapter shall not apply to a non-profit contractor/Bidder or non-profit grantee unless it employs or contracts with ten (10) or more individuals.
- (2) This Chapter shall apply to any grant, contract, or subcontract or other form of financial assistance awarded to or entered into with a contractor/Bidder or grantee after the effective date of this Chapter and to the extension or renewal after the effective date of this Chapter of any grant, contract, or subcontract or other form of financial assistance with a contractor/Bidder or grantee.

1:815. Living Wages Required.

- (1) Every contractor/Bidder or grantee, as defined in Section 1:813, shall pay its covered employees a living wage as established in this Section.
 - (a) For a covered employer that provides employee health care to its employees, the living wage shall be \$12.52 an hour, or the adjusted amount hereafter established under Section 1:815(3).
 - (b) For a covered employer that does not provide health care to its employees, the living wage shall be \$13.96 a hour, or the adjusted amount hereafter established under Section 1:815(3).

- (2) In order to qualify to pay the living wage rate for covered employers providing employee health care under subsection 1:815(1)(a), a covered employer shall furnish proof of said health care coverage and payment therefor to the City Administrator or his/her designee.
- (3) The amount of the living wage established in this Section shall be adjusted upward no later than April 30, 2002, and every year thereafter by a percentage equal to the percentage increase, if any, in the federal poverty guidelines as published by the United States Department of Health and Human Services for the years 2001 and 2002. Subsequent annual adjustments shall be based upon the percentage increase, if any, in the United States Department of Health and Human Services poverty guidelines when comparing the prior calendar year's poverty guidelines to the present calendar year's guidelines. The applicable percentage amount will be converted to an amount in cents by multiplying the existing wage under Section 1.815(1)(b) by said percentage, rounding upward to the next cent, and adding this amount of cents to the existing living wage levels established under Sections 1:815(1)(a) and 1:815(1)(b). Prior to April 1 of each calendar year, the City will notify any covered employer of this adjustment by posting a written notice in a prominent place in City Hall, and, in the case of a covered employer that has provided an address of record to the City, by a written letter to each such covered employer.

Contractor agrees that all subcontracts entered into by the Contractor shall contain similar wage provision covering subcontractor's employees who perform work on this contract.

Section 5 - Non-Discrimination

The Contractor agrees to comply, and to require its subcontractor(s) to comply, with the nondiscrimination provisions of Section 209 of the Elliot-Larsen Civil Rights Act (MCL 37.2209). The Contractor further agrees to comply with the nondiscrimination provisions of Chapter 112 of the Ann Arbor City Code and to assure that applicants are employed and that employees are treated during employment in a manner which provides equal employment opportunity. The Contractor further agrees to comply with the provisions of Section 9:161 of Chapter 112 of the Ann Arbor City Code and in particular the following excerpts:

9:161 NONDISCRIMINATION BY CITY CONTRACTORS

- (1) All Contractors proposing to do business with the City of Ann Arbor shall satisfy the nondiscrimination administrative policy adopted by the City Administrator in accordance with the guidelines of this section. All Contractors shall receive approval from the Director prior to entering into a contract with the City, unless specifically exempted by administrative policy. All City Contractors shall take affirmative action to insure that applicants are employed and that employees are treated during employment in a manner which provides equal employment opportunity and tends to eliminate inequality based upon race, national origin or sex.
- (2) Each prospective contractor shall submit to the City data showing current total employment by occupational category, sex and minority group. If, after verifying this data, the Director concludes that it indicates total minority and female employment commensurate with their availability within the contractor's labor recruitment area, i.e., the area from which the contractor can reasonably be expected to recruit, said contractor shall be accepted by the Director as having fulfilled affirmative action requirements for a period of one year at which

time the Director shall conduct another review. Other Contractors shall develop an affirmative action program in conjunction with the Director. Said program shall include specific goals and timetables for the hiring and promotion of minorities and females. Said goals shall reflect the availability of minorities and females within the Contractor's labor recruitment area. In the case of construction Contractors, the Director shall use for employment verification the labor recruitment area of the Ann Arbor-Ypsilanti standard metropolitan statistical area. Construction Contractors determined to be in compliance shall be accepted by the Director as having fulfilled affirmative action requirements for a period of six (6) months at which time the Director shall conduct another review.

- (3) In hiring for construction projects, contractors shall make good faith efforts to employ local persons, so as to enhance the local economy.
- (4) All Contracts shall include provisions through which the Contractor agrees, in addition to any other applicable Federal or State labor laws:
 - (a) To set goals, in conference with the Human Resources Director, for each job category or division of the work force used in the completion of the City work;
 - (b) To provide periodic reports concerning the progress the Contractor has made in meeting the affirmative action goals it has agreed to;
 - (c) To permit the Director access to all books, records and accounts pertaining to its employment practices for the purpose of determining compliance with the affirmative action requirements.
- (5) The Director shall monitor the compliance of each contractor with the nondiscrimination provisions of each contract. The Director shall develop procedures and regulations consistent with the administrative policy adopted by the City Administrator for notice and enforcement of non-compliance. Such procedures and regulations shall include a provision for the posting of Contractors not in compliance.
- (6) All City Contracts shall provide further that breach of the obligation not to discriminate shall be a material breach of the Contract for which the City shall be entitled, at its option, to do any or all of the following:
 - (a) To cancel, terminate, or suspend the Contract in whole or part and/or refuse to make any required periodic payments under the Contract;
 - (b)Declare the Contractor ineligible for the award of any future contracts with the City for a specified length of time;
 - (c)To recover liquidated damages of a specified sum, said sum to be that percentage of the labor expenditure for the time period involved which would have accrued to minority group members had the affirmative action not been breached;

(d)Impose for each day of non-compliance, liquidated damages of a specified sum, based upon the following schedule:

Contract Amount	Assessed Damages Per Day of Non-Compliance
\$ 10,000 - 24,999	\$ 25.00
25,000 - 99,999	50.00
100,000 - 199,999	100.00
200,000 - 499,999	150.00
500,000 - 1,499,999	200.00
1,500,000 - 2,999,999	250.00
3,000,000 - 4,999,999	300.00
5,000,000 - and above	500.00

(e) In addition the Contractor shall be liable for any costs or expenses incurred by the City of Ann Arbor in obtaining from other sources the work and services to be rendered or performed or the goods or properties to be furnished or delivered to the City under this contract.

Section 6 - Materials, Appliances, Employees

Unless otherwise stipulated, the Contractor shall provide and pay for all materials, labor, water, tools, equipment, light, power, transportation, and other facilities necessary or used for the execution and completion of the work. Unless otherwise specified, all materials incorporated in the permanent work shall be new, and both workmanship and materials shall be of the highest quality. The Contractor shall, if required, furnish satisfactory evidence as to the kind and quality of materials.

The Contractor shall at all times enforce strict discipline and good order among its employees, and shall seek to avoid employing on the work any unfit person or anyone not skilled in the work assigned.

Adequate sanitary facilities shall be provided by the Contractor.

Section 7 - Qualifications for Employment

The Contractor shall employ competent laborers and mechanics for the work under this Contract. For work performed under this Contract, employment preference shall be given to qualified local residents.

Section 8 - Royalties and Patents

The Contractor shall pay all royalties and license fees. It shall defend all suits or claims for infringements of any patent rights and shall hold the City harmless from loss on account of infringement except that the City shall be responsible for all infringement loss when a particular process or the product of a particular manufacturer or manufacturers is specified, unless the City has notified the Contractor prior to the signing of the Contract that the particular process or product is patented or is believed to be patented.

Section 9 - Permits and Regulations

The Contractor must secure and pay for all permits, permit or plan review fees and licenses necessary for the prosecution of the work. These include but are not limited to City building permits, right-of-way permits, lane closure permits, right-of-way occupancy permits, and the like. The City shall secure and pay for easements shown on the plans unless otherwise specified.

The Contractor shall give all notices and comply with all laws, ordinances, rules and regulations bearing on the conduct of the work as drawn and specified. If the Contractor observes that the contract documents are at variance with those requirements, it shall promptly notify the Supervising Professional in writing, and any necessary changes shall be adjusted as provided in the Contract for changes in the work.

Section 10 - Protection of the Public and of Work and Property

The Contractor is responsible for the means, methods, sequences, techniques and procedures of construction and safety programs associated with the work contemplated by this contract. The Contractor, its agents or sub-contractors, shall comply with the "General Rules and Regulations for the Construction Industry" as published by the Construction Safety Commission of the State of Michigan and to all other local, State and National laws, ordinances, rules and regulations pertaining to safety of persons and property.

The Contractor shall take all necessary and reasonable precautions to protect the safety of the public. It shall continuously maintain adequate protection of all work from damage, and shall take all necessary and reasonable precautions to adequately protect all public and private property from injury or loss arising in connection with this Contract. It shall make good any damage, injury or loss to its work and to public and private property resulting from lack of reasonable protective precautions, except as may be due to errors in the contract documents, or caused by agents or employees of the City. The Contractor shall obtain and maintain sufficient insurance to cover damage to any City property at the site by any cause.

In an emergency affecting the safety of life, or the work, or of adjoining property, the Contractor is, without special instructions or authorization from the Supervising Professional, permitted to act at its discretion to prevent the threatened loss or injury. It shall also so act, without appeal, if authorized or instructed by the Supervising Professional.

Any compensation claimed by the Contractor for emergency work shall be determined by agreement or in accordance with the terms of Claims for Extra Cost - Section 15.

Section 11 - Inspection of Work

The City shall provide sufficient competent personnel for the inspection of the work.

The Supervising Professional shall at all times have access to the work whenever it is in preparation or progress, and the Contractor shall provide proper facilities for access and for inspection.

If the specifications, the Supervising Professional's instructions, laws, ordinances, or any public authority require any work to be specially tested or approved, the Contractor shall give the Supervising Professional timely notice of its readiness for inspection, and if the inspection is by an authority other than the Supervising Professional, of the date fixed for the inspection. Inspections by

the Supervising Professional shall be made promptly, and where practicable at the source of supply. If any work should be covered up without approval or consent of the Supervising Professional, it must, if required by the Supervising Professional, be uncovered for examination and properly restored at the Contractor's expense.

Re-examination of any work may be ordered by the Supervising Professional, and, if so ordered, the work must be uncovered by the Contractor. If the work is found to be in accordance with the contract documents, the City shall pay the cost of re-examination and replacement. If the work is not in accordance with the contract documents, the Contractor shall pay the cost.

Section 12 - Superintendence

The Contractor shall keep on the work site, during its progress, a competent superintendent and any necessary assistants, all satisfactory to the Supervising Professional. The superintendent will be responsible to perform all on-site project management for the Contractor. The superintendent shall be experienced in the work required for this Contract. The superintendent shall represent the Contractor and all direction given to the superintendent shall be binding as if given to the Contractor. Important directions shall immediately be confirmed in writing to the Contractor. Other directions will be confirmed on written request. The Contractor shall give efficient superintendence to the work, using its best skill and attention.

Section 13 - Changes in the Work

The City may make changes to the quantities of work within the general scope of the Contract at any time by a written order and without notice to the sureties. If the changes add to or deduct from the extent of the work, the Contract Sum shall be adjusted accordingly. All the changes shall be executed under the conditions of the original Contract except that any claim for extension of time caused by the change shall be adjusted at the time of ordering the change.

In giving instructions, the Supervising Professional shall have authority to make minor changes in the work not involving extra cost and not inconsistent with the purposes of the work, but otherwise, except in an emergency endangering life or property, no extra work or change shall be made unless in pursuance of a written order by the Supervising Professional, and no claim for an addition to the Contract Sum shall be valid unless the additional work was ordered in writing.

The Contractor shall proceed with the work as changed and the value of the work shall be determined as provided in Claims for Extra Cost - Section 15.

Section 14 - Extension of Time

Extension of time stipulated in the Contract for completion of the work will be made if and as the Supervising Professional may deem proper under any of the following circumstances:

- (1) When work under an extra work order is added to the work under this Contract;
- (2) When the work is suspended as provided in Section 20;

- (3) When the work of the Contractor is delayed on account of conditions which could not have been foreseen, or which were beyond the control of the Contractor, and which were not the result of its fault or negligence;
- (4) Delays in the progress of the work caused by any act or neglect of the City or of its employees or by other Contractors employed by the City;
- (5) Delay due to an act of Government;
- (6) Delay by the Supervising Professional in the furnishing of plans and necessary information;
- (7) Other cause which in the opinion of the Supervising Professional entitles the Contractor to an extension of time.

The Contractor shall notify the Supervising Professional within 7 days of an occurrence or conditions which, in the Contractor's opinion, entitle it to an extension of time. The notice shall be in writing and submitted in ample time to permit full investigation and evaluation of the Contractor's claim. The Supervising Professional shall acknowledge receipt of the Contractor's notice within 7 days of its receipt. Failure to timely provide the written notice shall constitute a waiver by the Contractor of any claim.

In situations where an extension of time in contract completion is appropriate under this or any other section of the contract, the Contractor understands and agrees that the only available adjustment for events that cause any delays in contract completion shall be extension of the required time for contract completion and that there shall be no adjustments in the money due the Contractor on account of the delay.

Section 15 - Claims for Extra Cost.

If the Contractor claims that any instructions by drawings or other media issued after the date of the Contract involved extra cost under this Contract, it shall give the Supervising Professional written notice within 7 days after the receipt of the instructions, and in any event before proceeding to execute the work, except in emergency endangering life or property. The procedure shall then be as provided for Changes in the Work-Section 13. No claim shall be valid unless so made.

If the Supervising Professional orders, in writing, the performance of any work not covered by the contract documents, and for which no item of work is provided in the Contract, and for which no unit price or lump sum basis can be agreed upon, then the extra work shall be done on a Cost-Plus-Percentage basis of payment as follows:

- (1) The Contractor shall be reimbursed for all reasonable costs incurred in doing the work, and shall receive an additional payment of 15% of all the reasonable costs to cover both its indirect overhead costs and profit;
- (2) The term "Cost" shall cover all payroll charges for employees and supervision required under the specific order, together with all worker's compensation, Social Security, pension and retirement allowances and social insurance, or other regular payroll charges on same; the cost of all material and supplies required of either temporary or permanent character; rental of all

power-driven equipment at agreed upon rates, together with cost of fuel and supply charges for the equipment; and any costs incurred by the Contractor as a direct result of executing the order, if approved by the Supervising Professional;

- (3) If the extra is performed under subcontract, the subcontractor shall be allowed to compute its charges as described above. The Contractor shall be permitted to add an additional charge of 5% percent to that of the subcontractor for the Contractor's supervision and contractual responsibility;
- (4) The quantities and items of work done each day shall be submitted to the Supervising Professional in a satisfactory form on the succeeding day, and shall be approved by the Supervising Professional and the Contractor or adjusted at once;
- (5) Payments of all charges for work under this Section in any one month shall be made along with normal progress payments. Retainage shall be in accordance with Progress Payments-Section 16.

No additional compensation will be provided for additional equipment, materials, personnel, overtime or special charges required to perform the work within the time requirements of the Contract.

When extra work is required and no suitable price for machinery and equipment can be determined in accordance with this Section, the hourly rate paid shall be 1/40 of the basic weekly rate listed in the Rental Rate Blue Book published by Dataquest Incorporated and applicable to the time period the equipment was first used for the extra work. The hourly rate will be deemed to include all costs of operation such as bucket or blade, fuel, maintenance, "regional factors", insurance, taxes, and the like, but not the costs of the operator.

Section 16 - Progress Payments

The Contractor shall submit each month, or at longer intervals, if it so desires, an invoice covering work performed for which it believes payment, under the Contract terms, is due. The submission shall be to the City's Finance Department - Accounting Division. The Supervising Professional will, within 10 days following submission of the invoice, prepare a certificate for payment for the work in an amount to be determined by the Supervising Professional as fairly representing the acceptable work performed during the period covered by the Contractor's invoice. To insure the proper performance of this Contract, the City will retain a percentage of the estimate in accordance with Act 524, Public Acts of 1980. The City will then, following the receipt of the Supervising Professional's Certificate, make payment to the Contractor as soon as feasible, which is anticipated will be within 15 days.

An allowance may be made in progress payments if substantial quantities of permanent material have been delivered to the site but not incorporated in the completed work if the Contractor, in the opinion of the Supervising Professional, is diligently pursuing the work under this Contract. Such materials shall be properly stored and adequately protected. Allowance in the estimate shall be at the invoice price value of the items. Notwithstanding any payment of any allowance, all risk of loss due to vandalism or any damages to the stored materials remains with the Contractor.

In the case of Contracts which include only the Furnishing and Delivering of Equipment, the payments shall be; 60% of the Contract Sum upon the delivery of all equipment to be furnished, or in the case of delivery of a usable portion of the equipment in advance of the total equipment delivery, 60% of the estimated value of the portion of the equipment may be paid upon its delivery in advance of the time of the remainder of the equipment to be furnished; 30% of the Contract Sum upon completion of erection of all equipment furnished, but not later than 60 days after the date of delivery of all of the equipment to be furnished; and payment of the final 10% on final completion of erection, testing and acceptance of all the equipment to be furnished; but not later than 180 days after the date of delivery of all of the equipment to be furnished, unless testing has been completed and shows the equipment to be unacceptable.

With each invoice for periodic payment, the Contractor shall enclose a Contractor's Declaration - Section 43, and an updated project schedule per Order of Completion - Section 2.

Section 17 - Deductions for Uncorrected Work

If the Supervising Professional decides it is inexpedient to correct work that has been damaged or that was not done in accordance with the Contract, an equitable deduction from the Contract price shall be made.

Section 18 - Correction of Work Before Final Payment

The Contractor shall promptly remove from the premises all materials condemned by the Supervising Professional as failing to meet Contract requirements, whether incorporated in the work or not, and the Contractor shall promptly replace and re-execute the work in accordance with the Contract and without expense to the City and shall bear the expense of making good all work of other contractors destroyed or damaged by the removal or replacement.

If the Contractor does not remove the condemned work and materials within 10 days after written notice, the City may remove them and, if the removed material has value, may store the material at the expense of the Contractor. If the Contractor does not pay the expense of the removal within 10 days thereafter, the City may, upon 10 days written notice, sell the removed materials at auction or private sale and shall pay to the Contractor the net proceeds, after deducting all costs and expenses that should have been borne by the Contractor. If the removed material has no value, the Contractor must pay the City the expenses for disposal within 10 days of invoice for the disposal costs.

The inspection or lack of inspection of any material or work pertaining to this Contract shall not relieve the Contractor of its obligation to fulfill this Contract and defective work shall be made good. Unsuitable materials may be rejected by the Supervising Professional notwithstanding that the work and materials have been previously overlooked by the Supervising Professional and accepted or estimated for payment or paid for. If the work or any part shall be found defective at any time before the final acceptance of the whole work, the Contractor shall forthwith make good the defect in a manner satisfactory to the Supervising Professional. The judgment and the decision of the Supervising Professional as to whether the materials supplied and the work done under this Contract comply with the requirements of the Contract shall be conclusive and final.

Section 19 - Acceptance and Final Payment

Upon receipt of written notice that the work is ready for final inspection and acceptance, the Supervising Professional will promptly make the inspection. When the Supervising Professional finds the work acceptable under the Contract and the Contract fully performed, the Supervising Professional will promptly sign and issue a final certificate stating that the work required by this Contract has been completed and is accepted by the City under the terms and conditions of the Contract. The entire balance found to be due the Contractor, including the retained percentage, shall be paid to the Contractor by the City within 30 days after the date of the final certificate.

Before issuance of final certificates, the Contractor shall file with the City:

- (1) The consent of the surety to payment of the final estimate;
- (2) The Contractor's Affidavit in the form required by Section 44.

In case the Affidavit or consent is not furnished, the City may retain out of any amount due the Contractor, sums sufficient to cover all lienable claims.

The making and acceptance of the final payment shall constitute a waiver of all claims by the City except those arising from:

- (1) unsettled liens;
- (2) faulty work appearing within 12 months after final payment;
- (3) hidden defects in meeting the requirements of the plans and specifications;
- (4) manufacturer's guarantees.

It shall also constitute a waiver of all claims by the Contractor, except those previously made and still unsettled.

Section 20 - Suspension of Work

The City may at any time suspend the work, or any part by giving 5 days notice to the Contractor in writing. The work shall be resumed by the Contractor within 10 days after the date fixed in the written notice from the City to the Contractor to do so. The City shall reimburse the Contractor for expense incurred by the Contractor in connection with the work under this Contract as a result of the suspension.

If the work, or any part, shall be stopped by the notice in writing, and if the City does not give notice in writing to the Contractor to resume work at a date within 90 days of the date fixed in the written notice to suspend, then the Contractor may abandon that portion of the work suspended and will be entitled to the estimates and payments for all work done on the portions abandoned, if any, plus 10% of the value of the work abandoned, to compensate for loss of overhead, plant expense, and anticipated profit.

Section 21 - Delays and the City's Right to Terminate Contract

If the Contractor refuses or fails to prosecute the work, or any separate part of it, with the diligence required to insure completion, ready for operation, within the allowable number of consecutive calendar days specified plus extensions, or fails to complete the work within the required time, the City may, by written notice to the Contractor, terminate its right to proceed with the work or any part of the work as to which there has been delay. After providing the notice the City may take over the work and prosecute it to completion, by contract or otherwise, and the Contractor and its sureties shall be liable to the City for any excess cost to the City. If the Contractor's right to proceed is terminated, the City may take possession of and utilize in completing the work, any materials, appliances and plant as may be on the site of the work and useful for completing the work. The right of the Contractor to proceed shall not be terminated or the Contractor charged with liquidated damages where an extension of time is granted under Extension of Time - Section 14.

If the Contractor is adjudged a bankrupt, or if it makes a general assignment for the benefit of creditors, or if a receiver is appointed on account of its insolvency, or if it persistently or repeatedly refuses or fails except in cases for which extension of time is provided, to supply enough properly skilled workers or proper materials, or if it fails to make prompt payments to subcontractors or for material or labor, or persistently disregards laws, ordinances or the instructions of the Supervising Professional, or otherwise is guilty of a substantial violation of any provision of the Contract, then the City, upon the certificate of the Supervising Professional that sufficient cause exists to justify such action, may, without prejudice to any other right or remedy and after giving the Contractor 3 days written notice, terminate this Contract. The City may then take possession of the premises and of all materials, tools and appliances thereon and without prejudice to any other remedy it may have, make good the deficiencies or finish the work by whatever method it may deem expedient, and deduct the cost from the payment due the Contractor. The Contractor shall not be entitled to receive any further payment until the work is finished. If the expense of finishing the work, including compensation for additional managerial and administrative services exceeds the unpaid balance of the Contract Sum, the Contractor and its surety are liable to the City for any excess cost incurred. The expense incurred by the City, and the damage incurred through the Contractor's default, shall be certified by the Supervising Professional.

Section 22 - Contractor's Right to Terminate Contract

If the work should be stopped under an order of any court, or other public authority, for a period of 3 months, through no act or fault of the Contractor or of anyone employed by it, then the Contractor may, upon 7 days written notice to the City, terminate this Contract and recover from the City payment for all acceptable work executed plus reasonable profit.

Section 23 - City's Right To Do Work

If the Contractor should neglect to prosecute the work properly or fail to perform any provision of this Contract, the City, 3 days after giving written notice to the Contractor and its surety may, without prejudice to any other remedy the City may have, make good the deficiencies and may deduct the cost from the payment due to the Contractor.

Section 24 - Removal of Equipment and Supplies

In case of termination of this Contract before completion, from any or no cause, the Contractor, if notified to do so by the City, shall promptly remove any part or all of its equipment and supplies from the property of the City, failing which the City shall have the right to remove the equipment and supplies at the expense of the Contractor.

The removed equipment and supplies may be stored by the City and, if all costs of removal and storage are not paid by the Contractor within 10 days of invoicing, the City upon 10 days written notice may sell the equipment and supplies at auction or private sale, and shall pay the Contractor the net proceeds after deducting all costs and expenses that should have been borne by the Contractor and after deducting all amounts claimed due by any lien holder of the equipment or supplies.

Section 25 - Responsibility for Work and Warranties

The Contractor assumes full responsibility for any and all materials and equipment used in the construction of the work and may not make claims against the City for damages to materials and equipment from any cause except negligence or willful act of the City. Until its final acceptance, the Contractor shall be responsible for damage to or destruction of the project (except for any part covered by Partial Completion and Acceptance - Section 26). The Contractor shall make good all work damaged or destroyed before acceptance. All risk of loss remains with the Contractor until final acceptance of the work (Section 19) or partial acceptance (Section 26). The Contractor is advised to investigate obtaining its own builders risk insurance.

The Contractor shall guarantee the quality of the work for a period of one year. The Contractor shall also unconditionally guarantee the quality of all equipment and materials that are furnished and installed under the contract for a period of one year. At the end of one year after the Contractor's receipt of final payment, the complete work, including equipment and materials furnished and installed under the contract, shall be inspected by the Contractor and the Supervising Professional. Any defects shall be corrected by the Contractor at its expense as soon as practicable but in all cases within 60 days. Any defects that are identified prior to the end of one year shall also be inspected by the Contractor and the Supervising Professional and shall be corrected by the Contractor at its expense as soon as practicable but in all cases within 60 days.

The Contractor shall assign all manufacturer or material supplier warranties to the City prior to final payment. The assignment shall not relieve the Contractor of its obligations under this paragraph to correct defects.

Section 26 - Partial Completion and Acceptance

If at any time prior to the issuance of the final certificate referred to in Acceptance and Final Payment - Section 19, any portion of the permanent construction has been satisfactorily completed, and if the Supervising Professional determines that portion of the permanent construction is not required for the operations of the Contractor but is needed by the City, the Supervising Professional shall issue to the Contractor a certificate of partial completion, and immediately the City may take over and use the portion of the permanent construction described in the certificate, and exclude the Contractor from that portion.

The issuance of a certificate of partial completion shall not constitute an extension of the Contractor's time to complete the portion of the permanent construction to which it relates if the Contractor has failed to complete it in accordance with the terms of this Contract. The issuance of the certificate shall not release the Contractor or its sureties from any obligations under this Contract including bonds.

If prior use increases the cost of, or delays the work, the Contractor shall be entitled to extra compensation, or extension of time, or both, as the Supervising Professional may determine.

Section 27 - Payments Withheld Prior to Final Acceptance of Work

The City may withhold or, on account of subsequently discovered evidence, nullify the whole or part of any certificate to the extent reasonably appropriate to protect the City from loss on account of:

- (1) Defective work not remedied;
- (2) Claims filed or reasonable evidence indicating probable filing of claims by other parties against the Contractor;
- (3) Failure of the Contractor to make payments properly to subcontractors or for material or labor;
- (4) Damage to another Contractor.

When the above grounds are removed or the Contractor provides a Surety Bond satisfactory to the City which will protect the City in the amount withheld, payment shall be made for amounts withheld under this section.

Section 28 - Contractor's Insurance

- A. The Contractor shall procure and maintain during the life of this Contract, including the guarantee period and during any warranty work, such insurance policies, including those set forth below, as will protect itself and the City from all claims for bodily injuries, death or property damage which may arise under this Contract; whether the acts were made by the Contractor or by any subcontractor or anyone employed by them directly or indirectly. The following insurance policies are required:
 - 1. Worker's Compensation Insurance in accordance with all applicable state and federal statutes. Further, Employers Liability Coverage shall be obtained in the following minimum amounts:

```
Bodily Injury by Accident - $500,000 each accident
Bodily Injury by Disease - $500,000 each employee
Bodily Injury by Disease - $500,000 each policy limit
```

2. Commercial General Liability Insurance equivalent to, as a minimum, Insurance Services Office form CG 00 01 07 98. The City of Ann Arbor shall be named as an additional

insured. There shall be no added exclusions or limiting endorsements including, but not limited to: Products and Completed Operations, Explosion, Collapse and Underground coverage or Pollution. Further, the following minimum limits of liability are required:

\$1,000,000 Each occurrence as respect Bodily Injury Liability or Property Damage Liability, or both combined.

\$2,000,000 Per Job General Aggregate

\$1,000,000 Personal and Advertising Injury

\$2,000,000 Products and Completed Operations Aggregate

- 3. Motor Vehicle Liability Insurance, including Michigan No-Fault Coverages, equivalent to, as a minimum, Insurance Services Office form CA 00 01 07 97. The City of Ann Arbor shall be named as an additional insured. There shall be no added exclusions or limiting endorsements. Coverage shall include all owned vehicles, all non-owned vehicles and all hired vehicles. Further, the limits of liability shall be \$1,000,000 for each occurrence as respects Bodily Injury Liability or Property Damage Liability, or both combined.
- 4. Umbrella/Excess Liability Insurance shall be provided to apply excess of the Commercial General Liability, Employers Liability and the Motor Vehicle coverage enumerated above, for each occurrence and for aggregate in the amount of \$1,000,000.
- B. Insurance required under Section A.2 and A.3 of this Contract shall be considered primary as respects any other valid or collectible insurance that the City may possess, including any self-insured retentions the City may have; and any other insurance the City does possess shall be considered excess insurance only and shall not be required to contribute with this insurance. Further, the Contractor agrees to waive any right of recovery by its insurer against the City.
- In the case of all Contracts involving on-site work, the Contractor shall provide to the City before the commencement of any work under this Contract documentation demonstrating it has obtained the above mentioned policies. Documentation must provide and demonstrate an unconditional 30 day written notice of cancellation in favor of the City of Ann Arbor. Further, the documentation must explicitly state the following: (a) the policy number; name of insurance company; name and address of the agent or authorized representative; name and address of insured; project name; policy expiration date; and specific coverage amounts; (b) any deductibles or self-insured retentions which shall be approved by the City, in its sole discretion; (c) that the policy conforms to the requirements specified. An original certificate of insurance may be provided as an initial indication of the required insurance, provided that no later than 21 calendar days after commencement of any work the Contractor supplies a copy of the endorsements required on the policies. Upon request, the Contractor shall provide within 30 days a copy of the policy(ies) to the City. If any of the above coverages expire by their terms during the term of this Contract, the Contractor shall deliver proof of renewal and/or new policies to the Administering Service Area/Unit at least ten days prior to the expiration date.

D. Any Insurance provider of Contractor shall be admitted and authorized to do business in the State of Michigan and shall carry and maintain a minimum rating assigned by A.M. Best & Company's Key Rating Guide of "A-" Overall and a minimum Financial Size Category of "V". Insurance policies and certificates issued by non-admitted insurance companies are not acceptable unless approved in writing by the City.

Section 29 - Surety Bonds

Bonds will be required from the successful bidder as follows:

- (1) A Performance Bond to the City of Ann Arbor for the amount of the bid(s) accepted;
- (2) A Labor and Material Bond to the City of Ann Arbor for the amount of the bid(s) accepted.

Bonds shall be executed on forms supplied by the City in a manner and by a Surety Company satisfactory to the City Attorney.

Section 30 - Damage Claims

The Contractor shall be held responsible for all damages to property of the City or others, caused by or resulting from the negligence of the Contractor, its employees, or agents during the progress of or connected with the prosecution of the work, whether within the limits of the work or elsewhere. The Contractor must restore all property injured including sidewalks, curbing, sodding, pipes, conduit, sewers or other public or private property to not less than its original condition with new work.

Section 31 - Refusal to Obey Instructions

If the Contractor refuses to obey the instructions of the Supervising Professional, the Supervising Professional shall withdraw inspection from the work, and no payments will be made for work performed thereafter nor may work be performed thereafter until the Supervising Professional shall have again authorized the work to proceed.

Section 32 - Assignment

Neither party to the Contract shall assign the Contract without the written consent of the other. The Contractor may assign any monies due to it to a third party acceptable to the City.

Section 33 - Rights of Various Interests

Whenever work being done by the City's forces or by other contractors is contiguous to work covered by this Contract, the respective rights of the various interests involved shall be established by the Supervising Professional, to secure the completion of the various portions of the work in general harmony.

The Contractor is responsible to coordinate all aspects of the work, including coordination of, and with, utility companies and other contractors whose work impacts this project.

Section 34 - Subcontracts

The Contractor shall not award any work to any subcontractor without prior written approval of the City. The approval will not be given until the Contractor submits to the City a written statement concerning the proposed award to the subcontractor. The statement shall contain all information the City may require.

The Contractor shall be as fully responsible to the City for the acts and omissions of its subcontractors, and of persons either directly or indirectly employed by them, as it is for the acts and omissions of persons directly employed by it.

The Contractor shall cause appropriate provisions to be inserted in all subcontracts relative to the work to bind subcontractors to the Contractor by the terms of the General Conditions and all other contract documents applicable to the work of the subcontractors and to give the Contractor the same power to terminate any subcontract that the City may exercise over the Contractor under any provision of the contract documents.

Nothing contained in the contract documents shall create any contractual relation between any subcontractor and the City.

Section 35 - Supervising Professional's Status

The Supervising Professional has the right to inspect any or all work. The Supervising Professional has authority to stop the work whenever stoppage may be appropriate to insure the proper execution of the Contract. The Supervising Professional has the authority to reject all work and materials which do not conform to the Contract and to decide questions which arise in the execution of the work.

The Supervising Professional shall make all measurements and determinations of quantities. Those measurements and determinations are final and conclusive between the parties.

Section 36 - Supervising Professional's Decisions

The Supervising Professional shall, within a reasonable time after their presentation to the Supervising Professional, make decisions in writing on all claims of the City or the Contractor and on all other matters relating to the execution and progress of the work or the interpretation of the contract documents.

Section 37 - Storing Materials and Supplies

Materials and supplies may be stored at the site of the work at locations agreeable to the City unless specific exception is listed elsewhere in these documents. Ample way for foot traffic and drainage must be provided, and gutters must, at all times, be kept free from obstruction. Traffic on streets shall be interfered with as little as possible. The Contractor may not enter or occupy with agents, employees, tools, or material any private property without first obtaining written permission from its owner. A copy of the permission shall be furnished to the Supervising Professional.

Section 38 - Lands for Work

The Contractor shall provide, at its own expense and without liability to the City, any additional land

and access that may be required for temporary construction facilities or for storage of materials.

Section 39 - Cleaning Up

The Contractor shall, as directed by the Supervising Professional, remove at its own expense from the City's property and from all public and private property all temporary structures, rubbish and waste materials resulting from its operations unless otherwise specifically approved, in writing, by the Supervising Professional.

Section 40 - Salvage

The Supervising Professional may designate for salvage any materials from existing structures or underground services. Materials so designated remain City property and shall be transported or stored at a location as the Supervising Professional may direct.

Section 41 - Night, Saturday or Sunday Work

No night or Sunday work (without prior written City approval) will be permitted except in the case of an emergency and then only to the extent absolutely necessary. The City may allow night work which, in the opinion of the Supervising Professional, can be satisfactorily performed at night. Night work is any work between 8:00 p.m. and 7:00 a.m. No Saturday work will be permitted unless the Contractor gives the Supervising Professional at least 48 hours but not more than 5 days notice of the Contractor's intention to work the upcoming Saturday.

Section 42 - Sales Taxes

Under State law the City is exempt from the assessment of State Sales Tax on its direct purchases. Contractors who acquire materials, equipment, supplies, etc. for incorporation in City projects are not likewise exempt. State Law shall prevail. The Bidder shall familiarize itself with the State Law and prepare its Bid accordingly. No extra payment will be allowed under this Contract for failure of the Contractor to make proper allowance in this bid for taxes it must pay.

Section 43

CONTRACTOR'S DECLARATION

Thereby accide that Thave not, during the	period	, 20, to	, 20,				
performed any work, furnished any materials, sustained any loss, damage or delay, or otherwise							
done anything in addition to the regular items (or executed change orders) set forth in the Contract							
titled Eighth Street Sanitary Sewer Manhole Replacement, ITB 4337, for which I shall ask, demand,							
sue for, or claim compensation or extension	sue for, or claim compensation or extension of time from the City, except as I hereby make claim for						
additional compensation or extension of the	ime as set forth	on the attached itemiz	zed statement. I				
further declare that I have paid all payroll obligations related to this Contract that have become due							
during the above period and that all invoice	es related to thi	s Contract received mo	re than 30 days				
prior to this declaration have been paid in f	full except as lis	ted below.					
There <u>is/is not</u> (Contractor please circle on			nized statement				
attached regarding a request for additional compensation or extension of time.							
www.nearen.g.w.reducer.ter.manner.		extension of time.					
wind to some and the source and the	r	extension of time.					
and a regularity is required to a decision in	r	extension of time.					
		———					
	Date	———					
Contractor							
		- Catchision of time.					
Contractor By(Signature)							
Contractor By (Signature) Its							
Contractor By(Signature)							

Section 44

CONTRACTOR'S AFFIDAVIT

The undersigned Contractor,, represents that on 20, it was awarded a contract by the City of Ann Arbor, Michigan to under the erms and conditions of a Contract titled Eighth Street Sanitary Sewer Manhole Replacement, ITB 4337. The Contractor represents that all work has now been accomplished and the Contract is complete. The Contractor warrants and certifies that all of its indebtedness arising by reason of the Contract was been fully paid or setisfactorily accounted and that all plains from subcontractors and others for
H337. The Contractor represents that all work has now been accomplished and the Contract is complete. The Contractor warrants and certifies that all of its indebtedness arising by reason of the Contract
The Contractor warrants and certifies that all of its indebtedness arising by reason of the Contract
· · · · · · · · · · · · · · · · · · ·
has been fully paid or satisfactorily secured; and that all claims from subcontractors and others for abor and material used in accomplishing the project, as well as all other claims arising from the performance of the Contract, have been fully paid or satisfactorily settled. The Contractor agrees that, if any claim should hereafter arise, it shall assume responsibility for it immediately upon request to do so by the City of Ann Arbor.
The Contractor, for valuable consideration received, does further waive, release and relinquish any
and all claims or right of lien which the Contractor now has or may acquire upon the subject
premises for labor and material used in the project owned by the City of Ann Arbor.
This affidavit is freely and voluntarily given with full knowledge of the facts.
Contractor Date
Ву
(Signature)
ts
(Title of Office)
Subscribed and sworn to before me, on this day of, 20 County, Michigan
Notary Public
County, MI My commission expires on:

STANDARD SPECIFICATIONS

All work under this contract shall be performed in accordance with the Public Services Department Standard Specifications in effect at the date of availability of the contract documents stipulated in the Advertisement. All work under this Contract which is not included in these Standard Specifications, or which is performed using modifications to these Standard Specifications, shall be performed in accordance with the Detailed Specifications included in these contract documents.

A copy of the Public Services Department Standard Specifications may be purchased from the Engineering Division, (Fourth Floor, City Hall, Ann Arbor, Michigan), for \$35.00 per copy. In addition, a copy of these Standard Specifications is available for public viewing at the Engineering Division office, for review Monday through Friday between the hours of 8:30 a.m. and 4:00 p.m. Copies of the Standard Specifications can also be downloaded from the web link:

http://www.a2gov.org/government/publicservices/project_management/privatedev/pages/standardspecificationsbook.aspx.



SECTION 01000

GENERAL REQUIREMENTS

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Work under this Contract consists of the replacement of two sanitary manholes, the replacement of 62 lineal feet of sanitary sewer, bypass pumping, and related restoration work.
- B. All work under this Contract shall be completed in accordance with the City of Ann Arbor Public Services Department Standard Specifications, unless otherwise amended within the Detailed Specifications or Contract Drawings.

1.2 WORK SCHEDULE

- A. The CONTRACTOR shall provide a work schedule. The schedule shall be complete and shall show in detail the manner in which he proposes to complete the work under this contract and approximately monthly billing of the Contract. The purpose of the schedule is to assist the OWNER in notifying the public of inconveniences and to anticipate cashflow on the job, and to determine if the CONTRACTOR is reasonably proceeding with the work to assure completion within the specified time.
- B. As a guide in preparing a construction sequence for the most significant portions of the project, the CONTRACTOR shall use the following in addition to the detailed sequence on the plans. All other proposed improvements may be constructed concurrently in accordance with an approved schedule.
 - 1. Exploration and coordination of existing utilities.
 - 2. Sawcut and remove existing pavement.
 - 3. Install temporary sanitary bypass.
 - 4. Remove and replace the sanitary manholes and sewer.
 - Perform final restoration activities.

1.3 MATERIAL AND QUALITY CONTROL TESTING

- A. CONTRACTOR shall be responsible for providing, paying for, coordinating and scheduling the services of an independent testing firm (acceptable to OWNER) to perform all materials and compaction testing and related tasks.
- B. Independent testing firm will provide the testing services listed below. Any additional required by the Contract Documents beyond what is listed, shall be provided by the CONTRACTOR.
 - Backfill
 - a. Sieve analysis per source.
 - b. Proctor per source.
 - c. Compaction testing at 400 SF intervals per lift, as required.

- 2. Aggregate Base
 - a. Sieve analysis per source.
 - b. Proctor per source.
 - c. Compaction testing once per 1,000 SF of placement.
- 3. Asphalt Pavement
 - a. Temperature
 - b. Extraction per day.
 - c. Thickness and density once per 1,000 SF of placement.
- 4. Concrete
 - a. Temperature, per 50 CYD.
 - b. Slump, per 50 CYD.
 - c. Air entrainment, per 50 CYD.
 - d. Comprehensive strength, per 50 CYD. Four (4) cylinders each with laboratory testing.
- C. Acceptable testing companies for selection by the CONTRACTOR are:
 - 1. CTI (Brighton, Michigan; Telephone: (248) 486-5100)
 - 2. SME (Plymouth, Michigan; Telephone: (734) 454-9900)
 - 3. PSI (Plymouth, Michigan; Telephone: (734) 453-7900)
 - 4. TEC (Ann Arbor, Michigan; Telephone: (734) 623-0400)

1.4 COORDINATION AND COOPERATION WITH OTHERS

- A. The Contractor is reminded as to the requirements of article 104.07 of the 2012 edition of the MDOT Standard Specifications, "Cooperation by the Contractor." The Contractor shall directly coordinate his/her work with individual City Departments/Divisions/Units.
- B. The following Utility Owners may have overhead and/or underground facilities located within the Right-of-Way:
 - 1. The City of Ann Arbor
 - 2. DTE MichCon (Michigan Consolidated Gas Company)
 - 3. DTE Edison (Detroit Edison Company)
 - 4. SBC (AT&T)
 - Comcast
 - 6. MCI Communications
 - 7. Sprint Communications
 - 8. The University of Michigan

1.5 PROTECTION OF EXISTING UTILITIES

A. Damages to utilities by the Contractor's operations shall be repaired by the utility owner at the Contractor's expense. Delays to the work due to utility repairs are the sole responsibility of the Contractor. The Contractor shall keep construction debris out of utilities at all times. The Contractor shall be back charged an amount of \$50.00 per day for each manhole/inlet/utility pipe that contains construction debris caused as a result of the Contractor's (including subcontractors and suppliers) work. The Contractor is solely responsible for any damages to the utilities or abutting properties due to construction debris.

- B. Certain sanitary and storm sewers within the influence of construction may have been cleaned and videotaped prior to construction. The City may also choose to videotape utility line(s) during or after the work of this Contract to inspect them for damages and/or construction debris. If such inspection shows damage and/or debris, then all costs of such inspection, cleaning, repairs, etc, shall be the Contractor's sole responsibility. If such inspection is negative, the City will be responsible for the costs of such inspection.
- C. Costs for this work will not be paid for separately, but shall be included in the bid price of the Contract Item "General Conditions."

1.6 CONSTRUCTION STAKING

A. The CONTRACTOR will be required to contact the ENGINEER for staking 48 hours in advance of necessary staking. The ENGINEER will provide construction staking, in accordance with the GENERAL CONDITIONS for the complete project only one time. Any and all stakes that are destroyed or tampered with after staking are to be replaced at the CONTRACTORS expense.

1.7 AUDIOVISUAL TAPE COVERAGE

- A. The CONTRACTOR shall furnish to the OWNER, an audio-video DVD recording for all areas proposed for improvement.
- B. The audio-video recording shall be DVD and of such quality to accurately describe the existing conditions. The DVD shall be produced one (1) week prior to the placement of materials or equipment in the construction area. The DVD shall be of commercial quality and of size commonly used.
- C. Both sides of the entire area must be recorded with the rate of speed less than 48 ft per minute. Camera functions such as panning rate; zoom-in/zoom-out shall be controlled to provide optimum object clarity.
- D. The DVD must be recorded while the visibility is clear and at no time will it be allowed during periods of ground cover.
- E. The DVD shall be continuous running and shall include date, time, and location at appropriate intervals. The location shall be easily referenced to the Contract Drawings.
- F. The audiovisual tape shall be paid on a lump sum basis and shall include all labor, equipment, and materials required to perform the filming and to provide the finished videotape the Engineer. The unit price includes filming the entire project limits, for each and every street, as described above.

1.8 GENERAL CONDITIONS, INSURANCE, BONDS, & MOBILIZATION

- A. This pay item shall include all work described and required by the Plans and Specifications for which no item of work is listed in the Bid Form, including but not limited to:
 - 1. Scheduling and organization of all work, subcontractors, suppliers, testing, inspection, surveying, and staking.
 - 2. Coordination of, and cooperation with, other contractors, agencies, departments, and utilities.

- 3. Protection and maintenance of Utilities.
- 4. Maintaining drainage.
- 5. Maintaining driveways drive openings, sidewalks, bike paths, mail or other deliveries, and solid waste/recycle pick-ups. This includes the placement and maintenance of gravel in driveway openings as directed by the Engineer.
- 6. Storing all materials and equipment off lawn areas.
- 7. Temporary relocation and final replacement/re-setting of mailboxes.
- 8. Site clean-up.
- 9. Coordination efforts to furnish various HMA mixtures as directed by the Engineer.
- 10. Coordination efforts to furnish and operate various-size vehicles/equipment as directed by the Engineer.
- 11. Furnishing and operating vacuum-type street cleaning equipment a minimum of once per week or more frequently as directed by the Engineer.
- 12. Furnishing and operating vacuum-type utility structure cleaning equipment.
- 13. Furnishing and operating both vibratory plate and pneumatic-type ("pogo-stick") compactors.
- 14. Furnishing and operating a backhoe during all work activities.
- 15. Furnishing and operating a jackhammer and air compressor during all work activities.
- 16. Noise and dust control.
- 17. Mobilization(s) and demobilization(s).
- 18. Furnishing submittals and certifications for materials and supplies.
- 19. Disposing of excavated materials and debris The Contractor shall dispose of, at the Contractor's expense, all excavated material. Costs for this work will not be paid for separately.
- 20. Independent material testing.
- 21. All miscellaneous and incidental items such as overhead, bonds, insurance, and permits.
- B. This item of work will be paid for on a pro rata basis at the time of each progress payment. Measurement will be based on the ratio between work completed during the payment period and the total contract amount. When all of the work of this Contract has been completed, the measurement of this item shall be 1.0 Lump Sum, minus any deductions incurred for inadequate performance as described herein. This amount will not be increased for any reason, including extensions of time, extras, and/or additional work.

1.9 SOIL EROSION CONTROL

- A. The Contractor shall furnish, place, maintain and remove soil erosion and sedimentation control measures, including but not limited to, silt fence, tree protection fence, inlet filters at all drainage structures, all in accordance with all applicable City (and other governmental agencies) codes and standards, as directed by the Engineer, as detailed in the Standard Specifications, and as shown on the Plans.
- B. Soil erosion control shall be paid on a lump sum basis and shall include all labor, equipment, and materials required to perform the work as described above and as required on the plans. This item of work will be paid for on a pro rata basis at the time of each progress payment. Measurement will be based on the ratio between work completed during the payment period and the total contract amount. When all of the work of this Contract has been completed, the measurement of this item shall be 1.0 Lump Sum, minus any deductions incurred for inadequate performance as described herein.

1.10 CLEAN-UP & RESTORATION

- A. This item of work shall conform to Division IX, Section II, Item No. 891, Clean-Up & Restoration of the Public Services Area Standard Specifications, except as specified herein.
- B. This work shall include the removal of all surplus materials from the site including; but not limited to; tools, dirt, rubbish, construction debris, and excess excavated material. This work shall also include the restoration of all existing lawn areas, road surfaces, culverts, drives, and sidewalks disturbed by the work. This work includes placing topsoil, fertilizer, seeding, and furnishing and installing mulch blankets on all disturbed areas as approved by the Engineer. Mulch blankets are required on all seeded areas.
- C. It is the responsibility of the Contractor to establish a dense lawn of permanent grasses, free from mounds and depressions prior to final acceptance and payment of this project. Any portion of a seeded area that fails to show a uniform germination shall be reseeded. Such reseeding shall be at the Contractor's expense and shall continue until a dense lawn is established. The Contractor is responsible for restoring all areas disturbed by his construction.
- D. The Contractor shall maintain all lawn areas until they have been accepted by the Engineer. Lawn maintenance shall begin immediately after the grass seed is in place and continue until final acceptance with the following requirements: Lawns shall be protected and maintained by watering, mowing, and reseeding as necessary, until the period of time when the final acceptance and payment is made by the Engineer for the project, to establish a uniform, weed-free, stand of the specified grasses. Maintenance includes furnishing and installing additional topsoil, and reseeding all as may be required to correct all settlement and erosion until the date of final acceptance.
- E. Damage to seeded areas resulting from erosion shall be repaired by the Contractor at the Contractor's expense. Scattered bare spots in seeded areas will not be allowed over three (3) percent of the area nor greater than 6"x 6" in size. When the above requirements have been fulfilled, the Engineer will accept the lawn.
- F. Measurement and payment for this item of work shall conform to Division IX, Section 2, Item No. 891, Clean-Up & Restoration of the Public Services Area Standard Specifications except as modified herein.

G. The completed work for "Clean-up and Restoration" will be paid for on a lump sum (LS) basis. 80% of said lump sum shall be paid upon completion and approval of the site by the Engineer. By May 31st of the year following the completion of the project, the Engineer will inspect the seeded turf to ensure that the end product is well established; weed free, and in a growing and vibrant condition. If the Engineer determines that the restored areas meet the project requirements, the remaining 20% of the lump sum will be paid. If the Engineer determines that the restored areas do not meet the project requirements, the Contractor will continue with any and all measures necessary to meet the project requirements. All costs associated with the remedial measures shall be borne entirely by the Contractor.

PART 2 - PRODUCTS

2.1 CLEAN-UP & RESTORATION

- A. The materials shall meet the requirements specified in the MDOT 2012 Standard Specifications as designated, as specified herein, and as approved by the Engineer:
 - 1. Seed shall be THM seed mixture as described in Table 8 16-1.
 - 2. Fertilizers shall be a Class A. The percentages by weight shall be 12- 12- 12, or as approved by the Engineer.
 - 3. Water used shall be obtained from fresh water sources and shall be free from injurious chemicals and other toxic substances.
 - Mulch blankets shall be High Velocity Straw Mulch Blankets as specified in MDOT section 917.

PART 3 - EXECUTION

NOT USED

END OF SECTION

SECTION 01550

TRAFFIC CONTROL

PART 1 - GENERAL

1.1 SUMMARY

- A. Traffic shall be maintained in accordance with the City of Ann Arbor Public Services Department Standard Specifications except as specified in Sections 103.05, 810, 812, 919, and 920 of the Michigan Department of Transportation (MDOT), 2012 Standard Specifications for Construction, the 2005 Michigan Manual of Uniform Traffic Control Devices (MMUTCD) and as amended herein.
- B. The Contractor shall furnish, erect, maintain and, upon completion of the work, remove all traffic control devices and barricade lights within the project and around the perimeter of the project for the safety and protection of local traffic. This includes, but is not limited to, advance, regulatory, and warning signs; barricades and channeling devices at intersecting streets on which traffic is to be maintained; barricades at the ends of the project and at right-of-way lines of intersecting streets, and moving traffic control devices for construction operations.

1.2 SUBMITTALS

- A. The CONTRACTOR shall provide the ENGINEER with a Maintenance of Traffic Plan for approval thirty (30) days prior to the closure of any lanes or streets.
- B. The CONTRACTOR shall submit all necessary Maintenance of Traffic Plans to the City of Ann Arbor. The CONTRACTOR shall be responsible for producing all required plans.

1.3 MEASUREMENT AND PAYMENT PROCEDURES

- A. This item of work will be paid for on a pro rata basis at the time of each progress payment. Measurement will be based on the ratio between work completed during the payment period and the total contract amount. When all of the work of this Contract has been completed, the measurement of this item shall be 1.0 Lump Sum, minus any deductions incurred for inadequate performance as described herein. This amount will not be increased for any reason, including extensions of time, extras, and/or additional work.
- B. The completed work as measured for this item of work will be paid for at the Contract Unit Price for the "Traffic Control" Pay Item.
- C. The unit price for this item of work shall include all labor, material, and equipment costs to perform all the work specified in the City Standard Specifications and as modified by this Detailed Specification.

PART 2 - PRODUCTS

2.1 TEMPORARY TRAFFIC CONTROL MATERIALS

A. The materials and equipment shall meet the requirements specified in the corresponding sections of the MDOT 2012 Standard Specifications for Construction and the 2005 Michigan Manual of Uniform Traffic Control Devices (MMUTCD).

B. Lighted plastic drum barricades meeting current MDOT and MMUTCD specifications shall be used on this project as Type II Barricades.

PART 3 - EXECUTION

3.1 TRAFFIC CONTROL

- A. Plans are provided that detail half-width closure of a 70 foot section of Eighth Street. Trenches in the road are to be barricaded with temporary concrete barriers or portable water filled barrier per NCHRP 350, TL-2 or as approved by the Engineer.
- B. The CONTRACTOR shall provide all required Type II and Type III barricades, flashers, flashing arrows, flaggers, and all signing required to properly and safely maintain traffic flow through the construction area in accordance with the Michigan Manual of Uniform Traffic Control Devices. The CONTRACTOR shall provide as many signs and barricades as required by the ENGINEER to protect and maintain traffic through this area at all times. The CONTRACTOR shall add any additional devices required by the ENGINEER to provide a smooth flow of traffic.
- C. Driveways shall not be blocked for extended periods of time unless arrangements can be made with the affected property owner(s). When it becomes necessary to temporarily block driveways, the Contractor shall notify the affected property owners in advance to coordinate the work and allow sufficient time for vehicles to vacate from properties. It may be necessary to allow for vehicles to temporarily park in the roadway at locations that do not interfere with the Contractor's work. During these periods the owners of the respective vehicles must be available to, with proper notice, move their vehicles if it becomes necessary to accommodate the work.
- D. The CONTRACTOR shall provide all dust control and other means to reduce dust during construction. The CONTRACTOR shall grade and maintain the area of the road being used as traveling surface for the through, as well as the local traffic. Grading of the road and application of dust control measures shall be made on a weekly basis at minimum, or as often as required by the ENGINEER.
- E. Mailboxes and newspaper boxes that are in the way of the construction shall be removed and reset immediately in a temporary location approved by the Engineer. Mail and paper delivery shall not be interrupted during the construction. Upon completion of the construction, all mailboxes and newspaper boxes, including their supports, shall be repositioned in their permanent locations as approved by the Engineer.
- F. The work of maintaining and relocating existing warning, regulatory and/or guide signs; and of removing, salvaging and reinstalling existing signs and supports is included in the bid price for the contract pay item "Traffic Control."
- G. In the event of the CONTRACTOR's failure to comply with these provisions, the OWNER may with or without notice, cause the same to be done; and will deduct the cost of such work from any money due or to become due the CONTRACTOR under this contract, but the performance of such work by the OWNER or at his insistence, shall serve in no way to release the CONTRACTOR from his general or particular liability for the safety of the Public or the work.

3.2 STREET SWEEPING

A. All open streets upon which construction activities have occurred shall be broom cleaned at the end of each workday. These construction activities include, but are not limited to,

deliveries, hauling, and equipment transport. Large pieces of debris shall be removed immediately.

END OF SECTION

SECTION 02240

DEWATERING

PART 1 - GENERAL

1.1 DESCRIPTION

- A. If necessary, the CONTRACTOR shall supply all labor, materials, tools and equipment required to lower and control the groundwater levels and hydrostatic pressures to permit all excavation and construction specified under this contract to be performed in the dry. The control of all ice, snow and surface water shall be considered as part of the work under this Section
- B. The work under this Section shall include all costs of mobilization, supply, installation, operation, maintenance, supervision, and final dismantling and removal from the site of any and all dewatering equipment. The work under this Section shall be incidental to piping and manhole construction costs.
- C. The CONTRACTOR or his dewatering subcontractor shall be currently and appropriately licensed by the State of Michigan to undertake the work covered under this Section and shall submit such information to the ENGINEER.

1.2 SUBMITTALS

- A. The CONTRACTOR shall submit complete plans and description of the overall dewatering sys-tem he proposed to use for the work under this Section for review by the ENGINEER, showing the details of the dewatering system prior to initiation of any excavation within 3 feet of the prevailing groundwater levels.
- B. Review by the ENGINEER of the dewatering system proposed by the CONTRACTOR will be only with respect to the basic principles of the methods the CONTRACTOR intends to employ. Review by the ENGINEER of the dewatering system will be based on the demonstrated performance of the system to satisfy the requirements for dewatering as specified herein.

1.3 SITE CONDITIONS

A. The CONTRACTOR shall take all the steps that he considers necessary to familiarize himself with the site conditions, the ground conditions and the groundwater conditions. Copies of the logs of the borings and a soils report are among the data available and a part of these Contract Documents. The data described above is furnished for information only, and it shall be expressly understood that the OWNER and/or the ENGINEER will not be held responsible for any interpretation or conclusions drawn therefrom by the CONTRACTOR.

PART 2 - PRODUCTS

NOT USED

PART 3 - EXECUTION

3.1 GENERAL

- A. It is the intent of this Section that an adequate dewatering system shall be installed to lower and control the groundwater in order to permit excavation, grading, construction of the structures and the placement of the fill materials, all to be performed under dry conditions. The dewatering system shall be adequate to pre-drain the water-bearing strata above and below the bottom of the structure foundations, the drains, the sewers and all other excavations. In addition, the system to be used shall reduce the hydrostatic head in the water-bearing strata below the structure foundations, the drains, sewers, and all other excavations to the extent that the water level and piezometric water levels in the construction area are substantially a minimum of 3 feet below the prevailing excavation surface at all times. Appropriate screens and filters shall be used to prevent loss of soil through the dewatering equipment.
- B. Prior to any excavation below the groundwater level, the dewatering system shall be placed into operation to lower the water levels as required and shall be operated continuously 24 hrs. per day, 7 days per week until all drains, sewers and structures have been satisfactorily constructed including placement of fill materials and no longer requiring dewatering. An adequate weight of fill material or of structure shall be in place to prevent buoyancy or flotation prior to discontinuing operation of the dewatering system.
- C. The CONTRACTOR shall obtain written approval from the ENGINEER before discontinuing the operation of the dewatering system.
- D. The CONTRACTOR shall be solely responsible for the arrangement, location and depths of the dewatering system necessary to accomplish the work described under this Section. The dewatering shall be accomplished in a manner that will reduce the hydrostatic head below any excavation to the extent that the water level and piezometric water levels in the construction area are substantially a minimum of 3 feet below the prevailing excavation surface, will prevent the loss of fines, seepage, boils, quick conditions or softening of the foundation strata, will maintain stability of the sides and bottom of the excavation and will result in all construction operations being performed in the dry.
- E. The control of all surface and subsurface water, ice and snow is considered as part of the dewatering requirements. The control shall be adequate such that the stability of excavated and constructed slopes are not adversely affected by water, that erosion is controlled, and that flooding of excavations or damage to the existing and/or new structures or portions thereof does not occur. Surface water or roof runoff shall not be directed toward the excavations.
- F. The CONTRACTOR shall dispose of all water removed from the excavations in such a manner as will not endanger public health, property, any portion of the work under construction or completed either by him or any other CONTRACTOR, shall not recharge the water bearing strata and shall be performed in such a manner as will cause no inconvenience whatsoever to the OWNER, ENGINEER, or to others engaged on work about the site. Water shall be conveyed in conduits or open water channels to avoid erosion in foundation areas. However, open channels adjacent to existing footings shall not be permitted.

- G. The CONTRACTOR shall provide complete standby equipment, installed and available, for immediate operation as may be required, to adequately maintain dewatering on a continuous basis in the event that all or any part of the dewatering system may become inadequate or fail.
- H. If the dewatering requirements are not satisfied due to inadequacy or failure of the dewatering system, loosening of the foundation strata or instability of the slopes or damage to the foundations or structures may occur. The supply of all labor, materials and plant, and the performance of all work necessary to carry out any necessary additional work for the reinstatement of the structures or the foundations soils resulting from such inadequacy or failure shall be undertaken by the CONTRACTOR subject to the approval of the ENGINEER and at no additional expense to the OWNER.

3.2 OBSERVATION WELLS

- A. If site conditions necessitate, the CONTRACTOR shall supply, install, take measurements and maintain the observation wells (piezometers) at various locations near existing structures to insure complete drawdown.
- B. The observation wells shall be of a suitable design proposed by the CONTRACTOR and as reviewed by the ENGINEER.
- C. The CONTRACTOR shall be responsible for installing and maintaining all observation wells and observing and recording the elevation of the groundwater and piezometric water levels in all the observation wells daily. A record of the information obtained shall be given to the ENGINEER each day. The CONTRACTOR shall also permit the ENGINEER to make his own observations. Any observation well that becomes inactive, damaged or destroyed shall be replaced within 24 hrs by the CONTRACTOR at no additional expense to the OWNER. If an observation well becomes inactive, damaged, or destroyed, and if in the opinion of the ENGINEER the observations from that observation well are critical, further excavation shall be suspended at the discretion of the ENGINEER and at no additional expense to the OWNER. Excavation shall not recommence until that observation well is repaired or replaced to the satisfaction of the ENGINEER and reliable observations can be obtained from that well or its replacement well.
- D. The CONTRACTOR shall demonstrate by adding or removing water from all observation well risers that the observation wells are functioning properly.
- E. All observation wells shall be satisfactorily installed and proven to be functioning properly prior to commencement of dewatering in any section of the site.

3.3 CONTROL OF GROUNDWATER LEVELS

A. The observation wells and test pits or holes shall be used as a primary basis of determining compliance with the requirements of this Section.

3.4 REMOVAL OF SYSTEM(S)

A. After all requirements of this Section are met, the CONTRACTOR shall remove all materials and equipment used during this operation. All holes, wells, and pits shall be filled immediately with suitable material.

END OF SECTION

SECTION 02700

PAVEMENT AND WALKS

PART 1 - GENERAL

1.1 SUMMARY

A. All HMA pavement, concrete pavement, curb & gutter, and sidewalks shall be installed in accordance with the City of Ann Arbor Public Services Department Standard Specifications except as amended herein.

1.2 MEASUREMENT AND PAYMENT PROCEDURES

- A. All HMA paving items shall be by the ton, in place. Unused portions of material loads shall be returned to the plant and re-weighed, and the corrected weight slip shall be provided to the Engineer. All weight slips must include the type of mixture (codes are not acceptable), as well as vehicle number, gross weight, tare weight and net weight. The unit prices for these items of work shall include all labor, material, and equipment costs to perform all the work specified in the City Standard Specifications and as modified by this Detailed Specification.
- B. All costs for furnishing and operating vacuum-type street cleaning equipment, backhoes, jackhammers, and air compressors shall be included in the bid prices for these items of work or in the item of work "General Conditions."
- C. Measurement of these HMA paving items shall be by the ton, in place. Unused portions of material loads shall be returned to the plant and re-weighed, and the corrected weight slip shall be provided to the Engineer. All weight slips must include the type of mixture (codes are not acceptable), as well as vehicle number, gross weight, tare weight and net weight.

PART 2 - PRODUCTS

2.1 SUBBASE

A. Subbase shall meet the requirements of MDOT Section 902, Class II material.

2.2 AGGREGATE BASE COURSE

A. Aggregate shall meet the requirements of MDOT Section 902, 21AA limestone aggregate.

2.3 HMA BASE AND LEVELING

A. HMA leveling course shall meet the requirements of MDOT Section 501, for HMA mixture 13A, PG 58-28 with maximum application rate of 220 lb/syd.

2.4 HMA SURFACE

A. HMA surface course shall meet the requirements of MDOT Section 501 for HMA mixture 13A, PG 58-28 with maximum application rate of 220 lbs/syd.

2.6 PRIME AND BOND COATS

A. Prime and bond coats shall meet the requirements of MDOT Section 904.

2.9 CONCRETE CURB AND GUTTER

A. Concrete curb and gutter shall meet the requirements of MDOT Section 802. Concrete shall be Grade P1 unless otherwise indicated on the plans for Grade HE.

PART 3 - EXECUTION

3.1 HMA PAVEMENT REMOVAL

- A. This work shall consist of removing HMA surface/base as described in the City of Ann Arbor Standard Specifications, except as modified herein, and as directed by the Engineer.
- B. In areas where HMA pavement removal is to be performed adjacent to existing HMA pavement that is to remain, the pavement shall be saw cut prior to removal. Backhoe teeth, jackhammers equipped with spike points, milling machines, and backhoe mounted wheel cutters shall not be used. Damage to adjacent pavement, pavement base, subbase, curb, gutter, sidewalk, utility structures, or other site features, due to removal operations shall be repaired by the Contractor, at the Contractor's expense, as directed by the Engineer.
- C. The Contractor shall remove pavement and pavement base to a minimum depth of 12-inches below existing grade. Removal of all material located within the 12-inch minimum thickness is included in this item of work. Any additional aggregate or clay base removed without written approval of the Engineer shall be replaced by the Contractor at the Contractor's expense with 21AA Aggregate compacted-in-place, or with HMA asphalt, as directed by the Engineer.
- D. The areas to be removed shall be marked and measured prior to the removal of any material. Measurement shall take place with both the Engineer and the Contractor (or their agents) present. Both parties shall come to an agreement regarding removal quantities prior to the actual removal of HMA pavement.

3.2 HMA PAVEMENT

- A. All concrete work shall be completed prior to placing HMA mixtures.
- B. The Contractor shall have a 10-foot long straight-edge, backhoe, air-compressor and jackhammer available during all paving operations.
- C. MDOT SS-1h bond coat shall be applied at a uniform rate of 0.05 gallons/square yard, on all exposed, existing HMA and concrete surfaces which will come in contact with the new HMA material. The Contractor shall take extra care to avoid covering surfaces which are not to be paved. After September 15, SS-1h bond coat shall not be diluted by more than 25%.
- D. The Contractor shall place HMA wedges using the leveling and wearing mixtures specified herein, as directed by the Engineer, prior to placing the wearing course. Such wedging shall be measured and paid for at the respective unit price of the appropriate HMA Pavement item

- E. Construction of butt joints, where directed by the Engineer, shall be measured and paid for as "Remove HMA Pavement."
- F. The Contractor shall schedule the paving operation to avoid longitudinal cold joints.
- G. HMA wearing and leveling courses shall be placed in lifts of 2-inches or less; base courses shall be placed in lifts of 3-inches or less.
- H. All specified HMA thickness dimensions are compacted-in-place.
- I. The Contractor shall construct the pavement courses to provide the final cross-slopes (crowns) specified by the Engineer.
- J. The Contractor shall construct feather joints, and shall feather the leveling and wearing courses at structures, in drive approaches, and at intersection joints, as directed by the Engineer. Feather joints shall vary the thickness of the asphalt from 0.0-inches to the required full paving thickness (approximately 1½-inches) over a 5-foot to 15-foot distance, or as directed by the Engineer. The Contractor shall rake all large aggregates out of the HMA mixture in feather joints, prior to compaction.
- K. The Contractor shall provide a minimum of two rakers during the placement of all wearing and leveling courses. Further, the Contractor shall provide, when directed by the Engineer, a second "Break-Down" roller in order to achieve the specified asphalt densities.
- L. The Contractor shall provide a minimum of 24-hours notice to the Engineer prior to paving, and shall obtain a "Permit To Pave" from the Engineer in advance of scheduling paving.
- M. The Contractor and Engineer shall carefully observe the paving operation for signs of faulty mixtures. Points of weakness in the surface shall be removed or corrected by the Contractor, at his/her expense, prior to paving subsequent lifts of HMA material. Such corrective action may include the removal and replacement of thin or contaminated sections of pavement, including sections that are weak or unstable. Once the Contractor or his representative is notified by the Engineer that the material being placed is out of allowable tolerances, or there is a problem with the paving operation, the Contractor shall stop the paving operation at once, and shall not be permitted to continue placing HMA material until again authorized by the Engineer.
- N. During the placement of leveling and wearing courses, the speed of the paving machine(s) shall not exceed 50-feet per minute.
- O. The Contractor shall furnish and operate enough materials and equipment so as to keep the paving machine(s) moving continuously at all times. Failure to do so shall be cause for the suspension of the paving operation until the Contractor can demonstrate to the satisfaction of the Engineer, that sufficient resources have been dedicated to perform the work in accordance with the specifications.
- P. The Contractor shall use an asphalt paver or spreader box to place HMA mixtures. The Contractor shall not use a grader, front-end loader or any similar device to place HMA mixtures. For small areas, where approved by the Engineer, the Contractor may place the material by hand directly into patch areas. The Contractor shall not place HMA materials on adjacent pavement surfaces.

- Q. Each layer of HMA mixture shall be compacted to between 92 to 96 percent (or as determined acceptable by the engineer) of the theoretical maximum density, as listed on the approved Job Mix Formula.
- R. Corrective action shall be enforced as described at Division 5 of the 2012 MDOT Standard Specifications and will be based on the City's testing reports.

3.3 CONCRETE CURB AND GUTTER

A. This work shall consist of constructing concrete curb and gutter in accordance with Sections 601, 602, and 802 of the 2012 edition of the MDOT except as specified herein, as shown on the Plans, as shown in this Detailed Specification, and as directed by the Engineer.

3.4 PRIME COAT

A. Prime coat shall be applied on a prepared aggregate base at a rate of 0.25 gallons per square yard.

3.5 BOND COAT

A. Bond coat shall be applied to an asphalt base course at a rate of 0.10 gallons per square yard.

END OF SECTION

Appendix A

Soil Borings



March 26, 2014

Ms. Tanya Sullivan, PE Stantec 3754 Ranchero Drive Ann Arbor, Michigan 48108

Re: Letter of Geotechnical Investigation

8th Street Sanitary Sewer Manhole Replacement

Ann Arbor, Michigan G2 Project No. 143024

Dear Ms. Sullivan:

We have completed the geotechnical investigation for the proposed 8th Street Sanitary Sewer Manhole Replacement in Ann Arbor, Michigan. The purpose of the geotechnical exploration is to evaluate the general subsurface conditions within area of the proposed replacement manhole, determine the subsurface soil and groundwater conditions, and provide recommendations for manhole construction. We anticipate the manhole replacement will be bear at a depth of 11.7 feet and consist of a 4-foot diameter pre-cast concrete structure.

FIELD OPERATIONS

We performed one soil boring, B-1, within the footprint of the proposed manhole replacement extending to a depth of 15 feet. A G2 representative marked the soil boring location in the field prior to drilling operations. The ground surface elevation was not available at the time of this investigation. The approximate soil boring location is shown on the Soil Boring Location Plan, Plate No. 1.

The soil boring was drilled using truck mounted rotary drilling rig. Continuous flight, 2-1/4-inch inside diameter, hollow-stem augers were used to advance the borehole. Within the soil boring, soil samples were obtained at intervals of 2-1/2 feet within the upper 10 feet and at intervals of 5 feet below that depth. These samples were obtained by the Standard Penetration Test method ASTM D 1586, which involves driving a 2-inch diameter split-spoon sampler into the soil with a 140-pound weight falling 30 inches. The sampler is generally driven three successive 6-inch increments with the number of blows for each increment recorded. The number of blows required to advance the sampler the last 12 inches is termed the Standard Penetration Resistance (N). The blow counts for each 6-inch increment and the resulting N-value are presented on the individual soil boring log.

The soil samples were placed in sealed containers in the field and brought to the laboratory for testing and classification. During drilling operations, the drilling crew maintained logs of the encountered subsurface conditions, including changes in stratigraphy and observed groundwater levels to be used in conjunction with our analysis of the subsurface conditions. The final boring log is based on the field log and laboratory soil classification and test results. After completion of drilling operations, the borehole was backfilled with excavated soil and capped with cold patch.

Geotechnical & Geoenvironmental Engineering Services 1595 Eisenhower Place Ann Arbor, Michigan 48108 734.390.9330 FAX 734.390.9331 March 26, 2014 G2 Project No. 143024 Page 2



LABORATORY TESTING

Representative soil samples were subjected to laboratory testing to determine soil parameters pertinent to utility design and construction. An experienced geotechnical engineer classified the samples in general conformance with the Unified Soil Classification System.

Laboratory testing included moisture contents and unconfined compressive strength determinations. The unconfined compressive strengths were determined by using a spring loaded hand penetrometer. The hand penetrometer estimates the unconfined compressive strength to a maximum of 4-1/2 tons per square foot (tsf) by measuring the resistance of the soil sample to the penetration of a calibrated spring-loaded cylinder.

The results of the moisture content and unconfined compressive strength laboratory tests are indicated on the boring log at the depths the samples were obtained. We will hold the soil samples for 60 days from the date of this report. If you would like the samples, please let us know.

SOIL CONDITIONS

Approximately 4 inches of bituminous concrete underlain by 6 inches of aggregate base are present at the ground surface of the soil boring. Silty clay fill with trace sand and gravel underlies the pavement section and extends to an approximate depth of 9 feet. Native silty sand with trace gravel is present below the silty clay fill soil and extends to an approximate depth of 12 feet. Silty clay is underlies native silty sand and extends to the explored depth of 15 feet.

The silty clay fill is soft to medium in consistency with moisture contents ranging from 20 to 21 percent, and an unconfined compressive strength of 1,000 pounds per square (psf). It should be noted that the high blow counts within the upper 2-1/2 feet was due to frost in the ground and are not indicative of the true strength of the upper silty clay fill. The native silty sand is medium compact in relative density with a Standard Penetration Test (SPT) N-value of 14 blows per foot (bpf). The underlying native clay is stiff in consistency with a moisture content of 22 percent.

The stratification depths shown on the soil boring log represent the soil conditions at the boring location. Variations of the soil conditions may occur away from the soil boring location. We have prepared the boring log on the basis of laboratory classification and testing as well as the field log of the soils encountered. The Soil Boring Location Plan, Plate No. 1, and Soil Boring Log, Figure No. 1 are attached with this letter report. General Notes Terminology defining the nomenclature used on the soil boring logs and elsewhere in this report are presented on Figure No. 2.

GROUNDWATER CONDITIONS

Groundwater observations were performed during and upon completion of the drilling operations. Groundwater was observed within the boring during drilling operations at a depth of 6 feet below existing grade. Upon completion of drilling operations, groundwater was observed at the approximate interface of fill soils and native granular soils at a depth of 9 feet below existing grade.

March 26, 2014 G2 Project No. 143024 Page 3



Fluctuations in perched and long term groundwater levels should be anticipated due to seasonal variations and following periods of prolonged precipitation. It should also be noted that groundwater observations made during drilling operations in predominantly cohesive soils are not necessarily indicative of the static groundwater level. This is due to the low permeability of such soils and the tendency of drilling operations to seal off the natural paths of groundwater flow.

RECOMMENDATIONS

As noted previously, groundwater was observed during drilling operations at a depth of 6 feet and upon completion at 9 feet. To allow for manhole construction in dry conditions, temporary construction dewatering will be required. Given the shallow thickness of the water bearing granular soils, well-point dewatering is not practical. Therefore, groundwater or surface run off should be controlled with normal pumping from properly constructed sumps. Alternatively, sheeting may be designed to extend through the granular strata and into the underlying cohesive soils to cut off groundwater seepage. If this is chosen, sheeting must be designed to resist the side groundwater pressures.

For open-cut excavations, we recommend a maximum slope of 1-1/2 horizontal unit to 1 vertical unit (1-1/2H:1V) for temporary excavations that extend below a depth of 5 feet within the clay fill soils and dewatered medium compact granular soils. Where seepage from excavation cuts is observed, the slopes will need to be flattened sufficiently to achieve stability, but in no case left steeper than 2:1 at and below the seepage level. The tops of the slopes should be barricaded to prevent vehicles and storage loads within 7 feet of the tops of the slopes. The soils exposed in slope faces should be inspected by our personnel so that modifications of the slopes may be made if variations in the soil or water conditions occur.

If sloped excavations are not possible due to access constraints, we recommend utilizing a trench box or driven sheet-pile shoring with internal bracing on adjustable horizontal struts. For design of cantilevered or single row internally braced shoring, we recommend the use of a triangular distribution above the excavation line. The pressure distribution recommended above the groundwater table is in general the equivalent fluid pressure of 45 pounds per square foot per foot. For excavations that extend below the groundwater table, we recommend that the equivalent fluid pressure be increased to 85 pounds per square foot.

All excavations should be safely sheeted, shored, sloped, or braced in accordance with MI-OSHA requirements. If material is stored or equipment is operated near an excavation, stronger shoring must be used to resist the extra pressure due to the superimposed loads. Care should always be exercised when excavating near existing roadways or utilities to avoid undermining. In no case should excavations extend below the level of adjacent existing structures unless underpinning is planned.

March 26, 2014 G2 Project No. 143024 Page 4



Jason B. Stoops, P.E.

Project Manager

We appreciate the opportunity to be of service to you and look forward to discussing the soil conditions presented herein. In the meantime, if you have any questions regarding this report or any other matter pertaining to the project, please call us.

Sincerely,

G2 Consulting Group, LLC

Michael G. Dagher, E.I.T.


Staff Engineer

MGD/JBS/ljv

Enclosures: Soil Boring Location Plan, Plate No. 1

Soil Boring Logs, Figure No. 1

General Notes Terminology, Figure No. 2





Legend

Soil Boring Performed by Strata Drilling on March 14, 2014

1992

Soil Boring Location Plan

8th Street Sanitary Sewer Manhole Replacement Ann Arbor, MI



Imagery Date: 5/9/2010 42°16'46.09" N 83°45'35.33" W elev 825 ft eye alt 1469 ft

Drawn by: MGD

Date: 03/10/14 Plate
Scale: NTS No. 1

Project Name: 8th Street Sanitary Sewer Manhole

Project Location: 8th Street

Ann Arbor, Michigan 48103

G2 Project No. 143024

Latitude: N/A Longitude: N/A



SUBSURFACE PROFILE SOIL SAMPLE I			PLE DAT	E DATA						
DEPTH (ft)	PRO- FILE	GROUND SURFACE ELEVATION:	N/A	DEPTH (ft)	SAMPLE TYPE-NO.	BLOWS/ 6-INCHES	STD. PEN. RESISTANCE (N)	MOISTURE CONTENT (%)	DRY DENSITY (PCF)	UNCONF. COMP. STR (PSF)
		Bituminous Concrete (4 inches) Aggregate Base (6 inches)	0.3	1			(1.)	(/4)	(101)	(= ==)
		Fill: Dark Gray Silty Clay with trace sand and gravel	2.5	-	S-1	10 9 10	19	20.7		
5		Fill: Soft to Medium Dark Gray Silty Clay with trace sand and gravel		5	S-2 S-3	1 1 2 1 2 3	3	21.2		1000*
10	▼		9.0	10	S-4	2 6 8	14			
		Medium Compact Dark Yellowish Brown Silty Sand with trace gravel	12.0							
		Stiff Gray Silty Clay with trace sand	15.0		S-5	3 4 6	10	22.1		
	-	End of Boring @ 15ft	10.0							
	-									
20	-			20						
	-									
25	-			25						
Total	actor:	15ft March 14, 2014 M. Dagher, EIT Strata Drilling, Inc. B. Sienkiewicz		Water 6 fe upor Notes: Bore	n removal ehole colla	lrilling ope of augers	erations; wet		ired at 9 fe	eet
Drillin 2-1/	ng Method /4 inch insi	: ide diameter hollow stem auger		Excava Bore	Excavation Backfilling Procedure: Borehole backfilled with auger cuttings					
									Гl	gure No.



GENERAL NOTES TERMINOLOGY

Unless otherwise noted, all terms herein refer to the Standard Definitions presented in ASTM 653.

		PARTICLE SIZE	CLASSIFIC	CATION	
Boulders	8	- greater than 12 inches	The major soil constituent is the principal noun, i.e. clay, silt,		
Cobbles		- 3 inches to 12 inches	sand, gravel. The second major soil constituent and other		
Gravel	- Coarse	- 3/4 inches to 3 inches	minor constituents are reported as follows:		
	- Fine	- No. 4 to 3/4 inches			
Sand	- Coarse	- No. 10 to No. 4	Second Major Constituent	Minor Constituent	
	- Medium	- No. 40 to No. 10	(percent by weight)	(percent by weight)	
	- Fine	- No. 200 to No. 40	Trace - 1 to 12%	Trace - 1 to 12%	
Silt		- 0.005mm to 0.074mm	Adjective - 12 to 35%	Little - 12 to 23%	
Clay		- Less than 0.005mm	And - over 35%	Some - 23 to 33%	

COHESIVE SOILS

If clay content is sufficient so that clay dominates soil properties, clay becomes the principal noun with the other major soil constituent as modifier, i.e. sandy clay. Other minor soil constituents may be included in accordance with the classification breakdown for cohesionless soils, i.e. silty clay, trace sand, little gravel.

Unconfined Compressive			
Consistency	Strength (psf)	Approximate Range of (N)	
Very Soft	Below 500	0 - 2	
Soft	500 - 1,000	3 - 4	
Medium	1,000 - 2,000	5 - 8	
Stiff	2,000 - 4,000	9 - 15	
Very Stiff	4,000 - 8,000	16 - 30	
Hard	8,000 - 16,000	31 - 50	
Very Hard	Over 16,000	Over 50	

Consistency of cohesive soils is based upon an evaluation of the observed resistance to deformation under load and not upon the Standard Penetration Resistance (N).

COHESIONLESS SOILS				
Density Classification	Relative Density %	Approximate Range of (N)		
Very Loose	0 - 15	0 - 4		
Loose	16 - 35	5 - 10		
Medium Compact	36 - 65	11 - 30		
Compact	66 - 85	31 - 50		
Very Compact	86 - 100	Over 50		

Relative Density of cohesionless soils is based upon the evaluation of the Standard Penetration Resistance (N), modified as required for depth effects, sampling effects, etc.

SAMPLE DESIGNATIONS

- AS Auger Sample Cuttings directly from auger flight
- BS Bottle or Bag Samples
- S Split Spoon Sample ASTM D 1586
- LS Liner Sample with liner insert 3 inches in length
- ST Shelby Tube sample 3 inch diameter unless otherwise noted
- PS Piston Sample 3 inch diameter unless otherwise noted
- RC Rock Core NX core unless otherwise noted

STANDARD PENETRATION TEST (ASTM D 1586) - A 2.0 inch outside-diameter, 1-3/8 inch inside-diameter split barrel sampler is driven into undisturbed soil by means of a 140-pound weight falling freely through a vertical distance of 30 inches. The sampler is normally driven three successive 6-inch increments. The total number of blows required for the final 12 inches of penetration is the Standard Penetration Resistance (N).